



Request for Quote

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS
 ONE CAPITOL HILL
 PROVIDENCE RI 02908

BUYER: Mosca, Gary
 PHONE #: 401-574-8124

CREATION DATE : 22-JUN-11
 BID NUMBER: 7448814
 TITLE: REGRADE-REPAIR OF BASEBALL FIELD AT THE KNIGHT CAMPUS - CCRI
 BID CLOSING DATE AND TIME: 19-JUL-2011 02:00:00

**B
I
L
L
T
O**
 CCRI KNIGHT CAMPUS
 400 EAST AVE
 WARWICK, RI 02886-1807
 US

**S
H
I
P
T
O**
 CCRI CONTROLLER'S OFFICE
 ACCOUNTS PAYABLE
 400 EAST AVENUE
 WARWICK, RI 02886
 US

Requisition Number: 1222198

Note to Bidders: THERE WILL BE A PE BID CONFERENCE HELD JULY 8TH 2011 @ 9:00 AM
 LOCATION: CCRI-KNIGHT CAMPUS
 400 EAST AVE
 WARWICK RI

TO DUE TIME RESTRAINTS CONCERNING THIS BID QUESTION PERIOD WILL END ON JULY 11TH 2011 AT THE ADJOURNMENT OF PRE BID CONFERENCE.

Line	Description	Quantity	Unit	Unit Price	Total
1	REGRADE - REPAIR OF BASEBALL OUTFIELD @ THE KNIGHT CAMPUS OF CCRI	1 00	Each		
2	REMEDIAION/UPGRADE BASEBALL INFIELD @ THE KNIGHT CAMPUS OF CCRI	1 00	Each		
3	IRRIGATION WORK ON IN-FIELD	1 00	Each		
4	IRRIGATION WORK IN OUT-FIELD HOURLY RATE NORMAL BUSINESS HOURS (7:30AM-3:30PM) WEEK DAYS @ \$ _____/HR HOURLY RATE OVERTIME HOURS (AFTER 3:30PM WEEK DAYS AND WEEKEND HOURS) @\$ _____HR PARTS FOR REPAIRS TO BE PROVIDED AT A DICOUNT OFF LIST PRICE _____%	1 00	Each		

Delivery: _____

Terms of Payment: _____

It is the Vendor's responsibility to check and download any and all addenda from the RIVIP This offer may not be considered unless a signed RIVIP generated Bidder Certification Cover Form is attached and the Unit Price column is completed The signed Certification Cover Form must be attached to the front of the offer

LINE ONE

REGRADE - REPAIR OF BASEBALL OUTFIELD @ THE KNIGHT CAMPUS OF CCRI TO INCLUDE BUT NOT BE LIMITED TO THE FOLLOWING:

VENDOR TO SUPPLY ALL LABOR, MATERIAL AND EQUIPMENT NEEDED

SCOPE OF WORK

1. REMOVE AND CAP ALL EXISTING IRRIGATION HEADS PRIOR TO CONSTRUCTION
2. SOD HARVEST GRASS OFF THE ENTIRE PLAYING FIELD SOD WILL BE REMOVED FROM FIELD USING LOW GROUND PRESSURE MACHINES AND STOCKPILED IN PARKING LOT. MATERIALS WILL THEN BE LOADED INTO TRUCKS AND TRANSPORTED TO AN OFF SITE LOCATION.
3. ROTO TILL 85,000 SQ. FT. TO THE DEPTH OF 8" USING A BLECAVATOR SOIL PROCESSOR TO BREAK UP ANY ORGANIC MATTER, SUCH AS ROOTS AND THATCH, FROM THE SOIL PROFILE.
4. ROUGH GRADE EXISTING SOILS USING A LOW GROUND PRESSURE (LOP) BULL DOZER WITH LASER TO CORRECT LARGE GRADING PROBLEMS
5. SUPPLY AND INSTALL 700 LINEAR FT. OF 6" ADS PERFORATED PIPE. THE PIPE WILL RUN ALONG THE OUTFIELD FENCE, AND COLLECT WATER SHEDDING DOWN THE SLOPE OF THE FIELD. WATER WILL THEN DISCHARGE INTO EXISTING RUN OFF AREAS BEHIND THE OUTFIELD FENCE. IN ADDITION TO THE SUB-SURFACE DRAINAGE, THERE WILL BE SIX (6) SURFACE DRAINS LOCATED IN STRATEGIC AREAS TO COLLECT ANY SURFACE WATER THAT MIGHT ACCUMULATE, RELIEVE GASES IN THE SOIL BY MOVING AIR THROUGH VENTED CAPS AND PROVIDE AN OPENING FOR CLEANING PIPES.
6. ALL TRENCHES WILL BE EQUIPPED WITH FILTER FABRIC ON THE BOTTOM AND THE SIDES OF THE TRENCH TO INSURE THAT THERE WILL BE NO MIGRATION OF MATERIALS INTO THE TRENCH. PIPE WILL ALSO BE EMBEDDED IN A 3/8" NATURAL STONE TO ASSURE THERE WILL BE ADEQUATE WATER MOVEMENT AROUND THE PIPE. 80% SAND 20% SOIL ROOT ZONE MIX WILL COMPLETE THE TRENCH. ROOT ZONE MIX WILL BE AN ENGINEERED BLEND NEEDED TO PROVIDE HIGH INFILTRATION. IT WILL HAVE THE APPROPRIATE SAND STRUCTURE TO ELIMINATE MIGRATION AND SEALING OFF THE DRAINAGE STONE
7. SUPPLY AND INSTALL 624 YARDS 2.5 MM SAND OVER THE ENTIRE SOIL AREA. SAND WILL THEN BE LASER GRADED TO INSURE PROPER THICKNESS OF SAND PRIOR TO PROCESSING
8. FIELD WILL BE BLENDED FOR A SECOND TIME USING A BLECAVATOR SOIL PROCESSOR TO THE DEPTH OF 8". THIS PROCESS WILL CONTINUE UNTIL A HOMOGENEOUS BLEND OF SAND AND SOIL IS PREVALENT.
9. SUPPLY AND INSTALL A FULLY AUTOMATED SUBSURFACE IRRIGATION SYSTEM USING HUNTER 125 STAINLESS STEEL HEADS, SDR 35 PIPE, PVC, SWING JOINTS AND HUNTER ZONE VALVES, WITH MANUAL BRASS VALVE SHUT OFFS. EXISTING MAIN LINE WILL BE USED.

10. POWER RAKE ENTIRE FIELD TO BLEND IN SOIL AMENDMENTS. FERTILIZER, LIME AND AMENDMENTS TO BE DETERMINED BASED ON SOIL ANALYSIS TAKEN PRIOR TO CONSTRUCTION.

11. FINAL GRADING WILL BE DONE WITH LASER GRADER THAT IS FULLY EQUIPPED WITH AUTOMATED CONTROLS CAPABLE OF FINE GRADING TO WITHIN 1/4" OVER 500'

12. SUPPLY AND INSTALL BIG ROLL 100% KENTUCKY BLUE GRASS.

ALL TRANSPORT AND INSTALLATION EQUIPMENT WILL BE LOW GROUND PRESSURE TO AVOID SOIL COMPACTION.

ADDITIONAL REQUIREMENTS:

A. PROJECT COMPLETION: 90 DAYS FROM ISSUANCE OF PURCHASE ORDER.

B. WORK HOURS: PROJECT IS TO BE COMPLETED DURING NORMAL OPERATING BUSINESS HOURS 7 AM - 3:30 PM MON-FRI. VENDOR MUST SCHEDULE WORK FOR NON OPERATING HOURS IN ADVANCE WITH PHYSICAL PLANT DEPARTMENT.

C. VENDOR RESPONSIBLE FOR ALL LABOR INCLUDING BUT NOT LIMITED TO ELECTRICAL, PLUMBING, GENERAL AS REQUIRED BY THE SCOPE OF WORK.

D. VENDOR RESPONSIBLE FOR ANY REQUIRED LOCAL AND STATE PERMITS.

E. AT ALL TIMES DURING AND AT COMPLETION OF PROJECT, CONSTRUCTION AREAS ARE TO BE KEPT IN A CLEAN, SAFE AND ACCEPTABLE CONDITION.

F. VENDOR RESPONSIBLE FOR REMOVING ALL PROJECT DEBRIS OFF-SITE DAILY.

G. VENDOR RESPONSIBLE FOR ALL SAFETY SIGNAGE AS REQUIRED TO ENSURE THE SAFETY OF CCRI STUDENTS, EMPLOYEES AND VISITORS TO THE CAMPUS.

H. ALL COMPLETED WORK MUST BE INSPECTED AND APPROVED BY THE ASSISTANT BUILDING AND GROUNDS OFFICER OR AN APPROPRIATE DESIGNEE.

LINE TWO

REMEDATION/UPGRADE BASEBALL INFIELD @ THE KNIGHT CAMPUS OF CCRI TO INCLUDE BUT NOT BE LIMITED TO THE FOLLOWING:

VENDOR TO SUPPLY ALL LABOR, MATERIAL AND EQUIPMENT NEEDED.

SCOPE OF WORK:

1. THIS SCOPE OF WORK IS BASED ON 38,000 SQ. FT OF REMEDIATION AREA WITH OUTLINE OF WORK LISTED BELOW.
2. REMOVE IRRIGATION HEADS, VALVES, QUICK CONNECTS AND ZONE VALVES FROM ENTIRE REMEDIATION AREAS.
3. ALL GRASS, THATCH AND ORGANIC MATTER WILL BE REMOVED FROM INFIELD, FOUL LINES AND 8,000 SQ. FT. OF THE OUTFIELD.
4. VENDOR MUST PROVIDE EXISTING CONDITIONS, IRRIGATION, AND PROPOSED FIELD PLANS TO OWNER PRIOR TO JOB COMMENCEMENT. PLANS MUST SHOW TRANSITION MEETING EXISTING CONTOURS.
5. REMOVE ALL INFIELD CLAY AND SOIL OFF THE ENTIRE REMEDIATION AREA. THESE MATERIALS MUST BE REMOVED IN SUCH MANNER AS TO BE SURE THAT THERE WILL BE NO INTEGRATION BETWEEN IN-FIELD MIX AND SOIL. MATERIALS THAT HAVE NOT BEEN CONTAMINATED DURING THE EXCAVATION PROCESS WILL BE SCREENED AND REUSED.
6. GRADE SUB BASE TO THE PROPER SLOPE AND ELEVATION TO WITHIN 1/4" USING FULLY AUTOMATED LASER GRADER.
7. REINSTALL INFIELD MIX AND SOIL BACK ONTO FIELD BASED ON MAJOR LEAGUE SPECIFICATIONS AND NEW ELEVATIONS AND SLOPE. ALL CONSTRUCTION MUST COMPLY WITH NEW GRADING PLANS. SOIL MUST TRANSITION INTO EXISTING OUTFIELD WITH NO VISUAL IMPERFECTIONS SUCH AS RAMPING UP OR DROPPING OFF.
8. FINISH GRADE ENTIRE REMEDIATION AREA TO PROPER SLOPE AND ELEVATION TO WITHIN 1/4" USING A FULLY AUTOMATED LASER GRADER.
9. SUPPLY AND INSTALL FERTILIZER AND/OR AMENDMENTS BASED ON SOIL ANALYSIS TAKEN PRIOR TO JOB.
10. SUPPLY AND INSTALL 4' BIG ROLLS OF 100% KENTUCKY BLUE GRASS SOD
11. FURNISH AND INSTALL NEW BASES, PITCHING RUBBER, AND HOME PLATE.
12. SUPPLY AND INSTALL HILL TOPPER PACKING CLAY FOR MOUND AND BATTER'S BOX
13. FURNISH AND INSTALL 2 TONS TURFACE PRO RED SOIL CONDITIONER.

ADDITIONAL REQUIREMENTS:

- A. PROJECT COMPLETION: 90 DAYS FROM ISSUANCE OF PURCHASE ORDER.
- B. WORK HOURS: PROJECT IS TO BE COMPLETED DURING NORMAL OPERATING BUSINESS HOURS 7 AM - 3:30 PM MON-FRI. VENDOR MUST SCHEDULE WORK FOR NON OPERATING HOURS IN ADVANCE WITH PHYSICAL PLANT DEPARTMENT.
- C. VENDOR RESPONSIBLE FOR ALL LABOR INCLUDING BUT NOT LIMITED TO ELECTRICAL, PLUMBING, GENERAL AS REQUIRED BY THE SCOPE OF WORK.
- D. VENDOR RESPONSIBLE FOR ANY REQUIRED LOCAL AND STATE PERMITS.

E. AT ALL TIMES DURING AND AT COMPLETION OF PROJECT, CONSTRUCTION AREAS ARE TO BE KEPT IN A CLEAN, SAFE AND ACCEPTABLE CONDITION.

F. VENDOR RESPONSIBLE FOR REMOVING ALL PROJECT DEBRIS OFF-SITE DAILY.

G. VENDOR RESPONSIBLE FOR ALL SAFETY SIGNAGE AS REQUIRED TO ENSURE THE SAFETY OF CCRI STUDENTS, EMPLOYEES AND VISITORS TO THE CAMPUS.

H. ALL COMPLETED WORK MUST BE INSPECTED AND APPROVED BY THE ASSISTANT BUILDING AND GROUNDS OFFICER OR AN APPROPRIATE DESIGNEE.

LINE THREE

IRRIGATION WORK ON IN-FIELD AS FOLLOWS:
SCOPE OF WORK:

1. SUPPLY AND INSTALL 1 ZONE IN FOUL TERRITORY WITH ROTORS.
2. SUPPLY AND INSTALL 1 ZONE IN FIELD WITH ROTORS. (4 HEADS)
3. SUPPLY AND INSTALL 1 ZONE BEHIND INFIELD SKIN WITH ROTORS. (5 HEADS)

VENDORS WILL INSTALL ALL NEW PVC PIPING, NEW SWING JOINTS AND HEADS, USING EXISTING WIRING AND CONTROLLER.

LINE FOUR

IRRIGATION WORK IN OUT – FIELD:

HOURLY RATE NORMAL BUSINESS HOURS (7:30AM-3:30PM) WEEKDAYS @
\$ _____ .00/HR

RATE OVERTIME HOURS (AFTER; 30PM WEEK DAYS AND WEEKEND
HOURS) @ \$ _____ .00/HR

PARTS FOR REPAIRS TO BE PROVIDED AT A DISCOUNT OFF LIST PRICE
_____ %

E. AT ALL TIMES DURING AND AT COMPLETION OF PROJECT, CONSTRUCTION AREAS ARE TO BE KEPT IN A CLEAN, SAFE AND ACCEPTABLE CONDITION

F. VENDOR RESPONSIBLE FOR REMOVING ALL PROJECT DEBRIS OFF-SITE DAILY

G. VENDOR RESPONSIBLE FOR ALL SAFETY SIGNAGE AS REQUIRED TO ENSURE THE SAFETY OF CCRI STUDENTS, EMPLOYEES AND VISITORS TO THE CAMPUS.

H. ALL COMPLETED WORK MUST BE INSPECTED AND APPROVED BY THE ASSISTANT BUILDING AND GROUNDS OFFICER OR AN APPROPRIATE DESIGNEE.

LINE THREE

IRRIGATION WORK ON IN-FIELD AS FOLLOWS:

SCOPE OF WORK:

1. SUPPLY AND INSTALL 1 ZONE IN FOUL TERRITORY WITH ROTORS
2. SUPPLY AND INSTALL 1 ZONE IN INFIELD WITH ROTORS (4 HEADS)
3. SUPPLY AND INSTALL 1 ZONE BEHIND INFIELD SKIN WITH ROTORS (5 HEADS)

VENDOR WILL INSTALL ALL NEW PVC PIPING, NEW SWING JOINTS AND HEADS, USING EXISTING WIRING AND CONTROLLER

LINE FOUR

IRRIGATION WORK IN OUT-FIELD:

HOURLY RATE NORMAL BUSINESS HOURS (7:30AM-3:30PM) WEEK DAYS @ \$__00/HR HOURLY

RATE OVERTIME HOURS (AFTER 3:30PM WEEK DAYS AND WEEKEND HOURS) @ \$__00/HR

MARK UP FOR PARTS OVER COST @ ___% FOR REPAIRS THAT MAY BE NECESSARY

Changed - for spec per law.

new version entered for bid

Contract Terms and Conditions

Table of Contents

Terms and Conditions	VII
BID STANDARD TERMS AND CONDITIONS	VII
TERMS AND CONDITIONS FOR THIS BID	VII
SURETY REQUIREMENTS	VII
INSPECTION REQUIREMENTS	VII
INSURANCE REQUIREMENTS	VII
AWARD	VII
LICENSE REQUIREMENTS	VII
HOURLY RATE SPECIFICS	VIII
VENDOR SPECIFICATIONS	VIII
RIVIP INFO - BID SUBMISSION REQUIREMENTS	VIII
DELIVERY PER AGENCY	VIII
WAGE REQUIREMENTS	VIII

Terms and Conditions

BID STANDARD TERMS AND CONDITIONS

TERMS AND CONDITIONS FOR THIS BID

SURETY REQUIREMENTS

BIDDER IS REQUIRED TO PROVIDE A BID SURETY IN THE FORM OF A BID BOND, OR A CERTIFIED CHECK PAYABLE TO THE STATE OF RHODE ISLAND, IN THE AMOUNT OF A SUM NOT LESS THAN FIVE PERCENT (5%) OF THE BID PRICE. BID SURETY MUST BE ATTACHED TO THE BID FORM. THE SUCCESSFUL BIDDER WILL ALSO BE REQUIRED TO FURNISH PERFORMANCE AND LABOR AND PAYMENT BONDS AT TIME OF TENTATIVE CONTRACT AWARD.

INSPECTION REQUIREMENTS

BIDDERS ARE RESPONSIBLE FOR INSPECTION OF EQUIPMENT AND/OR LOCATION, TAKING MEASUREMENTS* WHEN REQUIRED, AND MAKING THEMSELVES AWARE OF THE TOTAL REQUIREMENT BEFORE SUBMITTING A BID. *MEASUREMENTS PROVIDED WITH ANY BID ARE FOR REFERENCE PURPOSES AND ARE NOT GUARANTEED TO BE COMPLETELY ACCURATE.

INSURANCE REQUIREMENTS

AN INSURANCE CERTIFICATE IN COMPLIANCE WITH PROVISIONS OF ITEM 31 (INSURANCE) OF THE GENERAL CONDITIONS OF PURCHASE IS REQUIRED FOR COMPREHENSIVE GENERAL LIABILITY, AUTOMOBILE LIABILITY, AND WORKERS' COMPENSATION AND MUST BE SUBMITTED BY THE SUCCESSFUL BIDDER(S) TO THE DIVISION OF PURCHASES PRIOR TO AWARD. THE INSURANCE CERTIFICATE MUST NAME THE STATE OF RHODE ISLAND AS CERTIFICATE HOLDER AND AS AN ADDITIONAL INSURED. FAILURE TO COMPLY WITH THESE PROVISIONS MAY RESULT IN REJECTION OF THE OFFEROR'S BID. ANNUAL RENEWAL CERTIFICATES MUST BE SUBMITTED TO THE AGENCY IDENTIFIED ON THE PURCHASE ORDER. FAILURE TO DO SO MAY BE GROUNDS FOR CANCELLATION OF CONTRACT.

NOTE: IF THIS BID COVERS CONSTRUCTION, SCHOOL BUSING, HAZARDOUS WASTE, OR VESSEL OPERATION, APPLICABLE COVERAGES FROM THE FOLLOWING LIST MUST ALSO BE SUBMITTED TO THE DIVISION OF PURCHASES PRIOR TO AWARD: * PROFESSIONAL LIABILITY INSURANCE (AKA ERRORS & OMISSIONS) - \$1 MILLION OR 5% OF ESTIMATED PROJECT COST, WHICHEVER IS GREATER. * BUILDER'S RISK INSURANCE - COVERAGE EQUAL TO FACE AMOUNT OF CONTRACT FOR CONSTRUCTION. * SCHOOL BUSING - AUTO LIABILITY COVERAGE IN THE AMOUNT OF \$5 MILLION. * ENVIRONMENTAL IMPAIRMENT (AKA POLLUTION CONTROL) - \$1 MILLION OR 5% OF FACE AMOUNT OF CONTRACT, WHICHEVER IS GREATER. * VESSEL OPERATION - (MARINE OR AIRCRAFT) - PROTECTION & INDEMNITY COVERAGE REQUIRED IN THE AMOUNT OF \$1 MILLION.

AWARD

THE STATE, AT ITS SOLE DISCRETION, SHALL RESERVE THE RIGHT TO MAKE ONE OR MULTIPLE AWARDS FOR THIS REQUIREMENT AND/OR TO REJECT ANY OR ALL BIDS.

LICENSE REQUIREMENTS

VENDOR (OWNER OF COMPANY) IS RESPONSIBLE TO COMPLY WITH ALL LICENSING OR STATE PERMITS REQUIRED FOR THIS TYPE OF SERVICE. A COPY OF LICENSE/PERMIT SHOULD BE SUBMITTED WITH THIS BID. IN ADDITION TO THESE LICENSE REQUIREMENTS, BIDDER, BY SUBMISSION OF THIS BID, CERTIFIES THAT ANY/ALL WORK RELATED TO THIS BID, AND ANY SUBSEQUENT AWARD WHICH REQUIRES A RHODE ISLAND LICENSE(S), SHALL BE PERFORMED BY AN INDIVIDUAL(S) HOLDING A VALID RHODE ISLAND LICENSE

HOURLY RATE SPECIFICS

BIDDERS ARE ADVISED THE AWARD WILL BE BASED ON EITHER REGULAR, STRAIGHT-TIME HOURLY RATES OR A PERIODIC RATE SUCH AS 500 HOURS, MONTHLY OR ANNUALLY, DEPENDING ON THE SPECIFIC REQUIREMENTS OF A PARTICULAR BID. KEEP IN MIND THAT OVERTIME RATES, DISCOUNTS, AND OTHER MISCELLANEOUS PRICE-RELATED ITEMS ARE REQUIRED FOR INFORMATIONAL PURPOSES ONLY. OVERTIME RATE IS TO BE PAID IN ACCORDANCE WITH THE PROVISIONS OF THE RI DEPARTMENT OF LABOR AND TRAINING, EMPLOYER HANDBOOK. EMPLOYEES ARE TO BE COMPENSATED AT TIME AND ONE-HALF THE APPLICABLE PREVAILING WAGE RATE. OVERTIME RATES EXCEEDING ONE AND ONE HALF TIMES THE REGULAR HOURLY RATES FOR MONDAY THROUGH SATURDAY AND EXCEEDING TWO TIMES THE REGULAR RATE FOR SUNDAYS AND HOLIDAYS MAY BE GROUNDS FOR DISQUALIFICATION OF THE BID

VENDOR SPECIFICATIONS

ALL VENDORS MUST INCLUDE SPECIFICATIONS WITH BID PROPOSAL (EVEN THOSE BIDDING BRAND SPECIFIED) FAILURE TO SUBMIT SPECIFICATIONS WITH BID PROPOSAL MAY RESULT IN DISQUALIFICATION OF BID. ITEMS IN CATALOGS MUST BE CLEARLY MARKED AND PAGES TABBED.

RIVIP INFO - BID SUBMISSION REQUIREMENTS

It is the Vendor's responsibility to check and download any and all addenda from the RIVIP. This offer may not be considered unless a signed RIVIP generated Bidder Certification Cover Form is attached and the Unit Price column is completed. The signed Certification Cover Form must be attached to the front of the offer. When delivering offers in person to One Capitol Hill, vendors are advised to allow at least one hour additional time for clearance through security checkpoints

DELIVERY PER AGENCY

DELIVERY OF GOODS OR SERVICES AS REQUESTED BY AGENCY.

WAGE REQUIREMENTS

BIDDERS ARE ADVISED THAT ALL PROVISIONS OF TITLE 37 CHAPTER 13 OF THE GENERAL LAWS OF RHODE ISLAND APPLY TO THE WORK COVERED BY THIS REQUEST, AND THAT PAYMENT OF THE GENERAL PREVAILING RATE OF PER DIEM WAGES AND THE GENERAL PREVAILING RATE FOR REGULAR, OVERTIME, AND OTHER WORKING CONDITIONS EXISTING IN THE LOCALITY FOR EACH CRAFT, MECHANIC, TEAMSTER, OR TYPE OF WORKMAN NEEDED TO EXECUTE THIS WORK IS A REQUIREMENT FOR BOTH CONTRACTORS AND SUBCONTRACTORS. THE PREVAILING WAGE TABLE MAY BE OBTAINED AT THE RI DIVISION OF PURCHASES HOME PAGE BY INTERNET at www.purchasing.state.ri.us SELECT "INFORMATION" AND THEN SELECT "PREVAILING WAGE TABLE". THE STATE OF RHODE ISLAND USES THE GENERAL DECISION NUMBER RI20100001. PRINTING THE ENTIRE DOCUMENT AVERAGES APPROXIMATELY ONE MINUTE PER PAGE - YOU MAY WANT TO PRINT ONLY THE PAGES APPLICABLE TO YOUR BID. BIDDERS NOTE: IN THE EVENT THIS BID SPECIFIES PRICE OFFERS ON A TIME-AND-MATERIALS BASIS, i.e., AN HOURLY RATE, ANY OR ALL BIDS SUBMITTED IN AN AMOUNT LESS THAN THE PREVAILING RATE IN EFFECT FOR THE WORK COVERED BY

THIS REQUEST AS OF THE DATE OF BID ISSUANCE SHALL BE REJECTED BY THE DIVISION
OF PURCHASES