State of Rhode Island
Department of Administration / Division of Purchases
One Capitol Hill, Providence, Rhode Island 02908-5855
Tel: (401) 574-8100 Fax: (401) 574-8387

Solicitation Information
October 23, 2012

ADDENDUM # 3

RFQ# 7458118
Title: RE-ROOFING AND RELATED ROOF REPAIRS AT THE ACI, INTAKE SERVICE CTR. (SOUTH WING)
BID CLOSING DATE: OCOBER 26, 2012 AT 10:45 AM (EST)

Notice to Vendors:

SEE ATTACHED FOR CLARIFICATIONS

Thomas Bovis
Interdepartmental Project Manager

Interested parties should monitor this website, on a regular basis, for any additional information that may be posted.

DOCUMENT 00900

ADDENDA AND MODIFICATIONS

ADDENDUM NO. 3, 23 October 2012

RE: Re-Roofing and Related Roof Repairs at the Adult Correctional Institution, Intake Service Center (South Wing), Pastore Complex, 18 Slate Hill Road, Cranston, RI 02920

FROM: Castellucci, Galli Corporation
175 High Service Avenue
North Providence, Rhode Island 02911

This addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated May, 2012; Addendum No. 1, dated 15 October, 2012; and Addendum No. 2, dated 18 October, 2012 as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of one (1) page.

For clarification, please note the following:

1. Additional site visits will not be scheduled for Bidders to visit the building rooftop.

2. FM Global will not be involved with this project.

3. It is assumed that the majority of the existing roof decks at the Intake Service Center consist of either heavily reinforced concrete or hollow-core pre-cast/pre-stressed concrete (Flexicore); therefore, mechanically fastening of the new roofing system will not be allowed. Also, mechanical fastening of the new roofing system may potentially compromise the effectiveness of the vapor retarder by penetrating the barrier via fasteners.

END OF ADDENDUM