



# Request for Quote

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS  
ONE CAPITOL HILL  
PROVIDENCE RI 02908

BUYER: Gill, Raymond E Jr  
PHONE #: 401-574-8466

CREATION DATE : 16-NOV-12  
BID NUMBER: 7458262,1  
TITLE: REPAIRS TO FIX WATER INFILTRATION -  
ATTORNEY GENERAL OFFICE  
  
BLANKET START : 01-DEC-12  
BLANKET END : 30-JUN-13  
BID CLOSING DATE AND TIME:28-NOV-2012 10:15:00

B  
I  
L  
L  
  
T  
O  
  
ATTORNEY GENERAL  
150 SOUTH MAIN STREET  
PROVIDENCE, RI 02903  
US

S  
H  
I  
P  
  
T  
O  
  
ATTORNEY GENERAL  
150 SOUTH MAIN STREET  
PROVIDENCE, RI 02903  
US

Requisition Number: 1290535  
Note to Bidders: THERE WILL BE A MANDATORY PRE-BID  
HELD ON NOVEMBER 14, 2012 AT 10:00 AM  
ATTY GENERAL'S OFFICE  
150 SOUTH MAIN STREET  
PROVIDENCE, RI

MEETING ATTENDEES MUST BRING IDENTIFICATION TO ACCESS THE BUILDING. TWO PAGES OF SPECIFICATIONS ARE ATTACHED.  
Amendment Description: AMENDMENT 1 PROVIDES ADDITIONAL SPECIFICATION INFORMATION BASED ON THE MANDATORY PRE-BID HELD  
11/14/12 AND POSTS THE LIST OF VENDORS ATTENDING THE PRE-BID MEETING

Line	Description	Quantity	Unit	Unit Price	Total
1	REPAIRS NECESSARY TO FIX WATER INFILTRATION IN THE LOWER LEVEL AT 150 SOUTH MAIN STREET	1.00	Each		

Delivery: \_\_\_\_\_

Terms of Payment: \_\_\_\_\_

It is the Vendor's responsibility to check and download any and all addenda from the RIVIP. This offer may not be considered unless a signed RIVIP generated Bidder Certification Cover Form is attached and the Unit Price column is completed. The signed Certification Cover Form must be attached to the front of the offer



**State of Rhode Island**  
**Department of Administration / Division of Purchases**  
**One Capitol Hill, Providence, Rhode Island 02908-5855**  
**Tel: (401) 574-8100 Fax: (401) 574-8387**

RFQ 7458262 AMENDMENT 1

- There are no restrictions regarding the computer equipment that will affect the use of a jack hammer
- Equipment fumes need to be managed appropriately. If a piece of equipment is designed to discharge a large amount of fumes while operating it will need to be vented out or an exhaust system will need to be set up to remove the fumes from the building.
- In between the 3/4" crushed stone and the new concrete a layer of Mirafi 180N or equal shall be placed on top of the stone, followed by 18" of a clean bank run gravel with no more than 10% passing the #200 sieve. This gravel is to be compacted to 95% of its maximum dry density as determined by ASTM D1557 Method c. Concrete strength should be 5,000 psi. Concrete cylinder samples will be taken to test the strength of the concrete at no cost to the Contractor.
- Contractor's presence during the mandatory walk through are allowed to come back into the building to measure or bring sub-contractors in if necessary prior to submitting their bid. No questions will be answered during these visits. Contact Bill Masse @274-4400 ext. 2216 for an appointment.
- Upon opening the concrete floor, the contractor will assume the responsibility of maintaining and managing the water infiltration in the affected area until the project is completed
- Trench will need to be covered and secured for safety reasons when contractor is not on site.
- Once the PO is awarded contractor must complete the project within 45 days unless extension is approved by the agency rep
- Contractor responsible for protecting existing flooring from work area to service elevator

