



State of Rhode Island  
Department of Administration / Division of Purchases  
One Capitol Hill, Providence, Rhode Island 02908-5855  
Tel: (401) 574-8100 Fax: (401) 574-8387

**ADDENDUM # 1**

5/24/13

RFQ #7463372

**Title: Alterations; Miscellaneous Roofing Work – University of Rhode Island**

**Submission Deadline: June 04, 2013 @ 10:00 AM local prevailing time.**

**Per the issuance of ADDENDUM #1 the following are noted:**

- Pre-Bid attendance sheet
- Document 00900 – Addenda and Modifications

*Interested parties should monitor this website, on a regular basis, for any additional information that may be posted.*

Gary P. Mosca,  
Buyer

**DOCUMENT 00900 - ADDENDA AND MODIFICATIONS****ADDENDUM NO. 1 – May 23, 2013**

**FROM:** Lamborghini/ Feibelman Ltd.  
14 Imperial Place, Suite 201  
Providence, RI 02903

**TO:** Prospective Bidders

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated January 21, 2013 with amendments and additions noted below.

Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may disqualify the Bidder.

This Addendum consists of this page and the following attachments:

No.	Description	Issue Date	Number of pages
	Sign-in Sheet Pre-Bid Meeting	May 16, 2013	1

**MANDATORY PRE- BID MEETING**

A mandatory pre-bid meeting was held on May 16, 2013 and the Sign-in Sheet for that meeting is attached to this addendum.

**QUESTIONS AND ANSWERS**

1. QUESTION: Who is responsible for Builder's Risk Insurance for this project?

ANSWER: Contractor is responsible for Builder's Risk Insurance.

2. QUESTION: With reference to Instructions to Bidders, Section 2.3, should public copy requirements be met for all projects?

ANSWER: Comply with public copy requirements for all bids with a value in excess of \$500,000. Refer to NOTICE TO CONTRACTORS AND VENDORS BIDDING ON PUBLIC WORKS PROJECTS, revised 12/7/12, available on the State of Rhode Island, Division of Purchases website.

### CHANGES TO PROJECT MANUAL

3. SECTION 061600 – SHEATHING, page 061600, after paragraph 3.1.C, replace paragraph D. with the following,  
“D. For fastening of roof sheathing, comply with requirements of “Table 1 - Roof Sheathing Fastening Schedule” of the APA Data File “Roof Sheathing Fastening Schedules for Wind Uplift” for areas of 110 mph winds and as follows:
  1. Refer to Figure 1 “Roof Fastening Zones.”
  2. Use 8d common(0.131 X 2-1/2 inches) or ring-shank nails (0.135 X 2-1/2 inches)
  3. At main roof, supported panel end and edges, space 6” o. c.
  4. At main roof, panel field, space 6” on center in Zone 2 and 4” o.c. in Zone 3.
  5. At sheathing to gable end wall framing, space 3” o.c. Provide blocking at these panel edges perpendicular to gable end wall framing members in the first two bays of framing. Blocking shall be spaced a maximum of 4 feet o.c.
  6. At overhangs (eaves) at supported panel end and edges, space 6” o.c.
  7. At overhangs (eaves) at panel field, space 6” o.c in Zone 2 and 4” o.c. in Zone 3.”
  
4. SECTION 073113- SHINGLES, page 073113-3, 2.1A2, delete “ASTM D 3161 - Class F.”

**END OF ADDENDUM NO. 1**

