

June 21, 2013

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATION  
DEPARTMENT OF ADMINISTRATION

DIVISION OF PURCHASES BID NO. 7471369

RHODE ISLAND DEPARTMENT OF TRANSPORTATION

RHODE ISLAND CONTRACT NO.2013-CT-060

FEDERAL-AID PROJECT NO. FAP Nos: STPG-8888(212)

**Contract 3 – State Traffic Commission**

Atwood Avenue (Route 5) at Plainfield Street/Plainfield Pike (Route 14) and Atwood Avenue (Route 5) Walnut Grove Avenue.

CITY/TOWN OF Cranston, Johnston

COUNTY OF PROVIDENCE

NOTICE TO PROSPECTIVE BIDDERS

ADDENDUM NO. 5 Prospective bidders and all concerned are hereby notified of the following changes in the Plans, Specifications, Proposal and Distribution of Quantities for this contract. These changes shall be incorporated in the Plans, Specifications, Proposal and Distribution of Quantities, and shall become an integral part of the Contract Documents.

**A. Specifications - Job Specific**

1. JS-21

Delete page JS-21 in its entirety and replace it with revised page JS-21(R-1) attached to this Addendum No. 5. The Basis of Payment has been revised to include sampling.

**B. Proposal Addition/Deletion**

1. Proposal Page P-1

Delete Proposal Page P-1 in its entirety and replace it with revised Page P-1 attached to this Addendum No. 5. Only Acceptable Bid Prices have been added for item 202.9902, Disposal of Contaminated Soil, Type 1B and item 202.9903, Disposal of Contaminated Soil, Type 2.

2. Proposal Page P-5

Delete Proposal Page P-5 in its entirety and replace it with revised Page P-5 attached to this Addendum No. 5. Only Acceptable Bid Prices have been added for item 202.9902, Disposal of Contaminated Soil, Type 1B and item 202.9903, Disposal of Contaminated Soil, Type 2.

  
RI Department of Transportation  
Chief Engineer

will not be allowed at any facility that currently maintains a listing as a State of Federal waste site.

The Contractor shall provide all labor, equipment and materials to load and haul contaminated soil to the Engineer approved recycling/disposal facility. The Contractor shall be responsible for all costs associated with the loading and hauling of contaminated soil to the Engineer approved recycling/disposal facility.

All soils to be disposed shall be disposed within thirty (30) days of excavation. The Contractor shall be responsible for providing copies of all disposal related documents including but not limited to manifests, certified weight slips and signed bills of lading to the Engineer of actual quantities of material for off-site recycling.

Type 1B and Type 2 soils shall not be re-used on-site without the Engineer's prior approval. The Contractor shall submit a request for the on-site re-use of Type 1B and Type 2 soils as common borrow to the Engineer for approval 3 business days prior to the proposed re-use. The Contractor shall include documentation that the Type 1B and Type 2 soils meet the standard specification criteria for common borrow in the on-site re-use request for approval submittal.

The Contractor shall provide drawings showing the location, quantity, and depth of Type 1B and/or Type 2 soils that are reused on-site to the Engineer.

**METHOD OF MEASUREMENT:** "REMOVING, LOADING, AND HAULING OF CONTAMINATED SOILS" will be measured by the "ton".

**BASIS OF PAYMENT:** The measured quantity of "REMOVING, LOADING, AND HAULING OF CONTAMINATED SOILS" shall be paid for at the contract unit price per "ton" as listed in the Proposal. The price so stated shall constitute full and complete compensation for all additional labor, materials, and equipment required for excavating, loading, hauling, and stockpiling contaminated soils, soil stockpile sampling and laboratory analysis required by the disposal/recycling facility for disposal/recycling characterization, obtaining approval for soil recycling/disposal at a properly licensed soil recycling/disposal facility, and loading and transportation of the impacted soil to a properly licensed soil recycling/disposal facility, and other incidentals required to complete this work. Release of retainage under this item will not be made until all recycling/disposal documentation including but not limited to manifests and/or bills of lading, weight slips and disposal receipts has been submitted to the RIDOT.

Disposal of contaminated soil shall not be paid in this item. Disposal of contaminated soil shall be paid in items 202.9902 and 202.9903.

## SPECIAL NOTICE

### PROPOSAL

Project Name - Contract 3 – State Traffic Commission

Estimate Name - Addendum 5

R.I. Contract No. - 2013-CT-060

FAP Nos - STPG-8888(212)

All items in the Proposal must have a unit bid price in words and figures. All unit bid prices must be extended. Bids will not be accepted if they contain no unit price for an item or if they contain zero in words and figures as the unit price bid.

The minimum acceptable bid price for:

Code 212.2000, CLEANING AND MAINTENANCE OF EROSION CONTROLS is Two Thousand Five Hundred Dollars And No Cents (\$2,500.00) per LS

Code 907.0100, WATER FOR DUST CONTROL is Fourteen Dollars And Fifty Cents (\$14.50) per MGAL

Code 907.0200, CALCIUM CHLORIDE FOR DUST CONTROL (PROJECT WIDE) is Three Hundred Dollars And No Cents (\$300.00) per TON

Code 914.5010, FLAGPERSONS is Forty One Dollars And Ten Cents (\$41.10) per MHRS

Code 914.5020, FLAGPERSONS - OVERTIME is Fifty One Dollars And Thirty Eight Cents (\$51.38) per MHRS

Code 937.0200, MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION is Forty Thousand Dollars And No Cents (\$40,000.00) per LS

Code 943.0200, TRAINEE MAN-HOURS is Six Dollars And No Cents (\$6.00) per MHRS

The only acceptable bid price for:

Code 202.9902, DISPOSAL OF CONTAMINATED SOIL, TYPE 1B is Fifteen Dollars And No Cents (\$15.00) per TON

Code 202.9903, DISPOSAL OF CONTAMINATED SOIL, TYPE 2 is Seventy Five Dollars And No Cents (\$75.00) per TON

Code T12.9902, MAINTENANCE OF TEMPORARY TRAFFIC SIGNAL SYSTEM is Ten Thousand Dollars And No Cents (\$10,000.00) per LS

Items preceded with the letter "S" in the proposal are Specialty Items.

## Proposal Items

Project Name - Contract 3 – State Traffic Commission

Estimate Name - Addendum 5

R.I. Contract No. - 2013-CT-060

FAP Nos - STPG-8888(212)

-----  
 Note: The UNIT PRICE for each Item must be written in words and figures.  
 -----

No.	Item Code	Quantity	Description	Unit	Unit Bid Price	Amount (PxQ)
					\$0.00	\$0.00
022	202.0100	710.00	EARTH EXCAVATION			
	AT			CY		
023	202.0700	40.00	COMMON BORROW			
	AT			CY		
024	202.9901	77.00	REMOVING, LOADING, AND HAULING OF CONTAMINATED SOILS			
	AT			TON		
025	202.9902	51.00	DISPOSAL OF CONTAMINATED SOIL, TYPE 1B			
	AT	Fifteen Dollars And No Cents		TON	\$15.00	\$765.00
026	202.9903	26.00	DISPOSAL OF CONTAMINATED SOIL, TYPE 2			
	AT	Seventy Five Dollars And No Cents		TON	\$75.00	\$1,950.00
027	204.0100	2,043.00	TRIMMING AND FINE GRADING			
	AT			SY		
028	205.0270	50.00	TRENCH ROCK EXCAVATION-MECHANICAL (0-7')			
	AT			CY		