

July 31, 2013

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATION
DEPARTMENT OF ADMINISTRATION
DIVISION OF PURCHASES BID NO. 7484375

RHODE ISLAND DEPARTMENT OF TRANSPORTATION

RHODE ISLAND CONTRACT NO.2013-CH-075

FEDERAL-AID PROJECT NO. FAP Nos: IM-2955(109)

I-295 Ramps Resurfacing Warwick to Mass State Line

Warwick to the Massachusetts State Line

CITY/TOWN OF Statewide

COUNTY OF STATEWIDE

NOTICE TO PROSPECTIVE BIDDERS

ADDENDUM NO. 1 Prospective bidders and all concerned are hereby notified of the following changes in the Plans, Specifications, Proposal and Distribution of Quantities for this contract. These changes shall be incorporated in the Plans, Specifications, Proposal and Distribution of Quantities, and shall become an integral part of the Contract Documents.

A. Clarification

1. Page A-2

The project description on Page A-2 has been revised. Rte. 133 revised to Rte. 113.

B. Job Specific

1. Page JS-21

Delete Index Page JS-21 in its entirety and replace it with revised Index Page JS-21 (R-1) attached to this Addendum No. 1. The item code number for Inspection, GPS and Documentation – Outfall has been revised.

C. Distribution of Quantities

1. Index Page 1

Delete Index Page 1 in its entirety and replace it with revised Index Page 1 (R-1) attached to this Addendum No. 1. Item Codes 709.9905 and 709.9906 have been deleted.

2. Index Page 2


Delete Index Page 2 in its entirety and replace it with revised Index Page 2 (R-1) attached to this Addendum No. 1. Item Codes 709.9907, 709.9908 and 709.9909 have been added.

3. Page 50

Delete Page 50 in its entirety and replace it with revised Page 50 (R-1) attached to this Addendum No. 1. Item Nos. S027 and S028 have been deleted.

4. Page 114

Add Page 114 attached to this Addendum No. 1. Item Nos. S084, S085, and S086 have been added to the contract.



RI Department of Transportation
Chief Engineer

JOB SPECIFIC
R.I. CONTRACT NO. 2013-CH-075

CLOSED CIRCUIT TELEVISION INSPECTION (CCTV) INSPECTION,
LOCATION, and DOCUMENTATION OF STORM DRAIN PIPES & STRUCTURES

CODE 709.9907
INSPECTION, GPS AND DOCUMENTATION – PIPE

CODE 709.9908
INSPECTION, GPS AND DOCUMENTATION – STRUCTURE

CODE 709.9909
INSPECTION, GPS AND DOCUMENTATION – OUTFALL

DESCRIPTION:

This work consists of closed circuit television (CCTV) inspection, geographically referencing, and documentation of storm drains and drainage structures of all types and sizes as designated on the Plans or as directed by the Engineer, all in accordance with these Specifications.

Closed Circuit Television (CCTV) equipment shall be used to inspect the condition of all storm drain pipes and structures after the cleaning and flushing has been completed in accordance with RIDOT Standard Specifications Section 708, and has been accepted by the Engineer.

Inspection and documentation of pipes, inlets, manholes, water quality structures, and catch basins shall conform to the National Association of Sewer Service Companies (NASSCO) Standards for Pipeline Assessment & Certification Program (PACP) and for Manhole Assessment & Certification Program (MACP) (www.nassco.org). Inspections of outfalls shall be completed using forms and the RIDOT Outfall Database provided by the Department.

The CCTV Operator shall be MACP and PACP certified with a minimum of two active years of experience in performing CCTV inspections. The Contractor shall provide proof of qualifications to the Department prior to Award.

The geographical location of each structure within the storm drain system, including inlets, manholes, catch basins, and outfalls, shall be provided by the Contractor. Locational information (i.e. Northing and Easting coordinates) shall be: 1) obtained from a mapping-grade GPS unit or survey equipment with equal or greater accuracy and precision, 2) provided in either RI State Plane Feet NAD 83 coordinate system or Decimal Degrees (World Geodetic System) WGS84 coordinate system; vertical datum shall be provided in North American Vertical Datum of 1988 (NAVD88) and 3) must be accurate to within 5-feet. Coordinate System and accuracy must be documented for each data point as part of the MACP/PACP database and the RIDOT Outfall Database. Equipment used to locate structures must be documented in final data submission.

Addendum No. 1

Table of Contents - Distribution of Quantities

Project Name - I-295 Ramps Resurfacing Warwick to Mass State Line
 Estimate Name - Addendum No.1
 R.I. Contract No. - 2013-CH-075
 FAP Nos: IM-2955(109)

ItemCode	Description	Page
201.0321	CLEARING AND GRUBBING	1
201.0401	REMOVE AND DISPOSE GRANITE CURB	3
201.0402	REMOVE AND DISPOSE CONCRETE CURB	3
201.0409	REMOVE AND DISPOSE FLEXIBLE PAVEMENT	5
201.0428	REMOVE AND DISPOSE FRAME AND GRATE OR FRAME AND COVER	6
201.9901	REMOVE AND DISPOSE GUARDRAIL POST	9
201.9902	REMOVE AND DISPOSE GUARDRAIL BEAM ONLY	9
201.9903	REMOVE AND DISPOSE GORE MARKER	9
202.0100	EARTH EXCAVATION	10
204.0100	TRIMMING AND FINE GRADING	10
206.9901	SILT SACK	10
206.9902	COMPOST FILTER SOCK	17
212.2000	CLEANING AND MAINTENANCE OF EROSION CONTROLS	22
401.9902	CLASS 9.5 HOT MIX ASPHALT	22
402.9901	FRICTION COURSE	22
403.0300	ASPHALT EMULSION TACK COAT	25
601.0300	CLASS A PORTLAND CEMENT CONCRETE	25
702.0510	HEAVY-DUTY SQUARE FRAME AND ROUND COVER STANDARD 6.1.1	25
702.0515	FRAME AND GRATE HIGH CAPACITY STANDARD 6.3.3	25
702.0530	PRECAST CONCRETE INLET STONE 5' STANDARD 7.1.5	28
704.9901	RECONSTRUCT CATCH BASIN	29
707.1900	ADJUST FRAME & COVER TO GRADE	31
707.2000	ADJUST FRAME AND GRATE TO GRADE	32
708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	39
708.9042	CLEANING MANHOLES ALL TYPES AND SIZES	45
708.9901	CLEANING AND FLUSHING PIPE ALL SIZES	45
709.9905	** ITEM DELETED **	50
709.9906	** ITEM DELETED **	50
711.9901	3" PAVED WATERWAY CLASS 9.5 HOT MIX ASPHALT MODIFIED, STD. 8.4.0	50
821.1690	SAW & SEALING JOINTS IN BITUMINOUS CONCRETE PAVEMENT	51
839.0100	PARTIAL-DEPTH REMOVAL AND DISPOSAL OF BITUMINOUS PAVEMENT FROM CONCRETE BRIDGE DECKS	51
901.0160	REFLECTORIZED TRIANGULAR DELINEATORS STANDARD 34.2.5	51
901.0161	GUARDRAIL STEEL BEAM POST (IN EARTH AND ASPHALT)	52
901.0165	STEEL BEAM GUARDRAIL SECTION (12.5 FT. BY 12.0 INCHES)	56
901.0191	GUARDRAIL STEEL BEAM ANCHORAGE TRAILING END SECTION STANDARD 34.3.4	65
901.0198	GUARDRAIL END TREATMENT, NON-ENERGY ABSORBING TERMINAL	67
901.0199	GUARDRAIL END TREATMENT, ENERGY ABSORBING TERMINAL	70
901.9901	STEEL THRIE BEAM GUARDRAIL SECTION (12.5 FT. BY 12.0 INCHES)	70
901.9902	REMOVE AND RESET GUARDRAIL	70
906.0110	GRANITE CURB, QUARRY SPLIT STRAIGHT, STANDARD 7.3.0	71
906.0210	CEMENT CONCRETE CURB PRECAST STRAIGHT STANDARD 7.1.0	72
906.0211	CEMENT CONCRETE CURB PRECAST CIRCULAR STANDARD 7.1.0	72
906.0230	CEMENT CONCRETE SLOPE FACE CURB PRECAST STRAIGHT STANDARD 7.2.0	72
906.0231	CEMENT CONCRETE SLOPE FACE CURB PRECAST CIRCULAR STANDARD 7.2.0	74
906.0271	PRECAST CONCRETE SLOPE FACE TRANSITION CURB STANDARD 7.2.1	74
914.5010	FLAGPERSONS	75
914.5020	FLAGPERSONS - OVERTIME	75
920.0040	DUMPED STONE RIPRAP R-3, R-4, R-5 STANDARD 8.3.0	76
920.0135	BEDDING FOR RIPRAP FS-2 STANDARD 8.3.0	79
920.0200	FILTER FABRIC FOR RIP-RAP	82

Table of Contents - Distribution of Quantities
 Project Name - I-295 Ramps Resurfacing Warwick to Mass State Line
 Estimate Name - Addendum No.1
 R.I. Contract No. - 2013-CH-075
 FAP Nos: IM-2955(109)

ItemCode	Description	Page
922.0100	TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1	85
923.0105	DRUM BARRICADE STANDARD 26.2.0	87
923.0120	PLASTIC PIPE BARRICADE STANDARD 26.3.0	87
923.0200	FLUORESCENT TRAFFIC CONES STANDARD 26.1.0	87
924.0113	ADVANCE WARNING ARROW PANEL	87
925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	87
928.0800	TRUCK MOUNTED ATTENUATOR WITH TRUCK MOUNTED FLASHING ARROW BOARD	87
929.0110	FIELD OFFICE	88
931.0110	CLEANING AND SWEEPING PAVEMENT	88
932.0100	CUTTING AND MATCHING ASPHALT	88
932.0200	FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT	94
935.0400	REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING	97
936.0110	MOBILIZATION	99
937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	99
943.0200	TRAINEE MAN-HOURS	99
L01.0104	PLANTABLE SOIL 4 INCHES DEEP	99
L02.0101	GENERAL HIGHWAY SEEDING (TYPE 1)	103
L06.9901	BETULA NIGRA 'HERITAGE', 2-2.5" CAL., B&B	103
L06.9902	LIQUIDAMBAR STYRACIFLUM, 2-2.5" CAL., B&B	103
L06.9903	PINUS STROBUS, 6-7', B&B	103
T05.1030	ADJUST HANDHOLE TO GRADE	103
T13.1000	TRAFFIC DETECTORS-LOOP, STANDARD 19.6.0	104
T18.0201	REFLECTOR UNIT-SINGLE WHITE DELINEATOR	105
T18.9901	REFLECTOR UNIT SINGLE AMBER DELINEATOR	105
T20.0006	6 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	105
T20.0012	12 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	107
T20.0106	6 INCH YELLOW FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	109
T20.0900	BI-DIRECTIONAL CONTROL DEVICE STANDARD 20.2.0	111
T20.2006	6 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	111
T20.2012	12 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	112
T20.2016	6 INCH EPOXY RESIN PAVEMENT MARKINGS YELLOW	112
T20.9923	FAST DRYING WATERBORNE PAVEMENT MARKING WHITE - YIELD LINE	112
T20.9925	EPOXY RESIN PAVEMENT MARKINGS WHITE - YIELD LINE	113
709.9907	INSPECTION, GPS AND DOCUMENTATION - PIPE	114
709.9908	INSPECTION, GPS AND DOCUMENTATION - STRUCTURE	114
709.9909	INSPECTION, GPS AND DOCUMENTATION - OUTFALL	114

Distribution of Quantities

Project Name - I-295 Ramps Resurfacing Warwick to Mass State Line

Estimate Name - Addendum No.1

R.I. Contract No. - 2013-CH-075

FAP Nos: IM-2955(109)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
026	708.9901 Cont.	AT RAMP		1,391.00	0005	01
		ROUTE 7-S/NB ON-RAMP				
		AT RAMP		605.00	0005	01
		ROUTE 7-S/SB OFF-RAMP				
		AT RAMP		1,300.00	0005	01
		ROUTE 7-S/SB ON-RAMP				
		AT RAMP		1,765.00	0005	01
Item 708.9901 Total:				35,332.00		
S027	709.9905	INSPECTION, LOCATION AND	LF			
		DOCUMENTATION - PIPES				
		PROJECT WIDE				
		FROM ITEM 708.9040			0005	01
Item 709.9905 Total:				**DELETED**		
S028	709.9906	INSPECTION, LOCATION AND	EACH			
		DOCUMENTATION - DRAINAGE STRUCTURE				
		PROJECT WIDE				
		FROM ITEM 708.9041			0005	01
		FROM ITEM 708.9042			0005	01
Item 709.9906 Total:				**DELETED**		
029	711.9901	3" PAVED WATERWAY CLASS 9.5 HOT	SY			
		MIX ASPHALT MODIFIED, STD. 8.4.0				
		DIAMOND HILL ROAD/NB ON-RAMP				
		7+00 RT		14.00	0005	01
		DIAMOND HILL ROAD/SB OFF-RAMP				
		2+50		8.00	0005	01
		PLAINFIELD PIKE/NB ON-RAMP				
		157+90 RT		7.00	0005	01
		ROUTE 113-W/I-95 NB ON RAMP				
		FROM ITEM 201.0409		12.00	0005	01
		ROUTE 146-N/NB ON-RAMP				

Distribution of Quantities

Project Name - I-295 Ramps Resurfacing Warwick to Mass State Line

Estimate Name - Addendum No.1

R.I. Contract No. - 2013-CH-075

FAP Nos: IM-2955(109)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
S084	709.9907	INSPECTION, GPS AND DOCUMENTATION	LF			
		- PIPE				
		PROJECT WIDE				
		FROM ITEM 708.9040		29,115.00	0005	01
		Item 709.9907 Total:		29,115.00		
S085	709.9908	INSPECTION, GPS AND DOCUMENTATION	EACH			
		- STRUCTURE				
		PROJECT WIDE				
		FROM ITEM 708.9041		418.00	0005	01
		FROM ITEM 708.9042		10.00	0005	01
		Item 709.9908 Total:		428.00		
S086	709.9909	INSPECTION, GPS AND DOCUMENTATION	EACH			
		- OUTFALL				
		PROJECT WIDE				
		FROM ITEM 920.0040		173.00	0005	01
		Item 709.9909 Total:		173.00		