State of Rhode Island
Department of Administration / Division of Purchases
One Capitol Hill, Providence, Rhode Island 02908-5855
Tel: (401) 574-8100 Fax: (401) 574-8387

ADDENDUM #2

RFP # 7548386 **TITLE: D.O.T. GLOCESTER FACILITY REHABILITATION**

SUBMISSION DEADLINE: 1/30/14 – 11:00 A.M.

Prospective bidders and all concerned are hereby advised of the attached changes/modifications for the above referenced RFQ and are hereby requested to change their copies accordingly.

- **See attached.**

Lisa Hill

LISA HILL
CHIEF BUYER

Bidders must include a signed copy of this addendum with their proposal submission as acknowledgment.

Company Name (Print) **Signature of Authorized Representative**

Rhode Island Department of Transportation
Division of Highway & Bridge Maintenance
Glocester Facility Rehabilitation
Northwestern Maintenance District Facility

Bid No. 7548386
January 17, 2014

ADDENDUM NO.2

Prospective bidders and all concerned are hereby advised of the following changes/modifications in the Contract Documents for the above referenced Contract and are hereby requested to change their copies accordingly.

THIS ADDENDUM INCLUDES ONE (1) PAGE OF THE CONTRACT SPECIFIC DOCUMENTS. THE ADDENDUM REVISES THE CONTRACT SPECIFIC DOCUMENTS THAT ARE ADDITIONS TO BE ADDED TO THE A NEW SECTION "FRIEDRICH WALLMASTER COMMERCIAL GRADE AIR CONDITIONERS AND COMMERCIAL GRADE SOLID–SIDE WALL SLEEVE". SEE BELOW.

1.) TWO FRIEDRICH WALLMASTER COMMERCIAL GRADE 10,000 BTU AIR CONDITIONERS WITH A MINIMUM 9.4 EER WITH TWO COMMERCIAL GRADE SOLID-SIDE WALL SLEEVES ARE TO BE SUPPLIED UNDER THIS CONTRACT. ONE UNIT WITH SLEEVE IS TO BE INSTALLED IN THE SUPERINTENDENT'S OFFICE AND THE OTHER UNIT AND SLEEVE IS TO BE INSTALLED IN THE PERSONNEL OFFICE.

2.) ONE FRIEDRICH WALLMASTER COMMERCIAL GRADE 12,000 BTU AIR CONDITIONER WITH A MINIMUM 9.4 EER WITH A COMMERCIAL GRADE SOLID-SIDE SLEEVE IS TO BE SUPPLIED UNDER THIS CONTRACT. THE UNIT AND SLEEVE IS TO BE INSTALLED IN THE BREAK ROOM.

3.) ALL NECESSARY WIRING, NEW RECEPTACLES AND ALL INCEDENTAL MATERALS ARE INCLUDED WITH THE INSTALLATION.

4.) UNITS AND SLEEVE TO BE INSTALLED WITH MINIMUM INTRUSION INTO ROOMS.

5.) ***TIMOTHY CARROLL***, SUPERINTENDENT OF RIDOT MAINTENANCE FACILITIES, WILL DETERMINE THE INSTALLATION LOCATION OF THE AIR CONDITIONERS AND SLEEVES. ***MR. CARROLL*** CAN BE REACHED AT (401) 641-5768.

6.) ALL UNITS AND SLEEVES TO BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS MATERIAL DATA SHEETS. ALL UNITS TO INCLUDE A REMOTE CONTROL. ALL AIR CONDITIONING UNITS TO BE 240 VOLT RATED.