State of Rhode Island

Department of Administration
Division of Purchases
One Capitol Hill
Providence, RI 02908

REQUEST FOR QUOTE (RFQ) – BID# 7548568

2014-CH-028 APPONAUG CIRCULATOR BYPASS

SUBMISSION DEADLINE: Wednesday, April 09, 2014 at 01:00 PM (ET)

PRE-BID CONFERENCE: ☐ **NO**
☒ **YES** **Monday, March 24, 2014 at 9:00 AM (ET)**

Mandatory: ☒ **NO**
☐ **YES:** Any vendor who intends to submit a bid proposal in response to this solicitation must have its designated representative attend the mandatory pre-bid conference. The representative must register at the pre-bid conference and disclose the identity of the vendor whom he/she represents. Because attendance at the pre-bid conference is mandatory, a vendor's failure to attend and register at the pre-bid conference shall result in disqualification of the vendor's bid proposal as non-responsive to the solicitation.

Location: **RI DEPARTMENT OF ADMINISTRATION**
1 CAPITOL HILL- CONFERENCE ROOM "A" (2ND FLOOR)
PROVIDENCE, RI

Buyer Name: **LISA HILL**
Title: **CHIEF BUYER**

QUESTIONS Prospective bidders are hereby notified that all questions pertaining to this contract must be submitted to the Department of Transportation in writing through its website at http://www.dot.ri.gov/contracting/bids by accessing the questions & answers menu located within the 'contracting', then 'bidding opportunities' link. Response to the submitted questions will also be posted under this link, phone calls will not be accepted.

SURETY REQUIRED: **YES**

BOND REQUIRED: **YES**

DISK BASED BID: ☐ **NO**
☒ **YES:** See attached Disk Based Bidding Information

NOTE TO VENDORS:
Vendors must register on-line at the Rhode Island Division of Purchases website at www.purchasing.ri.gov. Offers received without the completed four-page Rhode Island Vendor Information Program (RIVIP) Generated Bidder Certification Cover Form attached may result in disqualification.

THIS IS NOT A BIDDER CERTIFICATION FORM

State of Rhode Island and Providence Plantations
Department of Transportation

Notice to Contractors
Special Provisions
Proposal
Contract Agreement
Contract Bond

for the Performance of

Rhode Island Contract Number: 2014-CH-028

Rhode Island Federal-Aid\State-Aid Project Numbers: **3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)**

Project: **Apponaug Circulator By-Pass**

Limits: **Apponaug Circulator in Warwick, RI. I-95 southbound Exit 10B Off-Ramp to West Shore Road/Station Street.**

City/Town: **Warwick**

County: **KENT**

Submitted By: _____

Address: _____

_____

_____

Name of Surety: _____

Total Bid: _____

(BIDDER MUST FILL IN ALL ABOVE SPACES)

The basis of award of the Contract will be the total bid for all quantities of work in the proposal subject to review and correction as provided for in the Rhode Island Department of Transportation Standard Specifications for Road and Bridge Construction and Standard Details.

NOTE: The State of Rhode Island Standard Specifications for Road and Bridge Construction and Standard Details consists of the following:

- The Rhode Island Standard Specifications for Road and Bridge Construction, Amended December 2010, with all revisions.
- The Rhode Island Standard Details, 1998 Edition, with all revisions.
- The Rhode Island Bridge Standard Details, 2010 Edition, with all revisions.
- The Division of Purchases Procurement Regulations Adopted December 2010.

*** Refer to Section 12.102.05 PREPARATION OF PROPOSAL of the STATE OF RHODE ISLAND PROCUREMENT REGULATIONS regarding the use of Quest Lite software for bid preparation.**

The above documents may be obtained at the Rhode Island Department of Transportation, Contracts and Specifications Office, upon request.

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS
DEPARTMENT OF ADMINISTRATION - DIVISION OF PURCHASES

NOTICE TO HIGHWAY AND BRIDGE CONTRACTORS

Sealed Proposals addressed to the State Purchasing Agent, Rhode Island Department of Administration, Division of Purchases, One Capitol Hill, Providence, Rhode Island 02903, will be opened and read in public on April 9, 2014 at 1:00PM. All bidders MUST register online at www.purchasing.ri.gov. A Bidder Certification Cover Sheet MUST accompany each bid. Bid item description and quantities estimated for this project will also be available online. Should you need assistance in registering or downloading a bid, call (401) 222-3766. Failure to comply will result in mandatory disqualification per Item 4 of Section 12.102.12 of the Division of Purchases Procurement Regulations Adopted December 2010 and RI General Law 37-2-17 which references the RI Vendor Information Program (RIVIP).

DESCRIPTION: Rhode Island Contract No. 2014-CH-028, Federal Aid Project Nos. NHP-TIGR(002), NHP-0001 (107), NHPG-0001(108), 3RD-PRTY(221), is for the improvements to Apponaug Circulator in the City of Warwick, RI. Work includes but is not limited to, the construction of new roundabouts, the construction of new roadways, wall construction, building and tower demolitions, management of hazardous materials, UST closures, the relocation of a river, river control structures, construction of water quality control basins, erosion protection, new bridge construction, bridge rehabilitation, new sidewalks, the removal of existing signals, new signal equipment, site preparation, full depth pavement reconstruction, installation of new granite curb and concrete sidewalks, storm drainage modifications, installation of new drainage, water line replacement, lighting, landscaping, pavement markings, highway signing, conversion of roadways from one-way traffic to two-way traffic, maintenance and protection of traffic, and other items of work as necessary to complete the work of this contract to the satisfaction of the Engineer.

The Contractor will be required, in accordance with the provisions of the Disadvantaged Business Enterprise Affirmative Action Certification for Contractors and Consultants, to meet the established Race-Conscious Goal, or Contract Goal, of not less than 18.00 percent of the contract bid price, to the Contractors, Subcontractors, and/or suppliers which qualify as Disadvantaged Business Enterprises (DBE's). Failure by the Contractor to demonstrate every good faith effort in fulfilling its DBE commitment during the construction period will result in the reduction in contract payments by the amount determined by multiplying the awarded contract value by the established DBE percentage, and subtracting the dollar value of the work actually performed by DBE contractors. This action will not preclude RIDOT from imposing sanctions or other remedies available as specified in paragraph (I)(C) of the Disadvantaged Business Enterprise Affirmative Action Certification for Contractors and Consultants.

Computer Disks for competitive bidding for the above described work will be furnished by the Department of Transportation, Division of Administrative Services, Contracts & Specifications Office, Room 108, Two Capitol Hill, Providence, Rhode Island, 02903, Tel.Number (401) 222-2495. The Plans, Specifications and Special Provisions may also be examined on or after March 19, 2014 every weekday except holidays between the hours of 8:00 AM and 4:00 PM.

The Bid Package consists of a single compact disk (CD) containing the following items: Construction Plans, Standard Specifications for Road and Bridge Construction, Compilations of Approved Specifications, Required Contract Provisions for Federal-Aid Construction Contracts, RI Division of Purchases Procurement Regulations, General Provisions, Rhode Island Standard Details, Rhode Island Bridge Standard Details, Federal Wage Rates, Contract-Specific General Provisions, Job-Specific Specifications, Distribution of Quantities, Appendices (if applicable), Quest Lite bid file, Quest Lite installation software and a Quest Lite User Manual. Only complete bid packages will be issued.

Appendix A, Appendix B, GPR Survey Report, Phased Construction Videos, Existing Plans

Prospective Bidders are hereby notified that all questions pertaining to this Contract must be submitted to the Department of Transportation in writing through its website at http://www.dot.ri.gov/contracting/bids/ by accessing the Questions & Answers Menu located within the "Contracting", then "Contract Opportunities" link. Responses to the submitted questions will also be posted under this link. PHONE CALLS WILL NOT BE ACCEPTED.

For help with RIDOT's Quest Lite bid preparation software, please contact the Contracts & Specifications Office, Room 108, Two Capitol Hill, Providence, Rhode Island, 02903, Tel. Number (401)-222-2495 or e-mail Quest@dot.ri.gov.

Please also note that all Bidding Documents required to be submitted and in fact submitted to the Purchasing Agent as part of a bid will be considered returned to the State and need not be returned to RIDOT.

A bid bond payable to the State of Rhode Island, in the amount of 5% of the total or gross sum of the bid must be furnished by each bidder. The Proposal Guaranty will be furnished by surety companies authorized/licensed to do business in the State of Rhode Island. The State reserves the right to retain the surety of all bidders until the successful bidder enters into the Contract or until such time as the award or cancellation of the Contract is announced at which point Sureties will be returned to all bidders by the State of Rhode Island. A performance bond of one hundred (100) percent of the contract price with a satisfactory surety company will be required of the successful bidder. All surety companies must be listed with The Department of the Treasury, Fiscal Services, Circular 570, (Latest Revision published by the Federal Register). The Department of Transportation reserves the right to reject any or all bids.

Required Contract Provisions - The attention of prospective bidders is called to the fact that this project is to be bid upon and the contract executed subject to all applicable federal laws and regulations for carrying out the provisions of the Federal-Aid Highway program..

Wages of labor on Federal -Aid Highway Projects - the prevailing rate of wages for laborers and mechanics employed by contractors or subcontractors on the initial construction of highway projects on the Federal - Aid Highway System, authorized under the Federal Highway Act of 1968, shall be paid wages at rates not less than those prevailing on the same type of work on similar construction in the immediate locality as determined by the United States Secretary of Labor, in accordance with the Act of August 30, 1935, known as the Davis - Bacon Act, under Decision Nos. 1 through 6 as applicable.

Prevailing wage rates and Davis - Bacon Wage Determination Reference Materials are available online at www.purchasing.ri.gov. It is advisable to print only the pages applicable to this bid; the rates active on the Rhode Island Vendor Information Program's bid solicitation date for this project are applicable for the duration of the contract resulting from this bid.

Work Hours Act of 1962 - This contract is subject to Work Hours Act of 1962, Public Law 87-581 and implementing regulations.

Pre-Bid Conference - A Pre-Bid Conference will be held in Providence, Rhode Island, at Rhode Island Department of Administration, Conference Room A on March 24, 2014 at 9:00AM, for the purpose of reviewing construction problems and/or operations concerning the project. Individuals requesting interpreter services for the hearing impaired must notify 401 -222-4971 (T.D.D.) a minimum of at least three (3) business days, seventy-two (72) hours prior to the conference date.

SPECIAL NOTE

ANY REFERENCE TO THE RHODE ISLAND DEPARTMENT OF PUBLIC WORKS OR THE DIRECTOR OF PUBLIC WORKS SHOULD BE REVISED TO THE RHODE ISLAND DEPARTMENT OF TRANSPORTATION AND THE DIRECTOR OF TRANSPORTATION RESPECTIVELY.

NOTICE TO ALL BIDDERS

The Rhode Island Department of Transportation, in accordance with Title VI of the Civil Rights Act of 1964, 42 U.S.C. §§ 2000d - 2000d-4 and 49 C.F.R. Part 21, Nondiscrimination in Federally-Assisted Programs of the Department of Transportation - Effectuation of Title VI of the Civil Rights Act of 1964, issued pursuant to such Act, hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, Disadvantaged Business Enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, sex, national origin, age, or disability in consideration for an award.

To report bid rigging activities call: **1-800-424-9071**

The U.S. Department of Transportation (DOT) operates the above toll-free hotline Monday through Friday, 8:00 a.m. to 5:00 p.m. eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the hotline to report such activities.

The hotline is part of the DOT's continuing effort to identify, and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
001	100.9902	DIESEL EMISSIONS REDUCTION PROGRAM	400,000.00	EACH
002	105.9901	PARTNERING	80,000.00	EACH
003	201.0301	CUTTING AND DISPOSING ISOLATED TREES AND STUMPS (4"- 24")	41.00	EACH
004	201.0302	CUTTING AND DISPOSING ISOLATED TREES AND STUMPS (24" OR PLUS)	5.00	EACH
005	201.0305	COMPLETE REMOVAL AND DISPOSAL OF ISOLATED STUMPS (6" TO 24")	5.00	EACH
006	201.0310	REMOVE AND DISPOSE SHRUBS	332.00	EACH
007	201.0320	CLEARING AND GRUBBING	3.00	ACRE
008	201.0401	REMOVE AND DISPOSE GRANITE CURB	1,800.00	LF
009	201.0402	REMOVE AND DISPOSE CONCRETE CURB	10,445.00	LF
010	201.0403	REMOVE AND DISPOSE SIDEWALKS	13,670.00	SY
011	201.0406	REMOVE AND DISPOSE HIGHWAY BOUNDS	20.00	EACH
012	201.0407	REMOVE AND DISPOSE PAVEMENT AND RIGID BASE	17,940.00	SY
013	201.0409	REMOVE AND DISPOSE FLEXIBLE PAVEMENT	60,700.00	SY
014	201.0410	REMOVE AND DISPOSE CATCH BASINS	65.00	EACH
015	201.0412	REMOVE AND DISPOSE MANHOLE	13.00	EACH
016	201.0414	REMOVE AND DISPOSE PIPE - ALL SIZES	7,519.00	LF
017	201.0415	REMOVE AND DISPOSE GUARDRAIL AND POST ALL TYPES	890.00	LF
018	201.0416	REMOVE AND DISPOSE LOT CURB (ALL SIZES)	143.00	LF
019	201.0418	REMOVE AND DISPOSE HYDRANT	6.00	EACH
020	201.0419	REMOVE AND DISPOSE FENCE	3,760.00	LF
021	201.0420	REMOVE AND DISPOSE CONCRETE SLAB	8,380.00	SY
022	201.0421	REMOVE AND DISPOSE BITUMINOUS CURB	670.00	LF
023	201.0423	REMOVE AND DISPOSE HANDHOLE	6.00	EACH
024	201.0424	REMOVE AND DISPOSE RETAINING WALL	1,470.00	CY
025	201.0426	REMOVE AND DISPOSE PRIVATE SIGN	24.00	EACH
026	201.0427	REMOVE AND DISPOSE CONCRETE CAR STOPS	38.00	EACH
027	201.0428	REMOVE AND DISPOSE FRAME AND GRATE OR FRAME AND COVER	6.00	EACH
028	201.0429	REMOVE AND DISPOSE CURB STOP BOX	35.00	EACH
029	201.0430	REMOVE AND DISPOSE CONCRETE MEDIAN BARRIER	765.00	LF
030	201.0432	REMOVE AND DISPOSE HEADWALL	1.00	EACH
031	201.0434	REMOVE AND DISPOSE MONITORING/OBSERVATION WELL	69.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
032	201.0610	REMOVE AND DISPOSE DIRECTIONAL, WARNING, REGULATORY, SERVICE, AND STREET SIGNS	265.00	EACH
033	201.9901	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT - CENTERVILLE ROAD/DIAMOND HILL ROAD	1.00	LS
034	201.9902	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT - CENTERVILLE ROAD/TOLL GATE ROAD/GILBANE STREET	1.00	LS
035	201.9903	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT - CENTERVILLE ROAD/POST ROAD	1.00	LS
036	201.9905	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT - VETERAN'S MEMORIAL DRIVE/POST ROAD/POST ROAD EXTENSION	1.00	LS
037	201.9906	REMOVE AND STOCKPILE GRANITE CURB - CIRCULAR	876.00	LF
038	201.9907	REMOVE AND STOCKPILE GRANITE CURB RETURN	95.00	EACH
039	201.9908	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT - POST ROAD PEDESTRIAN SIGNAL (POST OFFICE)	1.00	LS
040	201.9910	REMOVE AND DISPOSE FIRE HYDRANT AND TEE	1.00	EACH
041	201.9914	REMOVE AND DISPOSE CIRCUIT CONDUCTORS	3,000.00	LF
042	201.9915	REMOVE AND DISPOSE MULCH	1,405.00	SY
043	201.9918	REMOVE AND STOCKPILE DECORATIVE POLE/LUMINAIRE	30.00	EACH
044	201.9919	REMOVE AND DISPOSE RAILROAD TIES	164.00	LF
045	201.9921	REMOVE AND DISPOSE GROUND COVER	604.00	SY
046	201.9922	REMOVE AND DISPOSE CRUSHED STONE	190.00	SY
047	201.9923	REMOVE AND DISPOSE BOULDER	10.00	EACH
048	201.9924	REMOVE AND DISPOSE SPOT LIGHT	2.00	EACH
049	201.9925	REMOVE AND DISPOSE RAILROAD TIE RETAINING WALL	290.00	LF
050	201.9926	REMOVE AND DISPOSE FLAGPOLE	1.00	EACH
051	201.9928	REMOVE AND DISPOSE METAL POLE	2.00	EACH
052	201.9929	REMOVE AND DISPOSE LIGHT	8.00	EACH
053	201.9930	REMOVE AND DISPOSE STEEL POST	37.00	EACH
054	201.9931	REMOVE AND DISPOSE PLANT	26.00	EACH
055	201.9932	REMOVE AND DISPOSE PLASTIC PLANTER	3.00	EACH
056	201.9933	REMOVE AND DISPOSE WOOD PLANTER	1.00	EACH
057	201.9934	REMOVE AND DISPOSE WOOD POST	2.00	EACH
058	201.9935	REMOVE AND DISPOSE BRICK POSTS	2.00	EACH
059	201.9936	REMOVE AND DISPOSE ELECTRIC OUTLET	1.00	EACH
060	201.9937	REMOVE AND DISPOSE BRICK WALL	40.00	LF
061	201.9940	REMOVE AND DISPOSE SIGN FOUNDATION	1.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
062	201.9942	REMOVE AND DISPOSE RIPRAP DITCH	41.00	CY
063	201.9943	REMOVE, STOCKPILE, AND RESET CAR STOP	3.00	EACH
064	201.9944	REMOVE AND DISPOSE GRANITE STEPS - LOT #3065	1.00	LS
065	201.9945	REMOVE AND DISPOSE CONCRETE STEPS - LOT #3103	1.00	LS
066	201.9946	REMOVE AND DISPOSE CONCRETE RETAINING WALL AND STEPS - LOT #3661	1.00	LS
067	201.9947	BUILDING DEMOLITION - 3033 POST ROAD	1.00	LS
068	201.9953	UNDERGROUND STORAGE TANK CLOSURE	1.00	LS
069	201.9954	REMOVE AND DISPOSE 6" CONCRETE SIDEWALK WIDTH BY HAND	318.00	LF
070	201.9955	REMOVE AND DISPOSE 6" BITUMINOUS SIDEWALK WIDTH BY HAND	2,419.00	LF
071	201.9956	REMOVE AND RESET PRIVATE SIGN	9.00	EACH
072	201.9957	REMOVE AND RESET PLASTIC PLANTER	3.00	EACH
073	201.9958	REMOVE AND STOCKPILE CAST IRON FENCE	110.00	LF
074	201.9959	REMOVE AND STOCKPILE PVC FENCE	36.00	LF
075	201.9960	REMOVE AND RESET BRICK PAVERS	5.00	SY
076	201.9961	ABANDON SEPTIC TANK	1.00	LS
077	201.9963	REMOVE,DISPOSE AND CAP IRRIGATION SYSTEM	7.00	EACH
078	201.9964	ASBESTOS ABATEMENT - 3033 POST ROAD	1.00	LS
S079	201.9965	ASBESTOS ABATEMENT - WATER TOWER	1.00	LS
080	201.9966	REMOVE AND DISPOSE OF SIDEWALK IN TREE AREAS	88.00	SY
081	201.9967	WATER TOWER DEMOLITION	1.00	LS
082	201.9968	REMOVE AND DISPOSE APPONAUG RIVER CULVERT	1.00	LS
083	201.9969	REMOVE AND REPLACE SLAB WITHIN SAWTOOTH BUILDING	1.00	LS
084	201.9970	REMOVE AND SALVAGE SERVICE PEDESTAL	1.00	LS
S085	201.9971	HANDLING, HAULING, AND STOCKPILING CONTAMINATED SOILS	1.00	LS
S086	201.9972	1,000 GALLON UNDERGROUND STORAGE TANK CLOSURES	1.00	LS
S087	201.9973	12,000 GALLON UNDERGROUND STORAGE TANK CLOSURES	1.00	LS
S088	201.9974	SITE PREPARATION - FORMER APPONAUG MILL PROPERTY REMOVE AND DISPOSE SUBSURFACE REINFORCED CONCRETE SLABS	1.00	LS
S089	201.9975	SITE PREPARATION - FORMER APPONAUG MILL PROPERTY REMOVE AND DISPOSE SUBSURFACE STRUCTURES	1.00	LS
S090	201.9976	SITE PREPARATION - FORMER APPONAUG MILL PROPERTY REMOVE AND DISPOSE MISCELLANEOUS SUBSURFACE MATERIALS	1.00	LS

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
091	202.0100	EARTH EXCAVATION	42,379.00	CY
092	202.0400	MUCK EXCAVATION	400.00	CY
093	202.0700	COMMON BORROW	34,543.00	CY
094	202.0800	GRAVEL BORROW	2,005.00	CY
095	202.9902	LOAD, HAUL AND DISPOSE SOIL, TYPE 1A	853.00	CY
S096	202.9903	LOAD AND HAUL CONTAMINATED SOIL, TYPE 1B	1,028.00	TON
S097	202.9904	DISPOSAL OF CONTAMINATED SOIL, TYPE 1B	1,028.00	TON
S098	202.9905	LOAD AND HAUL CONTAMINATED SOIL, TYPE 2	8,281.00	TON
S099	202.9906	DISPOSAL OF CONTAMINATED SOIL, TYPE 2	8,281.00	TON
S100	202.9907	LOAD, HAUL AND DISPOSE CONTAMINATED SOIL, TYPE 3	75.00	TON
101	202.9910	OFFSITE MATERIAL USED FOR SOIL BLENDING	7,367.00	CY
102	202.9912	UNCLASSIFIED EXCAVATION	20,968.00	CY
S103	202.9914	CONTAMINATED SOIL EXCAVATION	8,499.00	CY
S104	202.9916	COAL ASH EXCAVATION, STOCKPILE, AND DISPOSAL	110.00	CY
105	203.0100	STRUCTURAL EXCAVATION EARTH	5,000.00	CY
106	203.0600	FILL GRAVEL BORROW UNDER STRUCTURES	530.00	CY
107	203.0700	PERVIOUS FILL	5,250.00	CY
108	203.9901	DEWATERING - PROJECT WIDE	1.00	LS
109	203.9902	DEWATERING AND TREATMENT - AREAS WITH CONTAMINATED GROUNDWATER	1.00	LS
110	204.0100	TRIMMING AND FINE GRADING	154,700.00	SY
111	205.0240	TRENCH ROCK EXCAVATION (0-7')	100.00	CY
112	205.0250	TRENCH ROCK EXCAVATION (7-12')	100.00	CY
113	205.0260	TRENCH ROCK EXCAVATION (12'-D)	30.00	CY
114	206.0201	BALED HAY EROSION CHECK STANDARD 9.1.0	3,300.00	LF
115	206.0208	REMOVAL OF BALED HAY EROSION CHECKS	6,560.00	LF
116	206.0230	BALED HAY EROSION CHECK AND SILT FENCE COMBINED STANDARD 9.3.0	9,820.00	LF
117	206.9901	COMPOST FILTER SOCK - 18 INCH DIAMETER	4,180.00	LF
118	206.9903	SILT FENCE TYPE II	160.00	LF
S119	206.9904	TURBIDITY CONTROL CURTAIN	260.00	LF
120	208.0100	DEWATERING BASIN STANDARD 9.7.0	2,448.00	SF
121	208.9901	DRY SOIL STOCKPILE - CONTAMINATED SOIL	10,000.00	SF
122	208.9902	WET SOIL STOCKPILE - CONTAMINATED SOIL	10,000.00	SF

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
123	208.9903	WET SOIL STOCKPILE - COMPLIANT SOIL	10,000.00	SF
124	208.9904	20 MIL. HDPE ALLOY LINER	330.00	SY
125	209.0110	BALED HAY CATCH BASIN INLET PROTECTION STANDARD 9.8.0	100.00	LF
126	209.9901	GORTON POND SEDIMENT REMOVAL AND MANAGEMENT	1.00	LS
127	209.9911	FILTER BAG FOR CATCH BASIN	259.00	EACH
128	211.0100	CONSTRUCTION ACCESSES STANDARD 9.9.0	550.00	SY
129	211.9901	VEHICLE WHEEL WASHING FACILITY	5.00	EACH
130	212.2000	CLEANING AND MAINTENANCE OF EROSION CONTROLS	1.00	LS
131	213.0100	PLACEMENT OF MILLINGS BENEATH GUARDRAIL	3,160.00	LF
132	301.0300	CRUSHED STONE OR CRUSHED GRAVEL BASE MODIFIED	91.00	CY
133	302.0100	GRAVEL BORROW SUBBASE COURSE	38,383.00	CY
134	303.0100	SPECIAL GRADED AGGREGATE FOR SHAPING AND TRIMMING DRIVEWAYS OR SHOULDERS	16.00	CY
135	303.9901	CHIP STONE	90.00	CY
136	303.9902	GRADED SCREENED AGGREGATE	90.00	CY
137	401.9902	CLASS 19.0 HOT MIX ASPHALT	3,000.00	TON
138	401.9903	CLASS 9.5 HOT MIX ASPHALT	1,211.00	TON
139	401.9905	CLASS 19.0 WITH PAY ADJUSTMENTS	25,096.00	TON
140	401.9906	MODIFIED CLASS 12.5 WITH PAY ADJUSTMENTS	11,563.00	TON
141	403.0300	ASPHALT EMULSION TACK COAT	146,080.00	SY
142	601.0300	CLASS A PORTLAND CEMENT CONCRETE	1,212.00	CY
143	603.1000	CONTROLLED LOW STRENGTH MATERIAL	400.00	CY
144	701.0612	REINFORCED CONCRETE PIPE M 170 CLASS V 12 INCH	7,860.00	LF
145	701.0618	REINFORCED CONCRETE PIPE M 170 CLASS V 18 INCH	3,730.00	LF
146	701.0624	REINFORCED CONCRETE PIPE M 170 CLASS V 24 INCH	1,513.00	LF
147	701.0630	REINFORCED CONCRETE PIPE M 170 CLASS V 30 INCH	425.00	LF
148	701.0636	REINFORCED CONCRETE PIPE M 170 CLASS V 36 INCH	1,118.00	LF
149	701.0642	REINFORCED CONCRETE PIPE M 170 CLASS V 42 INCH	30.00	LF
150	701.0648	REINFORCED CONCRETE PIPE M 170 CLASS V 48 INCH	54.00	LF
151	701.5206	6 INCH DUCTILE IRON WATER PIPE CLASS 52, RESTRAINED JOINT	172.00	LF
152	701.5212	12 INCH DUCTILE IRON WATER PIPE CLASS 52, RESTRAINED JOINT	240.00	LF
153	701.7712	12 INCH REINFORCED CONCRETE PIPE END SECTION STANDARD 2.3.0	5.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
154	701.7718	18 INCH REINFORCED CONCRETE PIPE END SECTION STANDARD 2.3.0	1.00	EACH
155	701.7724	24 INCH REINFORCED CONCRETE PIPE END SECTION STANDARD 2.3.0	2.00	EACH
156	701.7730	30 INCH REINFORCED CONCRETE PIPE END SECTION STANDARD 2.3.0	1.00	EACH
157	701.7742	42 INCH REINFORCED CONCRETE PIPE END SECTION STANDARD 2.3.0	1.00	EACH
158	701.8002	PIPE BEDDING CLASS B	220.00	CY
159	701.8003	PIPE BEDDING CLASS C	660.00	CY
160	701.8100	FURNISH AND INSTALL DUCTILE IRON FITTINGS	2,850.00	LBS
161	701.8106	6 INCH GATE VALVE AND BOX	7.00	EACH
162	701.8112	12 INCH GATE VALVE AND BOX	2.00	EACH
163	701.8150	TYPE K COPPER SERVICE PIPE	300.00	LF
164	701.8151	CURB STOP BOX	35.00	EACH
165	701.9001	CONDUCT LEAKAGE TEST	3.00	EACH
166	701.9002	STERILIZATION OF WATER MAINS	1.00	LS
167	701.9901	CURB STOP AND BOX	9.00	EACH
168	701.9904	12 INCH TRANSITION COUPLING	4.00	EACH
169	701.9905	12" PIPE INSULATION	90.00	LF
170	702.0511	FRAME AND COVER STANDARD 6.1.0	20.00	EACH
171	702.0514	FRAME AND GRATE STANDARD 6.4.0	1.00	EACH
172	702.0516	FRAME AND GRATE, HIGH CAPACITY, STANDARD 6.3.4	205.00	EACH
173	702.0517	FRAME AND GRATE, STANDARD 6.3.2	11.00	EACH
174	702.0522	FRAME AND COVER STANDARD 6.2.1	45.00	EACH
175	702.0541	GRANITE INLET STONE 38" STANDARD 7.3.6	21.00	EACH
176	702.0542	GRANITE APRON STONE 5FT. STANDARD 7.3.7	2.00	EACH
177	702.0543	GRANITE APRON STONE 38" STANDARD 7.3.8	175.00	EACH
178	702.0605	PRECAST CATCH BASIN 4' DIAMETER STANDARD 4.4.0	176.00	EACH
179	702.0610	PRECAST CATCH BASIN 5' DIAMETER STANDARD 4.4.0	5.00	EACH
180	702.0615	PRECAST CATCH BASIN 6' DIAMETER STANDARD 4.4.0	1.00	EACH
181	702.0625	PRECAST CATCH BASIN 6' SQUARE STANDARD 4.3.0	2.00	EACH
182	702.0630	PRECAST MANHOLE 4' DIAMETER STANDARD 4.2.0	19.00	EACH
183	702.0640	PRECAST MANHOLE 6' DIAMETER STANDARD 4.2.2	13.00	EACH
184	702.0650	PRECAST MANHOLE 6' SQUARE STANDARD 4.3.0	3.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
185	702.0705	CATCH BASIN W/GUTTER INLET STANDARD 3.4.1	17.00	EACH
186	702.0712	PRECAST CONCRETE DROP INLET STANDARD 4.5.0	3.00	EACH
187	702.0713	PRECAST CONCRETE DROP INLET WITH APRON STONE STANDARD 4.5.1	3.00	EACH
188	702.0714	PRECAST CONCRETE DROP INLET WITH APRON STONE STANDARD 4.5.2	18.00	EACH
189	702.0750	MANHOLES, CATCH BASINS & INLETS DEPTHS GREATER THAN 12' STANDARD 3.7.0	4.00	VLF
190	702.9901	12" DUCTILE IRON DRAINAGE PIPE CLASS 52	348.00	LF
191	702.9902	18" DUCTILE IRON DRAINAGE PIPE CLASS 52	64.00	LF
192	702.9903	PRECAST MANHOLE AND CATCH BASIN DEPTHS GREATER THAN 12 FEET	4.00	VLF
193	702.9904	ANTI-SEEP COLLAR	3.00	EACH
194	702.9911	ECCENTRIC PLUG VALVE & BOX	1.00	EACH
195	702.9912	DISCHARGE STRUCTURE NO. 1	1.00	EACH
196	702.9913	DISCHARGE STRUCTURE NO. 2	1.00	EACH
197	702.9914	DISCHARGE STRUCTURE NO. 3	1.00	EACH
198	702.9915	APPONAUG BYPASS SPILLWAY STRUCTURE	1.00	LS
199	702.9916	APPONAUG UPPER DAM STRUCTURE	1.00	LS
200	702.9918	INSTALL 12" WELDED STEEL GAS MAIN AND FITTINGS	169.00	LF
201	702.9919	36" DUCTILE IRON DRAINAGE PIPE CLASS 52	94.00	LF
202	702.9920	24" DUCTILE IRON DRAINAGE PIPE CLASS 52	382.00	LF
203	702.9921	EXCAVATE, CUT, REMOVE, STOCKPILE AND DISPOSE GAS PIPE	2,085.00	LF
204	706.9000	PLUG AND CAP PIPE ALL SIZES	23.00	EACH
205	707.0900	ADJUST MANHOLES TO GRADE	48.00	EACH
206	707.0950	ADJUST TELEPHONE MANHOLE TO GRADE	42.00	EACH
207	707.1000	ADJUST SANITARY MANHOLE	110.00	EACH
208	707.1100	ADJUST CATCH BASINS	32.00	EACH
209	707.1200	ADJUST CATCH BASIN TO MANHOLE	6.00	EACH
210	708.9040	CLEANING AND FLUSHING PIPE ALL SIZES	7,230.00	LF
211	708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	27.00	EACH
212	708.9042	CLEANING MANHOLES ALL TYPES AND SIZES	17.00	EACH
213	709.0100	CONCRETE CONNECTING COLLAR STANDARD 1.3.0	2.00	CY
214	709.8103	FURNISH & INSTALL CEMENT CONCRETE CLASS B THRUST & ANCHOR BLOCKS CAST-IN-PLACE	7.00	CY

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
215	709.9902	INSPECTION, GPS AND DOCUMENTATION - STRUCTURE	53.00	EACH
216	709.9903	INSPECTION, GPS AND DOCUMENTATION - OUTFALL	9.00	EACH
217	709.9904	INSPECTION, GPS AND DOCUMENTATION - PIPE	7,230.00	LF
218	712.0100	WATER GATE BOX	16.00	EACH
219	712.0200	GAS GATE BOX	12.00	EACH
220	713.8268	ADJUST CURB STOP BOX TO GRADE	164.00	EACH
221	713.8269	ADJUST WATER GATE BOXES TO GRADE	76.00	EACH
222	713.8300	ADJUST GAS GATE BOXES TO GRADE	57.00	EACH
223	713.9901	ADJUST MONITORING WELL TO GRADE	2.00	EACH
224	714.8163	POST TYPE HYDRANT	7.00	EACH
225	714.8263	REMOVE AND RELOCATE POST TYPE HYDRANT	6.00	EACH
226	799.9901	EARTH EXCAVATION & REFILL FOR TEST PITS	1,600.00	CY
227	799.9902	BORROW GRAVEL	2,100.00	CY
228	799.9903	EXCAVATION & REMOVAL OF BOULDERS	400.00	CY
229	799.9904	ROCK EXCAVATION (MECHANICAL)	100.00	CY
230	799.9905	HAY BALES AROUND CATCH BASINS	500.00	LF
231	799.9906	CALCIUM CHLORIDE FOR DUST CONTROL	3,500.00	LBS
232	799.9907	12" D.I. WATER MAIN	700.00	LF
233	799.9908	8" D.I. WATER MAIN	4,350.00	LF
234	799.9909	8" D.I. WATER MAIN W/2" FOAMGLASS INSULATION	30.00	LF
235	799.9910	6" D.I. WATER MAIN	250.00	LF
236	799.9911	4" D.I. WATER MAIN	100.00	LF
237	799.9912	12 X 12 TEES	2.00	EACH
238	799.9913	12 X 6 TEES	1.00	EACH
239	799.9914	12 X 12 CROSS	1.00	EACH
240	799.9915	8 X 8 TEES	4.00	EACH
241	799.9916	8 X 6 TEES	10.00	EACH
242	799.9917	8 X 4 TEES	2.00	EACH
243	799.9918	12" ELBOWS	10.00	EACH
244	799.9919	8" ELBOWS	20.00	EACH
245	799.9920	6" ELBOWS	6.00	EACH
246	799.9921	4" ELBOWS	6.00	EACH
247	799.9922	12 X 8 REDUCERS	3.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
248	799.9923	8 X 6 REDUCERS	3.00	EACH
249	799.9924	8 X 4 REDUCERS	1.00	EACH
250	799.9925	12" PERMANENT CAPS	2.00	EACH
251	799.9926	8" PERMANENT CAPS	6.00	EACH
252	799.9927	6" PERMANENT CAPS	10.00	EACH
253	799.9928	4" PERMANENT CAPS	10.00	EACH
254	799.9929	12" GATE VALVES & VALVE BOXES	10.00	EACH
255	799.9930	8" GATE VALVES & VALVE BOXES	10.00	EACH
256	799.9931	6" GATE VALVES & VALVE BOXES	12.00	EACH
257	799.9932	4" GATE VALVES & VALVE BOXES	2.00	EACH
258	799.9933	2" PERMANENT BLOW-OFF ASSEMBLIES	1.00	EACH
259	799.9934	1" PERMANENT BLOW-OFF ASSEMBLIES	1.00	EACH
260	799.9935	HYDRANTS	3.00	EACH
261	799.9936	HYDRANTS (6' BURY)	1.00	EACH
262	799.9937	1½" CORPORATION STOPS	5.00	EACH
263	799.9938	1" CORPORATION STOPS	5.00	EACH
264	799.9939	3/4" CORPORATION STOPS	40.00	EACH
265	799.9940	1½" CURB STOPS & BOXES	5.00	EACH
266	799.9941	1" CURB STOPS & BOXES	5.00	EACH
267	799.9942	3/4" CURB STOPS & BOXES	40.00	EACH
268	799.9943	1½" WATER SERVICE LINE & SERVICE	150.00	LF
269	799.9944	1" WATER SERVICE LINE	100.00	LF
270	799.9945	1" WATER SERVICE LINE W/2" FOAMGLASS INSULATION	50.00	LF
271	799.9946	3/4" WATER SERVICE LINE	1,000.00	LF
272	799.9947	3/4" WATER SERVICE LINE W/2" FOAMGLASS INSULATION	100.00	LF
273	799.9948	6" TEMPORARY WATER SYSTEM	1,100.00	LF
274	799.9949	2" TEMPORARY WATER SYSTEM	900.00	LF
275	799.9950	REPLACE EXIST. 8" SEWER PIPE WITH D.I. PIPE	20.00	LF
276	799.9951	REPLACE EXIST. 6" SEWER PIPE WITH DI PIPE INCLUDING FITTINGS	40.00	LF
277	799.9952	2" TEMP. BIT. CONCRETE PAVEMENT	5,300.00	SY
278	799.9953	R & D CONCRETE BASE	5,300.00	SY
279	799.9954	SOIL COMPACTION TESTING OF TRENCHES	1.00	LS
280	799.9955	REM. & DISPOSE EXIST. ASBESTOS CEMENT PIPE	100.00	LF

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
281	799.9956	F & I TRAFFIC LOOPS	100.00	LF
282	799.9957	R & D HYDRANT ASSEMBLIES	3.00	EACH
283	800.9901	APPONAUG RIVER BRIDGE NO. 1038	1.00	LS
284	800.9902	REHABILITATION OF APPONAUG MILL BRIDGE NO. 138	1.00	LS
285	803.9910	REMOVE AND DISPOSE CONCRETE	301.00	CY
286	803.9911	REMOVE AND DISPOSE MASONRY	64.00	CY
287	803.9912	REMOVE AND RESET MASONRY	15.00	CY
288	808.0800	CONCRETE RETAINING WALL CLASS HP 3/4" STANDARD 10.3.0	52.00	CY
289	808.9901	CONCRETE RETAINING WALL RI STD. 10.3.0 MODIFIED	130.00	CY
290	817.2110	REPAIRS TO STRUCTURAL CONCRETE MASONRY (PATCHING MORTAR)	50.00	CF
291	818.2020	PORTLAND CEMENT CONCRETE DECK REPAIRS (PARTIAL DEPTH REMOVAL)	100.00	SF
292	819.0800	DRILL AND GROUT REINFORCING DOWELS	100.00	EACH
293	831.9901	PVC COATED CHAIN LINK FENCE ON WALL - 4 FOOT	881.00	LF
S294	901.0101	GUARDRAIL STEEL BEAM SINGLE FACE EARTH AND ASPHALT	2,497.00	LF
295	901.0165	STEEL BEAM GUARDRAIL SECTION (12.5 FT. BY 12.0 INCHES)	40.00	EACH
S296	901.0190	GUARDRAIL STEEL BEAM ANCHORAGE APPROACH SECTION STANDARDS 34.3.1 AND 34.3.3	2.00	EACH
S297	901.0191	GUARDRAIL STEEL BEAM ANCHORAGE TRAILING END SECTION STANDARD 34.3.4	10.00	EACH
S298	901.0198	GUARDRAIL END TREATMENT, NON-ENERGY ABSORBING TERMINAL	4.00	EACH
S299	901.9901	GUARDRAIL STEEL BEAM SINGLE FACE EARTH AND ASPHALT WITH 9-FOOT POSTS	385.00	LF
S300	901.9902	APPROACH SECTION WITH NESTED RAIL	4.00	EACH
S301	903.0206	CHAIN LINK FENCE 6' STD 31.2.0	2,080.00	LF
S302	903.0227	GATE, CHAIN LINK 6' STANDARD 31.2.0	3.00	EACH
303	903.9901	PVC COATED CHAIN LINK FENCE - 4 FOOT	36.00	LF
304	903.9903	TEMPORARY CHAIN LINK FENCE, 6 FT. HIGH	4,340.00	LF
S305	903.9904	TEMPORARY CHAIN LINK FENCE GATE, 6 FT. HIGH, 20 FT. WIDE	5.00	EACH
306	905.0110	PORTLAND CEMENT SIDEWALK MONOLITHIC STANDARD 43.1.0	1,648.00	CY
307	905.0115	PORTLAND CEMENT CONCRETE DRIVEWAY STANDARD 43.5.0	584.00	CY
308	905.9901	INTEGRALLY COLORED AND STAMPED CONCRETE SIDEWALK BAND OR WHEELCHAIR RAMP 4 INCH DEPTH	60.00	CY
309	905.9907	INTEGRALLY COLORED AND STAMPED CONCRETE 8 INCH DEPTH	823.00	CY

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
310	905.9908	INTEGRALLY COLORED AND STAMPED CONCRETE 4 INCH DEPTH	275.00	CY
311	906.0100	SLOPE FACED GRANITE CURB - QUARRY SPLIT STRAIGHT STANDARD 7.4.0	532.00	LF
312	906.0101	SLOPE FACED GRANITE CURB - QUARRY SPLIT CIRCULAR STANDARD 7.4.0	563.00	LF
313	906.0102	SLOPE FACED GRANITE TRANSITION CURB STANDARD 7.4.1	4.00	EACH
314	906.0103	GRANITE TRANSITION CURB VERTICAL FACE TO SLOPED FACE STANDARD 7.4.2	12.00	EACH
315	906.0110	GRANITE CURB, QUARRY SPLIT STRAIGHT, STANDARD 7.3.0	13,549.00	LF
316	906.0111	GRANITE CURB, QUARRY SPLIT CIRCULAR, STANDARD 7.3.0	4,364.00	LF
317	906.0116	GRANITE CURB, QUARRY SPLIT 2 FOOT CORNERS, STANDARD 7.3.4	2.00	EACH
318	906.0118	6' GRANITE TRANSITION CURB, QUARRY SPLIT SPECIAL TRANSITION STANDARD 7.3.2	125.00	EACH
319	906.0119	3' GRANITE TRANSITION CURB STANDARD 7.3.1	144.00	EACH
320	906.0120	GRANITE WHEELCHAIR RAMP CURB STANDARDS 7.3.3, 43.3.0 AND 43.3.1	2.00	EACH
321	906.0130	GRANITE RAMP STONE STRAIGHT STANDARD 7.3.9	40.00	EACH
322	906.0131	GRANITE RAMP STONE CIRCULAR STANDARD 7.3.9	68.00	EACH
323	906.0210	CEMENT CONCRETE CURB PRECAST STRAIGHT STANDARD 7.1.0	1,841.00	LF
324	906.0211	CEMENT CONCRETE CURB PRECAST CIRCULAR STANDARD 7.1.0	104.00	LF
325	906.0221	6' PRECAST CONCRETE TRANSITION CURB STANDARD 7.1.2	6.00	EACH
326	906.0263	PRECAST CONCRETE RAMP STONE 18-INCH CIRCULAR STANDARD 7.1.9	3.00	EACH
327	906.0280	3' PRECAST CONCRETE TRANSITION CURB STANDARD 7.1.1	42.00	EACH
328	906.0561	CEMENT CONCRETE EDGING 18 INCH LOT CURB STANDARD 7.2.3	52.00	LF
329	906.0562	CEMENT CONCRETE EDGING 24 INCH LOT CURB STANDARD 7.2.3	155.00	LF
330	906.0600	BITUMINOUS CURBING STANDARD 7.5.0	227.00	LF
331	906.0602	BITUMINOUS BERM STANDARD 7.5.1	999.00	LF
332	906.0700	REMOVE, HANDLE, HAUL TRIM RESET CURB EDGING, STRAIGHT, CIRCULAR ALL TYPES	6,419.00	LF
333	906.9901	SLOPE FACED GRANITE CURB - QUARRY SPLIT STRAIGHT STANDARD 7.4.0 MODIFIED	288.00	LF
334	906.9902	SLOPE FACED GRANITE CURB - QUARRY SPLIT CIRCULAR STANDARD 7.4.0 MODIFIED	1,756.00	LF
335	906.9903	SLOPE FACED GRANITE TRANSITION CURB STANDARD 7.4.1 - CIRCULAR	6.00	EACH
336	906.9904	3' GRANITE TRANSITION CURB STANDARD 7.3.1 - CIRCULAR	16.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
337	906.9905	6' GRANITE TRANSITION CURB, QUARRY SPLIT SPECIAL TRANSITION STANDARD 7.3.2 - CIRCULAR	70.00	EACH
338	906.9906	GRANITE WHEELCHAIR RAMP CURB STANDARD 7.3.3 - CIRCULAR	36.00	EACH
339	906.9907	6' PRECAST CONCRETE TRANSITION CURB STANDARD 7.1.2 - CIRCULAR	2.00	EACH
340	906.9908	PRECAST CONCRETE WHEELCHAIR RAMP CURB STANDARD 7.1.3 - CIRCULAR	3.00	EACH
341	906.9909	BICYCLE RAMP GRANITE RAMP STONE STANDARD 7.3.9 MODIFIED	19.00	EACH
342	907.0100	WATER FOR DUST CONTROL	1,945.00	MGAL
343	907.0200	CALCIUM CHLORIDE FOR DUST CONTROL (PROJECT WIDE)	210.00	TON
344	908.0100	FLAGSTONE-BLUE STONE TREADS	149.00	SF
345	911.0100	WET STONE MASONRY RETAINING WALL STANDARD 10.1.0	267.00	CY
346	911.0101	STONE MASONRY STEPS STANDARD 10.4.0	11.00	CY
347	911.3200	REMOVE AND RESET WET STONE MASONRY WALLS	9.00	CY
348	911.9901	MODIFIED WET STONE MASONRY RETAINING WALL STD. 10.1.0	395.00	CY
349	911.9902	MODIFIED RUBBLE MASONRY WALL STD. 10.2.0	125.00	CY
350	911.9903	PRECAST CONCRETE MODULAR WALL	6,630.00	SF
351	914.5010	FLAGPERSONS	21,310.00	MHRS
352	914.5020	FLAGPERSONS - OVERTIME	2,100.00	MHRS
353	915.0200	HIGHWAY BOUNDS REINFORCED CONCRETE STANDARD 14.1.0	112.00	EACH
354	916.0600	SHOCK ABSORBING BARRIER MODULES	3.00	GRP
355	916.0650	REMOVE, RELOCATE AND RESET SHOCK ABSORBING BARRIER MODULES	1.00	GRP
356	916.9901	FURNISH AND INSTALL NON-GATING IMPACT ATTENUATOR	1.00	EACH
357	919.0101	TEST PITS	120.00	EACH
358	920.0040	DUMPED STONE RIPRAP R-3, R-4, R-5 STANDARD 8.3.0	260.00	SY
359	920.0135	BEDDING FOR RIPRAP FS-2 STANDARD 8.3.0	260.00	SY
360	920.0200	FILTER FABRIC FOR RIP-RAP	310.00	SY
361	920.9901	ARTICULATED CONCRETE BLOCK, (ACB MATS) OPEN CELL	3,735.00	SY
362	920.9902	ARTICULATED CONCRETE BLOCK, (ACB MATS) CLOSED CELL	1,080.00	SY
363	920.9903	NON-WOVEN FILTER FABRIC	4,815.00	SY
364	920.9904	GABIONS	110.00	CF
365	920.9905	GROUTED RIP-RAP	83.00	CY
366	920.9906	NON-WOVEN GEOTEXTILE FABRIC - CAPPED AREAS	15,150.00	SY

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
367	922.0100	TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1	1,363.00	SF
368	923.0105	DRUM BARRICADE STANDARD 26.2.0	75,000.00	BDAY
369	923.0120	PLASTIC PIPE BARRICADE STANDARD 26.3.0	50.00	EACH
370	923.0200	FLUORESCENT TRAFFIC CONES STANDARD 26.1.0	600.00	EACH
371	924.0113	ADVANCE WARNING ARROW PANEL	850.00	PDAY
372	925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	8,500.00	PDAY
373	926.0130	PRECAST MEDIAN BARRIER FOR TEMPORARY TRAFFIC CONTROL STANDARD 40.5.0	6,000.00	LF
374	928.0800	TRUCK MOUNTED ATTENUATOR WITH TRUCK MOUNTED FLASHING ARROW BOARD	100.00	PDAY
375	929.0110	FIELD OFFICE	46.00	PMO
376	931.0110	CLEANING AND SWEEPING PAVEMENT	760.00	HSY
377	932.0100	CUTTING AND MATCHING ASPHALT	865.00	LF
378	932.0101	CUTTING AND MATCHING CONCRETE	79.00	LF
379	932.0200	FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT	26,950.00	LF
380	932.0210	FULL DEPTH SAWCUT OF BITUMINOUS PAVEMENT AND RIGID BASE	13,080.00	LF
381	932.0220	FULL DEPTH SAWCUT OF BITUMINOUS SIDEWALK/DRIVEWAY	5,475.00	LF
382	932.0230	FULL DEPTH SAWCUT OF PORTLAND CEMENT CONCRETE SIDEWALK/DRIVEWAY	87.00	LF
383	935.0400	REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING	13,780.00	SY
384	936.0110	MOBILIZATION	1.00	LS
385	937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	1.00	LS
386	942.9901	CAST IRON DETECTABLE WARNING SYSTEM	1,021.00	SF
387	943.0200	TRAINEE MAN-HOURS	10,000.00	MHRS
S388	998.9901	CAST ALUMINUM LETTERING	96.00	EACH
S389	999.9903	STEEL PLANTERS	42.00	EACH
390	L01.0102	LOAM BORROW 4 INCHES DEEP	7,375.00	SY
391	L01.0104	PLANTABLE SOIL 4 INCHES DEEP	23,150.00	SY
S392	L01.9901	PLANTING BED LOAM - 24" DEPTH (ROUNDABOUTS)	1,045.00	CY
S393	L01.9902	PLANTING BED LOAM - 20" DEPTH (STEEL PLANTERS)	41.00	CY
S394	L01.9903	PLANTING BED LOAM - 12" DEPTH (MEDIANS / DEF. ISL.)	877.00	CY
S395	L01.9904	PLANTING BED LOAM - 6" DEPTH (ROUNDABOUTS)	239.00	CY
S396	L01.9905	PLANTABLE SOIL - 24" DEPTH (ROUNDABOUTS)	1,021.00	CY
S397	L01.9906	PLANTABLE SOIL - 10" DEPTH (STEEL PLANTERS)	21.00	CY

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
S398	L01.9907	PLANTABLE SOIL - 6" DEPTH (ROUNDABOUTS)	239.00	CY
S399	L01.9909	BIORETENTION SOIL	350.00	SY
S400	L01.9910	HIGH ORGANIC SOIL 6" DEPTH	3,050.00	SY
S401	L02.0101	GENERAL HIGHWAY SEEDING (TYPE 1)	23,150.00	SY
S402	L02.0102	RESIDENTIAL SEEDING (TYPE 2)	7,400.00	SY
S403	L02.0103	TEMPORARY SEEDING (TYPE 3)	2,500.00	SY
S404	L02.0105	WETLAND SEED MIX (TYPE 5)	3,050.00	SY
S405	L04.0514	FERTILIZATION OF SEEDED AND GRASSED AREAS	7.00	ACRE
S406	L05.0502	ADHESIVE MULCH STABILIZER	2.00	ACRE
407	L05.0506	JUTE MESH	7,790.00	SY
408	L05.9901	TURF REINFORCEMENT MAT	4,300.00	SY
409	L06.0513	WOOD CHIPS FURNISH AND SPREAD 4" DEPTH	671.00	SY
S410	L06.9901	AMELANCHIER CANADENSIS - CLUMP 7'-8' HT. B&B	8.00	EACH
S411	L06.9902	AMELANCHIER CANADENSIS - CLUMP 4'-5' HT. B&B	42.00	EACH
S412	L06.9903	ACER X FREEMANI 'ARMSTRONG' 3"-3.5" CAL. B&B	53.00	EACH
S413	L06.9904	ACER RUBRUM 'OCTOBER GLORY' 2"-2.5" CAL. B&B	29.00	EACH
S414	L06.9905	BETULA NIGRA 'CULLY' - CLUMP 14'-16' HT. B&B	14.00	EACH
S415	L06.9906	BETULA NIGRA 'CULLY' - CLUMP 12'-14' HT. B&B	13.00	EACH
S416	L06.9907	BETULA NIGRA 'CULLY' - CLUMP 10'-12' HT. B&B	16.00	EACH
S417	L06.9908	GLEDITSIA TRIA. 'SHADEMASTER' 3"-3.5" CAL. B&B	8.00	EACH
S418	L06.9909	LIRIODENDRON TULIPIFERA 2"-2.5" CAL. B&B	24.00	EACH
S419	L06.9910	NYSSA SYLVATICA 2"-2.5" CAL. B&B	15.00	EACH
S420	L06.9911	ULMUS HYBRIDA 'COMMENDATION' 3"-3.5" CAL. B&B	43.00	EACH
S421	L06.9912	ULMUS HYBRIDA 'HOMESTEAD' 3"-3.5" CAL. B&B	49.00	EACH
S422	L06.9913	ULMUS AMERICANA 'PRINCETON' 3"-3.5" CAL. B&B	23.00	EACH
S423	L06.9915	ABIES CONCOLOR 7'-8' HT. B&B	3.00	EACH
S424	L06.9916	JUNIPERUS VIRGINIANA 5'-6' HT. B&B	43.00	EACH
S425	L06.9917	PINUS STROBUS 7'-8' HT. B&B	17.00	EACH
S426	L06.9918	TSUGA CANADENSIS 5'-6' HT. B&B	5.00	EACH
S427	L06.9919	CLETHRA ALNIFOLIA 24"-30" HT. CONT.	121.00	EACH
S428	L06.9920	CORNUS SERICEA 'CARDINAL' 24"-30" HT. CONT.	299.00	EACH
S429	L06.9921	ILEX GLABRA 'SHAMROCK' 18"-24" HT. CONT.	769.00	EACH
S430	L06.9922	ILEX VERTICILLATA 'WINTER RED' 24"-30" HT. CONT.	226.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
S431	L06.9923	JUNIPERUS VIRGINIANA 'GREY OWL' 24"-30" HT. CONT.	45.00	EACH
S432	L06.9924	MYRICA PENSYLVANICA 24"-30" HT. CONT.	281.00	EACH
S433	L06.9925	PRUNUS MARITIMA 24"-30" HT. CONT.	49.00	EACH
S434	L06.9926	TAXUS BACCATA 'REPANDENS' 18"-24" SP. CONT.	196.00	EACH
S435	L06.9927	VIBURNUM DENTATUM 24"-30" HT. CONT.	283.00	EACH
S436	L06.9928	CAREX MORROWII 'ICE DANCE' #1 CONT.	5,419.00	EACH
S437	L06.9929	FESTUCA GLAUCA 'ELIJAH BLUE' #1 CONT.	8,817.00	EACH
S438	L06.9931	MUHLENBERGIA CAPILLARIS #2 CONT.	2,508.00	EACH
S439	L06.9932	PENNISETUM ALOPECUROIDES 'HAMELN' #2 CONT.	1,764.00	EACH
S440	L06.9933	PENNISETUM ALOPECUROIDES 'LITTLE BUNNY' #1 CONT.	3,938.00	EACH
S441	L06.9934	GINKGO BILOBA 'PRINCETON SENTRY' 3"-3.5" CAL. B&B	8.00	EACH
S442	L06.9935	RUDBECKIA HIRTA #1 CONT.	414.00	EACH
S443	L06.9936	HEDERA HELIX 'BALTICA' INDIVIDUAL CUTTING IN FLAT	1,344.00	EACH
S444	L07.9901	EXTENDED ESTABLISHMENT PERIOD	16.00	PMO
S445	L08.0109	TREE TRIMMING	80.00	MHRS
S446	L08.0110	TREE TRIMMING FOR UTILITIES	120.00	CHRS
447	L11.0102	TREE PLANT PROTECTION DEVICE STANDARD 51.1.0	75.00	EACH
448	L11.0103	SHRUB PLANT PROTECTION DEVICE STANDARD 51.2.0	1,100.00	LF
S449	L15.9901	TRIMMING TREE ROOTS IN SENSITIVE TREE ROOT AREA	80.00	LF
S450	T01.9901	RELOCATION OF SECONDARY ELECTRIC AND COMMUNICATIONS SERVICE – GAS STATION	1.00	LS
S451	T01.9902	RELOCATION OF SECONDARY ELECTRIC AND COMMUNICATION SERVICES – WAVE CREDIT UNION	1.00	LS
452	T01.9904	RELOCATION OF 2-4" CONCRETE ENCASED CITY COMMUNICATION CONDUITS	90.00	LF
S453	T04.5001	6 AWG SINGLE CONDUCTOR CABLE 600V INSULATION	806.00	LF
S454	T04.5302	14 AWG 2 CONDUCTOR TWISTED SHIELDED CABLE	737.00	LF
S455	T04.5303	14 AWG 3 CONDUCTOR CABLE	476.00	LF
S456	T04.5305	14 AWG 5 CONDUCTOR CABLE	1,907.00	LF
S457	T04.6902	'2' STRANDED COPPER CONDUCTOR 600V INSULATION	30,005.00	LF
S458	T04.6906	'6' STRANDED COPPER CONDUCTOR 600V INSULATION	10,275.00	LF
S459	T04.7500	SPLICE KIT	490.00	EACH
S460	T04.9901	OPTICAL DETECTOR CABLE	344.00	LF
S461	T05.0100	PRECAST TYPE A HANDHOLE STANDARD 18.2.0	172.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
S462	T05.0300	PRECAST TYPE B HEAVY DUTY HANDHOLE STANDARD 18.2.2	6.00	EACH
463	T05.1030	ADJUST HANDHOLE TO GRADE	7.00	EACH
S464	T05.9901	FIBER OPTIC HANDHOLE	25.00	EACH
S465	T05.9902	FIBER OPTIC SPLICE MANHOLE	7.00	EACH
S466	T06.1020	2 IN. RIGID STEEL CONDUIT - UNDERGROUND	670.00	LF
S467	T06.1030	3 IN. RIGID STEEL CONDUIT-UNDERGROUND	156.00	LF
S468	T06.2020	2 IN. RIGID STEEL CONDUIT-OVERHEAD	65.00	LF
S469	T06.5120	2 INCH SCHEDULE 40 POLYVINYL CHLORIDE PLASTIC CONDUIT - UNDERGROUND	2,820.00	LF
S470	T06.5130	3 INCH SCHEDULE 40 POLYVINYL CHLORIDE PLASTIC CONDUIT - UNDERGROUND	5,695.00	LF
S471	T06.5230	3 INCH SCHEDULE 80 POLYVINYL CHLORIDE PLASTIC CONDUIT - UNDERGROUND	1,962.00	LF
472	T06.5240	4 INCH SCHEDULE 80 POLYVINYL CHLORIDE PLASTIC CONDUIT - UNDERGROUND	5,030.00	LF
S473	T06.5420	2 INCH SCHEDULE 80 POLYVINYL CHLORIDE PLASTIC CONDUIT - UNDER EXISTING PAVEMENT	245.00	LF
S474	T06.5430	3 INCH SCHEDULE 80 POLYVINYL CHLORIDE PLASTIC CONDUIT - UNDER EXISTING PAVEMENT	1,530.00	LF
S475	T06.6020	2 INCH POLYVINYL CHLORIDE PLASTIC CONDUIT-OVERHEAD	90.00	LF
S476	T06.9901	RADAR VEHICLE DETECTOR	3.00	EACH
S477	T06.9902	SOLAR POWER EQUIPMENT	1.00	EACH
S478	T07.1250	FURNISH AND INSTALL 250 WATT HIGH PRESSURE SODIUM LUMINAIRE	98.00	EACH
S479	T08.0100	LIGHT STANDARD FOUNDATION WITH ANCHOR BOLTS STANDARD 18.1.0	69.00	EACH
S480	T08.2031	ALUMINUM LIGHTING STD. 30 FT. W/ SINGLE DAVIT ARM EXTN. 10 FT. STANDARD 18.3.0	39.00	EACH
S481	T08.2032	ALUM. LIGHTING STD. 30 FT. W/ DOUBLE DAVIT ARM EXTN. 10X10 FT. STANDARD 18.3.0	30.00	EACH
S482	T08.9902	DECORATIVE POLE/LUMINAIRE - SINGLE 70 WATT HPS	37.00	EACH
S483	T08.9903	DECORATIVE POLE FOUNDATION W/BOLTS	32.00	EACH
S484	T09.1000	SERVICE PEDESTAL STANDARD 18.4.0	5.00	EACH
S485	T09.9902	SERVICE RISER	5.00	EACH
S486	T11.2008	TRAFFIC SIGNAL STANDARD,8 FOOT,STD 19.4.0 ALUMINUM PEDESTAL POLE AND FOUNDATION	4.00	EACH
S487	T11.9902	30 FOOT GAL STEEL MAST ARM TRAFFIC SIGNAL POST AND FOUNDATION STD. 19.2.0	1.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
S488	T11.9910	DUAL MAST ARM (40X35) GAL STEEL TRAFFIC SIGNAL POST AND FOUNDATION STD. 19.2.0	1.00	EACH
S489	T11.9911	TRAFFIC SIGNAL STANDARD, WOOD, 35 FT. CLASS 3	3.00	EACH
S490	T12.0018	ACTUATED CONTROLLER TS-2, TYPE 1 W/8 PHASE ASSEMBLY GROUND MOUNTED INCLUDING FOUNDATION AND CABINET STD. 19.1.0	1.00	EACH
S491	T12.9150	METER SOCKET W/MANUAL BY-PASS	1.00	EACH
S492	T12.9901	TEMPORARY TRAFFIC SIGNAL SYSTEM	1.00	LS
S493	T12.9902	MAINTENANCE OF TEMPORARY TRAFFIC SIGNAL SYSTEM	1.00	LS
S494	T12.9903	TRAFFIC SIGNAL SYSTEM MASTER	1.00	EACH
S495	T12.9904	GROUND MOUNTED CONTROLLER CABINET - RVD STATION	3.00	EACH
S496	T12.9905	TRAFFIC SIGNAL MODIFICATIONS	1.00	LS
497	T12.9906	MOBILE CAMERA SURVEILLANCE SYSTEM	1.00	LS
S498	T13.1000	TRAFFIC DETECTORS-LOOP, STANDARD 19.6.0	881.00	LF
S499	T13.1002	TRAFFIC DETECTOR RELAY-LOOP 2 CHANNEL	1.00	EACH
S500	T13.1004	TRAFFIC DETECTOR RELAY-LOOP 4 CHANNEL	2.00	EACH
S501	T13.9902	HEAVY DUTY PEDESTRIAN DETECTOR – PUSH BUTTON WITH SIGN AND AUDIBLE PEDESTRIAN EQUIPMENT	4.00	EACH
S502	T13.9910	OPTICAL PHASE SELECTOR AND CHASSIS	1.00	EACH
S503	T13.9911	OPTICAL DETECTOR CONFIRMATION BEACON	1.00	EACH
S504	T13.9912	OPTICAL DETECTOR - SINGLE CHANNEL, ONE WAY	2.00	EACH
S505	T14.3513	1 WAY 3 SECTION MAST ARM MOUNTED SIGNAL HEAD 12 INCH	7.00	EACH
S506	T14.9901	1 WAY PEDESTAL MTD. LED PED SIGNAL HEAD W/COUNTDOWN TIMER- 12 INCH	4.00	EACH
S507	T15.0100	DIRECTIONAL REGULATORY AND WARNING SIGNS	2,685.60	SF
S508	T15.1000	STREET SIGN ASSEMBLY STD. 24.6.1	13.00	EACH
S509	T15.1100	STREET SIGN - OVERHEAD MOUNTED	2.00	EACH
S510	T15.2000	PARKING SIGNS	48.00	SF
S511	T15.9901	APPONAUG STREET SIGNS	5.00	EACH
512	T18.0100	FLEXIBLE DELINEATOR POST	100.00	EACH
S513	T20.0006	6 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	47,900.00	LF
S514	T20.0012	12 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	2,662.00	LF
S515	T20.0104	4 INCH YELLOW FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	30,065.00	LF

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
S516	T20.0820	FAST DRYING WATERBONE PAVEMENT ARROW - STRAIGHT, LEFT, RIGHT, OR COMBINED STANDARD 20.1.0	53.00	EACH
S517	T20.0822	FAST DRYING WATERBONE PAVEMENT MARKING WORD "ONLY" STANDARD 20.1.0	25.00	EACH
S518	T20.1000	REMOVE EXISTING PAVEMENT MARKINGS	5,000.00	LF
S519	T20.2006	6 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	29,250.00	LF
S520	T20.2012	12 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	5,213.00	LF
S521	T20.2014	4 INCH EPOXY RESIN PAVEMENT MARKINGS YELLOW	21,405.00	LF
S522	T20.2020	EPOXY RESIN PAVEMENT ARROW - STRAIGHT, LEFT, RIGHT, OR COMBINED STANDARD 20.1.0	53.00	EACH
S523	T20.2022	EPOXY RESIN PAVEMENT MARKING WORD "ONLY" STANDARD 20.1.0	25.00	EACH
S524	T20.9901	6 INCH TEMPORARY EPOXY RESIN PAVEMENT MARKINGS WHITE	10,000.00	LF
S525	T20.9902	12 INCH TEMPORARY EPOXY RESIN PAVEMENT MARKINGS WHITE	2,402.00	LF
S526	T20.9904	12 INCH TEMPORARY WATERBORNE PAVEMENT MARKING PAINT WHITE - 8 MILS	5,163.00	LF
S527	T20.9905	12 INCH TEMPORARY WATERBORNE PAVEMENT MARKING PAINT YELLOW - 8 MILS	565.00	LF
S528	T20.9906	12 INCH YELLOW FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	565.00	LF
S529	T20.9907	12 INCH TEMPORARY EPOXY RESIN PAVEMENT MARKINGS YELLOW	265.00	LF
S530	T20.9908	12 INCH EPOXY RESIN PAVEMENT MARKINGS YELLOW	565.00	LF
S531	T20.9909	6 INCH TEMPORARY WATERBORNE PAVEMENT MARKING PAINT WHITE - 8 MILS	29,250.00	LF
S532	T20.9910	4 INCH TEMPORARY EPOXY RESIN PAVEMENT MARKINGS YELLOW	18,465.00	LF
S533	T20.9913	4 INCH TEMPORARY WATERBORNE PAVEMENT MARKING PAINT YELLOW – 8 MILS	21,405.00	LF
S534	T20.9916	TEMPORARY WATERBORNE PAVEMENT MARKING PAINT WHITE - YIELD LINE - 8 MILS	396.00	LF
S535	T20.9917	FAST DRYING WATERBORNE PAVEMENT MARKING WHITE - YIELD LINE	396.00	LF
S536	T20.9918	EPOXY RESIN PAVEMENT MARKINGS WHITE - YIELD LINE	396.00	LF
S537	T20.9919	TEMPORARY WATERBORNE PAVEMENT MARKING WORD "ONLY" STANDARD 20.1.0 - 8 MILS	25.00	EACH
S538	T20.9920	TEMPORARY EPOXY RESIN PAVEMENT MARKING WORD "ONLY" STANDARD 20.1.0	22.00	EACH
S539	T20.9921	TEMPORARY EPOXY RESIN PAVEMENT MARKING WORD "YIELD"	26.00	EACH
S540	T20.9922	FAST DRYING WATERBORNE PAVEMENT MARKING WORD "YIELD" STANDARD 20.1.0	26.00	EACH

Item List

Date: 3/7/2014

Estimate Name - Advertising Estimate
Project Name - Apponaug Circulator By-Pass
R.I. Contract No. - 2014-CH-028
FAP Nos. - 3RD-PRTY(221), NHP-0001(107), NHPG-0001(108), NHP-TIGR(002)

Seq No.	Item Code	Description	Quantity	UM
S541	T20.9923	TEMPORARY WATERBORNE PAVEMENT MARKING WORD "YIELD" STANDARD 20.1.0 - 8 MILS	26.00	EACH
S542	T20.9924	EPOXY RESIN PAVEMENT MARKING WORD "YIELD" STANDARD 20.1.0	26.00	EACH
S543	T20.9925	TEMPORARY WATERBORNE PAVEMENT ARROW - STRAIGHT, LEFT, RIGHT OR COMBINED STD. 20.1.0	53.00	EACH
S544	T20.9926	FAST DRYING WATERBORNE PAVEMENT MARKING "FISHHOOK" SYMBOL - STRAIGHT, LEFT, RIGHT OR COMBINED	43.00	EACH
S545	T20.9927	TEMPORARY WATERBORNE PAVEMENT MARKING "FISHHOOK" SYMBOL - STRAIGHT, LEFT, RIGHT OR COMBINED - 8 MILS	43.00	EACH
S546	T20.9928	EPOXY RESIN PAVEMENT MARKING "FISHHOOK" SYMBOL - STRAIGHT, LEFT, RIGHT OR COMBINED	43.00	EACH
S547	T20.9930	TEMPORARY EPOXY RESIN PAVEMENT MARKING "FISH HOOK" SYMBOL – STRAIGHT, LEFT, RIGHT OR COMBINED	43.00	EACH
S548	T20.9932	TEMPORARY EPOXY RESIN PAVEMENT ARROW – STRAIGHT, LEFT, RIGHT OR COMBINED STANDARD 20.1.0	53.00	EACH
S549	T20.9933	TEMPORARY EPOXY RESIN PAVEMENT MARKING - YIELD LINE	396.00	LF
S550	T20.9934	TEMPORARY WATERBORNE PAVEMENT MARKING – HELMETED BICYCLIST SYMBOL WITH ARROW - 8 MILS	24.00	EACH
S551	T20.9935	EPOXY RESIN PAVEMENT MARKING – HELMETED BICYCLIST SYMBOL WITH ARROW	24.00	EACH

State of Rhode Island Department of Administration
Division of Purchases

RHODE ISLAND DEPARTMENT OF TRANSPORTATION

REVISED
November 20, 2013

NOTICE TO VENDORS

Each bid proposal for a *public works project* must include a "public copy" to be available for public inspection upon the opening of bids. **Bid proposals that do not include a copy for public inspection will be deemed nonresponsive.**

To comply with this requirement, *in addition to* the Quest Lite compatible electronic copy and one hard copy, bid proposals for *highway and bridge public works projects* must also include a duplicate original of the Quest Lite compatible electronic copy on a ***read-only*** CD-R media disc as the "public copy."

The public copy disc must be separately enclosed in a protective cover clearly marked "Public Copy" and include the following information (all available from the Bidder Certification Cover Form): (1) title of solicitation; (2) name of bidder and RIVIP vendor ID number; (3) bid number; and (4) date of bid.

The public copy may redact any trade secrets or commercial or financial information which is of a privileged or confidential nature pursuant to the "Access to Public Records Act," R. I. Gen. Laws §§ 38-2-1 *et seq.*

For further information on how to comply with this statutory requirement, see R. I. Gen. Laws §§ 37-2-18(b) and (j). Also see Procurement Regulations 5.11, 5.13, and 12.102.05 accessible at www.purchasing.ri.gov.

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS

Department of Labor and Training
Center General Complex
1511 Pontiac Avenue
Cranston, RI 02920-4407

TTY: Via RI Relay 711

Lincoln D. Chafee
Governor
Charles J. Fogarty
Director

STATE CONTRACT ADDENDUM

RHODE ISLAND DEPARTMENT OF LABOR AND TRAINING

PREVAILING WAGE REQUIREMENTS (37-13-1 ET SEQ.)

The prevailing wage requirements are generally set forth in RIGL 37-13-1 et seq. These requirements refer to the prevailing rate of pay for regular, holiday, and overtime wages to be paid to each craftsmen, mechanic, teamster, laborer, or other type of worker performing work on public works projects when state or municipal funds exceed one thousand dollars ($1,000).

All Prevailing Wage Contractors and Subcontractors are required to:

1. Submit to the Awarding Authority a list of the contractor's subcontractors for any part or all of the prevailing wage work in accordance with RIGL § 37-13-4;

2. Pay all prevailing wage employees at least once per week and in accordance with RIGL §37-13-7 (see Appendix B attached);

3. Post the prevailing wage rate scale and the Department of Labor and Training's prevailing wage poster in a prominent and easily accessible place on the work site in accordance with RIGL §37-13-11; posters may be downloaded at www.dlt.ri.gov/pw/Posters.htm .poster/htm or obtained from the Department of Labor and Training, Center General Complex, 1511 Pontiac Avenue, Cranston, Rhode Island;

4. Access the Department of Labor and Training website, at www.dlt.ri.gov on or before July 1st of each year, until such time as the contract is completed, to ascertain the current prevailing wage rates and the amount of payment or contributions for each covered prevailing wage employee and make any necessary adjustments to the covered employee's prevailing wage rates effective July 1st of each year in compliance with RIGL §37-13-8;

5. Attach a copy of this CONTRACT ADDENDUM and its attachments as a binding obligation to any and all contracts between the contractor and any

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS

Department of Labor and Training
Center General Complex
1511 Pontiac Avenue
Cranston, RI 02920-4407

Telephone; (401) 462-8000
TTY; Via RI Relay 711

Lincoln D. Chafee
Governor
Charles J. Fogarty
Director

subcontractors and their assignees for prevailing wage work performed pursuant to this contract;

6. Provide for the payment of overtime for prevailing wage employees who work in excess of eight (8) hours in any one day or forty (40) hours in any one week as provided by RIGL §37-13-10;

7. Maintain accurate prevailing wage employee payroll records on a Rhode Island Certified Weekly Payroll form available for download at www.dlt.ri.gov/pw.forms/htm, as required by RIGL §37-13-13, and make those records available to the Department of Labor and Training upon request;

8. Furnish the fully executed RI Certified Weekly Payroll Form to the awarding authority on a monthly basis for all work completed in the preceding month.

9. For general or primary contracts one million dollars ($1,000,000) or more, shall maintain on the work site a fully executed RI Certified Prevailing Wage Daily Log listing the contractor's employees employed each day on the public works site; the RI Certified Prevailing Wage Daily Log shall be available for inspection on the public works site at all times; this rule shall not apply to road, highway, or bridge public works projects. Where applicable, furnish both the Rhode Island Certified Prevailing Wage Daily Log together with the Rhode Island Weekly Certified Payroll to the awarding authority.

10. Assure that all covered prevailing wage employees on construction projects with a total project cost of one hundred thousand dollars ($100,000) or more has a OSHA ten (10) hour construction safety certification in compliance with RIGL § 37-23-1;

11. Employ apprentices for the performance of the awarded contract when the contract is valued at one million dollars ($1,000,000) or more, and comply with the apprentice to journeyperson ratio for each trade approved by the apprenticeship council of the Department of Labor and Training in compliance with RIGL §37-13-3.1;

12. Assure that all prevailing wage employees who perform work which requires a Rhode Island trade license possess the appropriate Rhode Island trade license in compliance with Rhode Island law; and

An Equal Opportunity Employer/Program. / Auxiliary aids and services are available upon request to individuals with disabilities.

TTY via Rf Relay 711

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS

Department of Labor and Training
Center General Complex
1511 Pontiac Avenue
Cranston, RI 02920-4407

Telephone: (401) 462-8000
TTY: Via RI Relay 711

Lincoln D. Chafee
Governor
Charles J. Fogarty
Director

13. Comply with all applicable provisions of RIGL §37-13-1, et. seq;

Any questions or concerns regarding this CONTRACT ADDENDUM should be addressed to the contractor or subcontractor's attorney. Additional Prevailing Wage information may be obtained from the Department of Labor and Training at www.dlt.ri.gov/pw.

CERTIFICATION

I hereby certify that I have reviewed this CONTRACT ADDENDUM and understand my obligations as stated above.

By: _____

Title: _____

Subscribed and sworn before me this____day of_____, 20_.

_____
Notary Public
My commission expires:_____

An Equal Opportunity Employer/Program, /Auxiliary aids and services are available upon request to individuals with disabilities.

TTY via RI Relay 711

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS

Department of Labor and Training
Center General Complex
1511 Pontiac Avenue
Cranston, RI 02920-4407

Telephone: (401) 462-8000

APPENDIX A

TITLE 37
Public Property and Works

CHAPTER 37-13
Labor and Payment of Debts by Contractors

SECTION 37-13-5

§ 37-13-5 Payment for trucking or materials furnished – Withholding of sums due. -A contractor or subcontractor on public works authorized by a proper authority shall pay any obligation or charge for trucking and material which have been furnished for the use of the contractor or subcontractor, in connection with the public works being performed by him or her, within ninety (90) days after the obligation or charge is incurred or the trucking service has been performed or the material has been delivered to the site of the work, whichever is later. When it is brought to the notice of the proper authority in a city or town, or the proper authority in the state having supervision of the contract, that the obligation or charge has not been paid by the contractor or subcontractor, the proper authority may deduct and hold for a period not exceeding sixty (60) days, from sums of money due to the contractor or subcontractor, the equivalent amount of such sums certified by a trucker or materialman creditor as due him or her, as provided in this section, and which the proper authority determines is reasonable for trucking performed or materials furnished for the public works.

APPRENDIX B

TITLE 37
Public Property and Works

CHAPTER 37-13
Labor and Payment of Debts by Contractors

SECTION 37-13-7

§ 37-13-7 Specification in contract of amount and frequency of payment of wages. -(a) Every call for bids for every contract in excess of one thousand dollars ($1,000), to which the state of Rhode Island or any political subdivision thereof or any public agency or quasi-public agency is a party, for construction, alteration, and/or repair, including painting and decorating, of public buildings or public works of the state of Rhode Island or any political subdivision thereof, or any public agency or quasi-public agency and which requires or involves the employment of employees, shall contain a provision stating the minimum wages to be paid various types of employees which shall be based upon the wages that will be determined by the director of labor and training to be prevailing for the corresponding types of employees employed on projects of a character similar to the contract work in the city, town, village, or other appropriate political subdivision of the state of Rhode Island in which the work is to be performed. Every contract shall contain a stipulation that the contractor or his or her subcontractor shall pay all the employees employed directly upon the site of the work, unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account, the full amounts accrued at time of payment computed at wage rates not less than those stated in the call for bids, regardless of any contractual relationships which may be alleged to exist between the contractor or subcontractor and the employees, and that the scale of wages to be paid shall be posted by the contractor in a prominent and easily accessible place at the site of the work; and the further stipulation that there may be withheld from the contractor so much of the accrued payments as may be considered necessary to pay to the employees employed by the contractor, or any subcontractor on the work, the difference between the rates of wages required by the contract to be paid the employees on the work and the rates of wages received by the employees and not refunded to the contractor, subcontractors, or their agents.

(b) The terms "wages", "scale of wages", "wage rates", "minimum wages", and "prevailing wages" shall include:

(1) The basic hourly rate of pay; and

(2) The amount of:

(A) The rate of contribution made by a contractor or subcontractor to a trustee or to a third person pursuant to a fund, plan, or program; and

(B) The rate of costs to the contractor or subcontractor which may be reasonably anticipated in providing benefits to employees pursuant to an enforceable commitment to carry out a financially responsible plan or program which was communicated in writing to the employees affected, for medical or hospital care, pensions on retirement or death, compensation for injuries or illness resulting from occupational activity, or insurance to provide any of the foregoing, for unemployment benefits, life insurance, disability and sickness insurance, or accident insurance, for vacation and holiday pay, for defraying costs of apprenticeship or other similar programs, or for other bona fide fringe benefits, but only where the contractor or subcontractor is not required by other federal, state, or local law to provide any of the benefits; provided, that the obligation of a contractor or subcontractor to make payment in accordance with the prevailing wage determinations of the director of labor and training insofar as this chapter of this title and other acts incorporating this chapter of this title by reference are concerned may be discharged by the making of payments in cash, by the making of contributions of a type referred to in subsection (b)(2), or by the assumption of an enforceable commitment to bear the costs of a plan or program of a type referred to in this subdivision, or any combination thereof, where the aggregate of any payments, contributions, and costs is not less than the rate of pay described in subsection (b)(l) plus the amount referred to in subsection (b)(2).

(c) The term "employees", as used in this section, shall include employees of contractors or subcontractors performing jobs on various types of public works including mechanics, apprentices, teamsters, chauffeurs, and laborers engaged in the transportation of gravel or fill to the site of public works, the removal and/or delivery of gravel or fill or ready-mix concrete, sand, bituminous stone, or asphalt flowable fill from the site of public works, or the transportation or removal of gravel or fill from one location to another on the site of public works, and the employment of the employees shall be subject to the provisions of subsections (a) and (b).

(d) The terms "public agency" and "quasi-public agency" shall include, but not be limited to, the Rhode Island industrial recreational building authority, the Rhode Island economic development corporation, the Rhode Island airport corporation, the Rhode Island industrial facilities corporation, the Rhode Island refunding bond authority, the Rhode Island housing and mortgage finance corporation, the Rhode Island resource recovery corporation, the Rhode Island public transit authority, the Rhode Island student loan authority, the water resources board corporate, the Rhode Island health and education building corporation, the Rhode Island higher education assistance authority, the Rhode Island turnpike and bridge authority, the Narragansett Bay water quality management district commission, Rhode Island telecommunications authority, the convention center authority, the board of governors for higher education, the board of regents for elementary and secondary education, the capital center commission, the housing resources commission, the Quonset Point-Davisville management corporation, the Rhode Island children's crusade for higher education, the Rhode Island depositors economic protection corporation, the Rhode Island lottery commission, the Rhode Island

partnership for science and technology, the Rhode Island public building authority, and the Rhode Island underground storage tank board.

RHODE ISLAND DEPARTMENT OF TRANSPORTATION

* *THIS IS A DISK-BASED BID* *

ELECTRONIC BIDDING PROCEDURE NOTICE

ALL BID OFFERS MUST BE PREPARED USING THE QUEST LITE BID PREPARATION SOFTWARE PACKAGE

Bidders MUST register in person at the RIDOT Contract Administration office to obtain the necessary Bidder Registration and Digital ID codes for the Quest Lite software.

RIDOT Provides:

CD



Plans (on CD)

Contract Documents (on CD)



DOQ Report (on CD)

Bidder Must Submit:



2 High-Density Compact Disks (CDs) w/Quest Lite Bid "zip" file**

Completed & Signed Proposal (Hard Copy)

Surety (Bid Bond)

Bid Surety (Hard Copy)

RIVIP Certification Form

Completed & Signed (Hard Copy)

Contact the Contracts & Specifications Office at 222-2495 to request technical assistance on issues directly related to the Quest Lite software
Office Hours: 8:00 AM – 4:00 PM

****Refer to the RIDOA "Notice to Contractors" for additional information on the "Public Copy" submission requirements.**

NO BID OFFER WILL BE CONSIDERED

UNLESS ACCOMPANIED BY A COMPACT DISK (CD)

CONTAINING THE BID PROPOSAL FILE

GENERATED BY THE QUEST LITE BID PREPARATION SOFTWARE

Failure to comply will result in a mandatory disqualification per Section 12.102.07 of the RI Dept of Administration Division of Purchases Procurement Regulations

Revision 02/25/11

Rhode Island Department of Transportation (RIDOT)

Notice to Contractors

THIS IS A DISK-BASED BID

Bid offers will be accepted ***only on a CD generated by RIDOT-supplied software called Quest Lite; each CD must be accompanied by a hard copy signed offer printed from the software and submitted at the Bid Opening.*** Minimum computer hardware and operating system requirements are listed here. ***Training is strongly recommended for all new bidders and others unfamiliar with these procedures. SEE BELOW.***

CONTACT: **RIDOT CONTRACTS & SPECIFICATIONS**
Rm. 108, Two Capitol Hill, Providence, RI 02903
Phone: **401-222-2495**
Hours: **Mon – Fri, 8:00AM – 4:00PM**

1. **Required Registration Codes for Each Bidder.**
Registration Codes for RIDOT software are necessary to install and use the software; a firm only needs to register once to acquire secure, unique bidder identification codes to be used with all RIDOT disk-based construction project bids **Bidders must retain these codes for future use.**

2. **The required Quest Lite installation software and all applicable Contract Documents are provided on a CD-ROM.**
The Contract Documents include the RI DOA Division of Purchases Procurement Regulations, RI Standard Specifications, Amended December 2010 and all revisions, the RI Standard Details for Highway and Bridge Construction, Bridge Standard Details, General Provisions, Special Provisions, Distribution of Quantities and Engineering Plans, and all other applicable documents

3. **Minimum Computer Hardware and Operating System Requirements.**
   - Windows XP SP2 w/Pentium IV processor
   - CD-ROM Drive, Floppy Drive, Printer & 15" Monitor (17" recommended)
   - 20GB Hard Disk with 1GB free (40 GB with 5 GB free recommended)
   - 512 MB RAM (1 GB recommended)
   - 32 MB Video Card (64 MB SVGA recommended)
   - Internet Explorer 6 0 SP 2

4. **Addenda, when necessary, are available on Purchases' RIVIP website.**
at: http://www.purchasing.ri.gov/RIVIP/BidSearch.asp
RIDOT will make all necessary addenda available at Purchases' web site It is the plan-holders responsibility to poll the RIVIP to keep up-to-date on addenda.

5. **Training may be requested up to three days prior to the Bid Opening.**
Training is provided on request Arrangements must be made through the RIDOT Contracts & Specifications Office at least three (3) days prior to the Bid Opening of the project

6. **Technical Support.**
Assistance is available upon request by contacting the Contracts & Specifications office during work hours or emailing Quest@dot.ri.gov.

01/25/2011

NOTICE TO HIGHWAY AND BRIDGE CONTRACTORS

Rhode Island Department of Transportation (RIDOT)
Contracts and Specifications

ELECTRONIC BIDDING PROCEDURES
QUEST LITE UPGRADE

Effective January 1, 2011, bid offers for all RIDOT Contracts requiring the use of the Department's Quest Lite bid preparation software **MUST** be prepared using **Quest Lite Version 040408 (2.8.4)**. Failure to comply with this requirement could result in the disqualification of your bid offer.

Full installation and upgrade-only software packages, including installation directions, for Quest Lite Version **040408 (2.8.4)** will be provided on the Project Advertising CD's, which are available to prospective bidders through the Contracts and Specifications office on or after the scheduled project advertising date.

Contractors presently using Quest Lite Version 040407 (2.8.3) need only install the upgrade package to complete the conversion, **UNLESS** a previous upgrade installation was used to upgrade from 2.8.2 to 2.8.3, in which case these installations must be removed and the full installation performed. Earlier versions (2.8.2 or lower) will require the full installation in all instances.

For technical assistance, contact the Contracts and Specifications office at 222-2495.

01/21/11

QUEST LITE VERSION 4.4.8 (2.8.4)

UPGRADE & FULL INSTALLATION

All bid offers prepared using the Department of Transportation's Quest Lite software must use the Quest Lite Version 040408 (2.8.4). If there is no Quest Lite installation, than the full installation must be completed. For earlier versions of Quest Lite, either the upgrade or full installation will be required to be completed. Both versions (upgrade and full installation) are provided on this project CD.

Before proceeding with any installations, note the following:

1. All users must register with the Department of Transportation in order to use Quest Lite. At the time of registration, users are provided with a set of unique company ID codes (Site Code, Bidder Code and company Short Name). Users **MUST RETAIN** these codes for future use.

2. Many users who currently have Quest Lite installed will only require the installation of the upgrade version. To determine if the upgrade installation is sufficient, the present version of the Quest Lite installation must be determined. This is accomplished in Quest Lite by clicking on Help/About. If the present version is 040407 (2.8.3) then the upgrade installation is sufficient **unless** an upgrade version has been previously used to upgrade version 2.8.2 to 2.8.3.

3. For earlier installations (versions below 2.8.3, and if an upgrade has been previously installed to upgrade to version 2.8.3), the full installation of Quest Lite is required (Note: if the full installation is required, the upgrade installation does not need to be performed after the full installation is completed.)

4. To determine if an upgrade version of Quest Lite version is present, it is generally easiest to use the "Add or Remove Programs" function from the Control Panel to view the Quest Lite installations. Should both an installation and an upgrade version be installed, both programs must be removed using the "Remove" function and the new version 2.8.4 installed.

5. It is recommended that users consult the Quest Lite User Manual provided on this CD prior to attempting the installation of the upgrade or full program installation.

6. After completing the installation of the upgrade or full installation, it is recommended that a test bid be submitted to the Department to ensure the program is functioning correctly and that the Quest Lite bid files can be correctly imported into the Department's Quest program. Test bids may be submitted on a CD to the Contracts office in Room 109 of the RIDOT Headquarters, or by e-mail to Quest@dot.ri.gov.

Installation Instructions – Upgrade Version

Upgrade Quest Lite only if the current installed version is 2.8 3, and a previous upgrade has not been installed.

1. Close Quest Lite before attempting the installation.
2. Using the project CD, double-click on the "Upgrade Only" option provided on the Start page.
3. When prompted for a password, enter "ridot".
4. Follow the instructions provided in the installation wizard to complete the installation.
5. When executing Quest Lite for the first time after installing the upgrade, users may be prompted to enter their company bidder codes.

Installation Instructions – Complete Installation

A complete Installation of the software is required only if Quest Lite is:

1. Not installed on the computer/laptop; or
2. The installed version of Quest Lite is older than 2 8.3, i.e. 2.8.2 or under; or
3. The 2.8 3 upgrade version of Quest Lite is installed.

If any of 1 through 3 above apply, follow these instructions:

1. If a Quest Lite version 2.8.2 or older, or a 2.8.3 upgrade are currently installed,
   a. Close Quest Lite.
   b. Remove all the existing installation(s) of Quest Lite. To accomplish this, follow the instructions provided on pages 19 – 25 of the Quest Lite User Manual provided with this project CD. Follow the installation removal directions for the operating system in use on the machine.
2. Using the project CD, double-click on the "Complete Installation" option provided on the Start page.
3. When prompted for a password, enter "ridot".
4. Follow the instructions provided in the installation wizard to complete the installation.
5. When executing Quest Lite for the first time after completing the installation, the user will be prompted to enter the company bidder codes provided by the Department. Once this information is entered, the installation process will be complete.

For technical assistance, contact the Contracts & Specifications office at 222-2495.