



STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS

Department of Administration
DIVISION OF PURCHASES
One Capitol Hill
Providence, RI 02908-5855

Tel: (401) 574-8100
Fax: (401) 574-8387
Website: www.purchasing.ri.gov

March 19, 2014

ADDENDUM NUMBER ONE
RFQ # 7548943

TITLE: Temporary Stabilization-Francis Street Parcels-Francis St, Providence, RI

Closing Date and Time: 11/25/14 at 1:30 PM

Per the issuance of this ADDENDUM #1 (2 pages) the following is noted:

This addendum posts answers to questions sent in on line until 5pm 11/18/14.

END OF QUESTIONS

Temporary Stabilization Plan
Bid # 7548943
Francis Street Providence, RI

Response to Contractor Questions dated November 18, 2014

Question 1: Plan sheet C3 show the Remediation area with 270 CY of material to be removed. Is the work to be carried in the base bid or is it to be paid under Alternate No. 1?

Response: The 270 cubic yards of remediation activities shall be carried in the base bid price. The Alternate No. 1 is a price for additional remediation activities, for volumes greater than 270 cubic yards.

Question 2: Plan sheet CI Soil Evaluation Data Note states "A and B horizons and HTM soils are to be removed and disposed. Test pit show that the depths of these soils are between 24" to 86" deep. Plan sheet C3 has a note that states the same. Plan sheet C4 Grading Note #1 "the proposed grading referenced on this plan is based upon removal of organic and fill soils in the upper horizons".

If the site is cut to the proposed grades that are shown on C4, the full amount of unsuitable soils will not be removed.

What is the intent of the work:

- Cut site to proposed grades and leave any unsuitable material below subgrade in Place?

-Remove all unsuitable material shown on the test pit and fill the to subgrade? If this is the option, what type of material will be used to fill to subgrade, since all material removed will be unsuitable?

Response: The project scope is to first remove the contaminated soil within the designated area referenced. This work will be supervised by the Environmental Engineer. The next operation would be to remove the A and B horizon soils and the HTM soils within the site limits referenced on the plans. After this removal, the Contractor shall re-grade the site with the remaining soil on site. Grading shall match the proposed grading on sheet C4 to the extent possible. See Grading notes on sheet C4. If additional material is deemed necessary by owner, it will be requested at that time, and this would be Alternate No. 1 and/or Alternate No. 2. After this mentioned work is complete and the site is graded, the Contractor shall place the crushed stone surface, per the base bid requirement.