

April 2, 2015

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATION
DEPARTMENT OF ADMINISTRATION

DIVISION OF PURCHASES BID NO. 7549427

RHODE ISLAND DEPARTMENT OF TRANSPORTATION

RHODE ISLAND CONTRACT NO.2015-CH-013

FEDERAL-AID PROJECT NO. FAP Nos: STP-RESF(288)

Improvements to Dexter Street and Repairs to Bridge #935

The roadway project limits will be from the intersection of School Street in Central Falls to Goff Avenue in Pawtucket, approximately 0.91 miles in length. Twenty-two side streets intersect Dexter Street within the project limits and approximately twenty feet of each side street is included within the project area.

CITY/TOWN OF Central Falls, Pawtucket

COUNTY OF PROVIDENCE

NOTICE TO PROSPECTIVE BIDDERS

ADDENDUM NO. 1 Prospective bidders and all concerned are hereby notified of the following changes in the Plans, Specifications, Proposal and Distribution of Quantities for this contract. These changes shall be incorporated in the Plans, Specifications, Proposal and Distribution of Quantities, and shall become an integral part of the Contract Documents.

A. Specification - Job Specific

1. JS-59

Replace Page JS-59 with Page JS-59(R-1) attached to this Addendum No. 1. The product name listed in the specification has been revised.

B. Distribution of Quantities

1. Index

Replace Pages Index:1 through 4 with Pages Index:1 (R-1) through 4(R-1) attached to this Addendum No. 1. Item Code 702.0615 has been deleted and Item Code 702.0605 has been added.

2. Page 11 of 87

Replace Page 11 of 87 with Page 11 of 87(R-1) attached to this Addendum No. 1. The quantity for Item Code 202.0100 - Earth Excavation has been revised.

3. Page 12 of 87

Replace Page 12 of 87 with Page 12 of 87(R-1) attached to this Addendum No. 1. The quantity for Item Code 302.0100 - Gravel Borrow Subbase Course has been revised.

4. Page 20 of 87

Replace Page 20 of 87 with Page 20 of 87(R-1) attached to this Addendum No. 1. Item Code 702.0615 - Precast Catch Basin 6' Diameter Standard 4.4.0 has been deleted.

5. Page 87 of 87

Replace Page 87 of 87 with Page 87 of 87(R-1) attached to this Addendum No. 1. Item Code 702.0605 - Precast Catch Basin 4' Diameter Standard 4.4.0 has been added.



RI Department of Transportation
Chief Engineer

JOB SPECIFIC
CODE 905.9901
FURNISH AND INSTALL DECORATIVE CROSSWALK

DESCRIPTION: Work under this item shall consist of the installation of decorative stamped asphalt material simulating hand laid red brick for crosswalks on Dexter Street, as shown on the Contract Drawings.

MANUFACTURER: The material shall be TrafficPatternsXD™ paving material manufactured by Ennis-Flint. There will be no approved equal.

The Contractor shall obtain from the Manufacturer, and submit to the Engineer, an affidavit regarding patent infringement rights stating that any suit or claim against the State due to alleged infringement rights shall be defended by the Manufacturer who will bear all costs, expenses and attorney's fees incurred thereof.

MATERIALS: The product used in this surfacing system shall be TrafficPatternsXD™. The crosswalk style shall be 8-foot wide Offset Brick as shown on the Plans.

Ennis-Flint
115 Todd Court
Thomasville, NC 27360
Telephone: 336-475-6600
Email: sales@ennisflint.com
<http://www.ennisflint.com>

The TrafficPatternsXD™ texturing tools shall be approved by the Manufacturer and be of high quality produce a brick pattern for the crosswalks. The Contractor shall refer to the Plans for the orientation of the brick patterns.

CONSTRUCTION METHODS: The installation of the decorative crosswalk must be completed by an accredited TrafficPatternsXD™ installer.

The decorative crosswalk shall be installed in accordance with the manufacturer's recommendations.

Any residue resulting from this work shall be removed and legally disposed of in a proper manner. The completed work area is to be left in a neat and clean condition, to the satisfaction of the Engineer.

PROTECTION OF PROPERTY: All surfaces, utility structures, poles, curbing, stone and other features not intended to be affected by the installation of the textured paving shall be protected from being contacted by the TrafficPatternsXD™ material. The Contractor shall be responsible for completely cleaning and/or restoring any surface or object or drainage system that is contaminated as a result of the Contractor's activities, at no additional cost to the State.

Table of Contents - Distribution of Quantities

Project Name - Improvements to Dexter Street and Repairs to Bridge #935

Estimate Name - Addendum 1

R.I. Contract No. - 2015-CH-013

FAP Nos: STP-RESF(288)

<u>ItemCode</u>	<u>Description</u>	<u>Page</u>
201.0301	CUTTING AND DISPOSING ISOLATED TREES AND STUMPS (4"- 24")	1
201.0305	COMPLETE REMOVAL AND DISPOSAL OF ISOLATED STUMPS (6'' TO 24'')	2
201.0403	REMOVE AND DISPOSE SIDEWALKS	2
201.0407	REMOVE AND DISPOSE PAVEMENT AND RIGID BASE	3
201.0409	REMOVE AND DISPOSE FLEXIBLE PAVEMENT	3
201.0410	REMOVE AND DISPOSE CATCH BASINS	3
201.0414	REMOVE AND DISPOSE PIPE - ALL SIZES	3
201.0415	REMOVE AND DISPOSE GUARDRAIL AND POST ALL TYPES	4
201.0422	REMOVE AND DISPOSE DROP INLET	4
201.0423	REMOVE AND DISPOSE HANDHOLE	4
201.0428	REMOVE AND DISPOSE FRAME AND GRATE OR FRAME AND COVER	5
201.0610	REMOVE AND DISPOSE DIRECTIONAL, WARNING, REGULATORY, SERVICE, AND STREET SIGNS	5
201.9901	REMOVE AND SALVAGE STREET SIGN (CENTRAL FALLS)	8
201.9902	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT AT DEXTER STREET & COWDEN STREET/MOORE STREET	9
201.9903	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT AT DEXTER STREET & SUMMER STREET/MOWRY STREET	9
201.9904	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT AT DEXTER STREET & CROSS STREET	10
201.9905	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT AT DEXTER STREET & BARTON STREET	10
201.9906	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT AT DEXTER STREET & DARLING STREET	10
201.9907	REMOVE, STOCKPILE, AND RESET BENCH	10
201.9908	REMOVE, STOCKPILE, AND RESET TREE WELL GRATE	10
202.0100	EARTH EXCAVATION	11
202.0800	GRAVEL BORROW	11
204.0100	TRIMMING AND FINE GRADING	11
209.9901	INLET SEDIMENT CONTROL DEVICE	11
212.2000	CLEANING AND MAINTENANCE OF EROSION CONTROLS	11
213.0100	PLACEMENT OF MILLINGS BENEATH GUARDRAIL	12
302.0100	GRAVEL BORROW SUBBASE COURSE	12
401.3002	CLASS 9.5 HMA FOR LEVELLING	12
401.3005	CLASS 9.5 HMA FOR MISCELLANEOUS WORK	12
401.3100	MODIFIED CLASS 9.5 HMA	13
401.4005	CLASS 4.75 HMA FOR MISCELLANEOUS WORK	13
401.9901	MODIFIED CLASS 9.5 HMA FOR BRIDGE DECKS	13
403.0300	ASPHALT EMULSION TACK COAT	13
408.9901	ISOLATED REPAIR OF ROADWAY CONCRETE BASE SLAB JOINT	13
412.0100	RUBBERIZED ASPHALT CHIP SEALING	14
601.0300	CLASS A PORTLAND CEMENT CONCRETE	14
701.0412	REINFORCED CONCRETE PIPE M 170 CLASS III 12 INCH	14
701.8151	CURB STOP BOX	15
702.0516	FRAME AND GRATE, HIGH CAPACITY, STANDARD 6.3.4	17
702.0517	FRAME AND GRATE, STANDARD 6.3.2	18
702.0541	GRANITE INLET STONE 38'' STANDARD 7.3.6	19
702.0543	GRANITE APRON STONE 38'' STANDARD 7.3.8	19
702.0615	** ITEM DELETED **	20
702.0713	PRECAST CONCRETE DROP INLET WITH APRON STONE STANDARD 4.5.1	20
704.0100	RECONSTRUCT CATCH BASIN/CORBEL CONES	21
705.1300	RECONSTRUCT CB TYPE 'D' TO CATCH BASIN WITH GUTTER INLET	21
707.0950	ADJUST TELEPHONE MANHOLE TO GRADE	22
707.1000	ADJUST SANITARY MANHOLE	22

Table of Contents - Distribution of Quantities

Project Name - Improvements to Dexter Street and Repairs to Bridge #935
 Estimate Name - Addendum 1
 R.I. Contract No. - 2015-CH-013
 FAP Nos: STP-RESF(288)

ItemCode	Description	Page
707.1900	ADJUST FRAME & COVER TO GRADE	24
707.2000	ADJUST FRAME AND GRATE TO GRADE	25
707.9901	ADJUST SEWER CLEANOUT TO GRADE	27
707.9902	ADJUST HYDRANT TO GRADE	29
708.9040	CLEANING AND FLUSHING PIPE ALL SIZES	29
708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	30
708.9042	CLEANING MANHOLES ALL TYPES AND SIZES	31
708.9901	CLEANING SEWER PIPES - ALL SIZES	32
712.0100	WATER GATE BOX	33
712.0200	GAS GATE BOX	35
803.9901	REMOVE AND DISPOSE FLEXIBLE PAVEMENT AND MEMBRANE	38
803.9902	REMOVE AND DISPOSE SEALANT	38
808.1642	PREFORMED POLYETHYLENE FOAM JOINT FILLER 1''	38
808.1670	POLYURETHANE JOINT SEALANT	39
810.0300	EPOXY COATED BARS GRADE 60	39
813.9901	TORCH-APPLIED WATERPROOFING MEMBRANE	39
817.2110	REPAIRS TO STRUCTURAL CONCRETE MASONRY (PATCHING MORTAR)	39
819.0800	DRILL AND GROUT REINFORCING DOWELS	39
821.1690	SAW & SEALING JOINTS IN BITUMINOUS CONCRETE PAVEMENT	40
901.0191	GUARDRAIL STEEL BEAM ANCHORAGE TRAILING END SECTION STANDARD 34.3.4	40
901.0193	GUARDRAIL STEEL BEAM SINGLE FACE STANDARD 34.2.0	40
901.0199	GUARDRAIL END TREATMENT, ENERGY ABSORBING TERMINAL	40
905.0110	PORTLAND CEMENT SIDEWALK MONOLITHIC STANDARD 43.1.0	40
905.0115	PORTLAND CEMENT CONCRETE DRIVEWAY STANDARD 43.5.0	41
905.9901	FURNISH AND INSTALL DECORATIVE CROSSWALK	43
906.0110	GRANITE CURB, QUARRY SPLIT STRAIGHT, STANDARD 7.3.0	45
906.0111	GRANITE CURB, QUARRY SPLIT CIRCULAR, STANDARD 7.3.0	46
906.0118	6' GRANITE TRANSITION CURB, QUARRY SPLIT SPECIAL TRANSITION STANDARD 7.3.2	48
906.0119	3' GRANITE TRANSITION CURB STANDARD 7.3.1	49
906.0120	GRANITE WHEELCHAIR RAMP CURB STANDARDS 7.3.3, 43.3.0 AND 43.3.1	53
906.0130	GRANITE RAMP STONE STRAIGHT STANDARD 7.3.9	55
906.0131	GRANITE RAMP STONE CIRCULAR STANDARD 7.3.9	56
906.0700	REMOVE, HANDLE, HAUL TRIM RESET CURB EDGING, STRAIGHT, CIRCULAR ALL TYPES	57
907.0100	WATER FOR DUST CONTROL	59
914.5010	FLAGPERSONS	59
914.5020	FLAGPERSONS - OVERTIME	59
915.0240	REMOVE AND RESET HIGHWAY BOUNDS (ALL TYPES)	59
919.0101	TEST PITS	60
922.0100	TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1	60
923.0105	DRUM BARRICADE STANDARD 26.2.0	61
923.0120	PLASTIC PIPE BARRICADE STANDARD 26.3.0	61
923.0200	FLUORESCENT TRAFFIC CONES STANDARD 26.1.0	61
923.9901	LONGITUDINAL PEDESTRIAN CHANNELIZING DEVICES	62
925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	62
929.0110	FIELD OFFICE	62
931.0110	CLEANING AND SWEEPING PAVEMENT	62
932.0100	CUTTING AND MATCHING ASPHALT	62
932.0210	FULL DEPTH SAWCUT OF BITUMINOUS PAVEMENT AND RIGID BASE	63
932.0220	FULL DEPTH SAWCUT OF BITUMINOUS SIDEWALK/DRIVEWAY	63
932.0230	FULL DEPTH SAWCUT OF PORTLAND CEMENT CONCRETE SIDEWALK/DRIVEWAY	64
935.0400	REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING	64

Table of Contents - Distribution of Quantities

Project Name - Improvements to Dexter Street and Repairs to Bridge #935

Estimate Name - Addendum 1

R.I. Contract No. - 2015-CH-013

FAP Nos: STP-RESF(288)

<u>ItemCode</u>	<u>Description</u>	<u>Page</u>
936.0100	MOBILIZATION AND DEMOBILIZATION	64
937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	64
942.0200	DETECTABLE WARNING PANEL STANDARD 48.1.0	64
943.0200	TRAINEE MAN-HOURS	65
L01.0102	LOAM BORROW 4 INCHES DEEP	65
L01.9901	PINE BARK MULCH FURNISH AND SPREAD 3" DEPTH	65
L02.0102	RESIDENTIAL SEEDING (TYPE 2)	65
L06.9901	ZELKOVA SERRATA 'MUSASHINO', MUSASHINO COLUMNAR JAPANESE ZELKOVA, 3-3 1/2" CAL., B&B	65
L06.9902	ACER RUBRUM 'COLUMNARE', COLUMNAR RED MAPLE. 3-3 1/2" CAL., B&B	66
L06.9903	GINKGO BILOBA 'PRINCETON SENTRY', PRINCETON SENTRY MAIDENHAIR TREE, 2 1/2-3" CAL., B&B	66
L11.0102	TREE PLANT PROTECTION DEVICE STANDARD 51.1.0	66
T04.5001	6 AWG SINGLE CONDUCTOR CABLE 600V INSULATION	66
T04.5302	14 AWG 2 CONDUCTOR TWISTED SHIELDED CABLE	66
T04.5303	14 AWG 3 CONDUCTOR CABLE	67
T04.5305	14 AWG 5 CONDUCTOR CABLE	67
T04.9901	VIDEO DETECTION CABLE	67
T05.0100	PRECAST TYPE A HANDHOLE STANDARD 18.2.0	67
T05.0400	BREAK INTO EXISTING HANDHOLE	68
T05.1030	ADJUST HANDHOLE TO GRADE	68
T06.1020	2 IN. RIGID STEEL CONDUIT - UNDERGROUND	69
T06.2020	2 IN. RIGID STEEL CONDUIT-OVERHEAD	69
T06.5130	3 INCH SCHEDULE 40 POLYVINYL CHLORIDE PLASTIC CONDUIT - UNDERGROUND	70
T06.5430	3 INCH SCHEDULE 80 POLYVINYL CHLORIDE PLASTIC CONDUIT - UNDER EXISTING PAVEMENT	71
T06.6020	2 INCH POLYVINYL CHLORIDE PLASTIC CONDUIT-OVERHEAD	72
T11.2008	TRAFFIC SIGNAL STANDARD, 8 FOOT, STD 19.4.0 ALUMINUM PEDESTAL POLE AND FOUNDATION	72
T11.9901	PEDESTRIAN PUSHBUTTON PEDESTAL	73
T12.0018	ACTUATED CONTROLLER TS-2, TYPE 1 W/8 PHASE ASSEMBLY GROUND MOUNTED INCLUDING FOUNDATION AND CABINET STD. 19.1.0	73
T12.9150	METER SOCKET W/MANUAL BY-PASS	73
T12.9901	VIDEO DETECTION SYSTEM HARDWARE UNIT	74
T12.9902	VIDEO DETECTION SYSTEM MONITOR	74
T13.1000	TRAFFIC DETECTORS-LOOP, STANDARD 19.6.0	74
T13.1004	TRAFFIC DETECTOR RELAY-LOOP 4 CHANNEL	74
T13.8210	ACCESSIBLE PEDESTRIAN DETECTOR - PUSHBUTTON WITH SIGN	75
T13.8220	ACCESSIBLE PEDESTRIAN DETECTOR - CONFIGURATION DEVICE	76
T13.9901	VIDEO DETECTION SYSTEM CAMERA	76
T14.9901	ONE-WAY PEDESTAL MOUNTED LED PEDESTRIAN SIGNAL HEAD WITH COUNTDOWN TIMER 12-INCH	76
T14.9902	ONE-WAY BRACKET MOUNTED LED PEDESTRIAN SIGNAL HEAD WITH COUNTDOWN TIMER 12-INCH	77
T14.9903	TWO-WAY PEDESTAL MOUNTED LED PEDESTRIAN SIGNAL HEAD WITH COUNTDOWN TIMER 12-INCH	77
T14.9904	TWO-WAY BRACKET MOUNTED LED PEDESTRIAN SIGNAL HEAD WITH COUNTDOWN TIMER 12-INCH	78
T15.0100	DIRECTIONAL REGULATORY AND WARNING SIGNS	78
T15.0200	REMOVE AND RELOCATE DIRECTIONAL REGULATORY AND WARNING SIGN	81
T15.1000	STREET SIGN ASSEMBLY STD. 24.6.1	82
T15.2000	PARKING SIGNS	82

Table of Contents - Distribution of Quantities

Project Name - Improvements to Dexter Street and Repairs to Bridge #935

Estimate Name - Addendum 1

R.I. Contract No. - 2015-CH-013

FAP Nos: STP-RESF(288)

<u>ItemCode</u>	<u>Description</u>	<u>Page</u>
T20.0006	6 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	83
T20.0012	12 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	83
T20.0104	4 INCH YELLOW FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	83
T20.0820	FAST DRYING WATERBORNE PAVEMENT ARROW - STRAIGHT, LEFT, RIGHT, OR COMBINED STANDARD 20.1.0	83
T20.1106	6 INCH TEMPORARY WATERBORNE PAINT PAVEMENT MARKINGS WHITE	84
T20.1112	12 INCH TEMPORARY WATERBORNE PAINT PAVEMENT MARKINGS WHITE	84
T20.1204	4 INCH TEMPORARY WATERBORNE PAINT PAVEMENT MARKINGS YELLOW	84
T20.1310	TEMPORARY WATERBORNE PAINT PAVEMENT ARROW - STRAIGHT, LEFT, RIGHT OR COMBINED STANDARD 20.1.0	84
T20.2006	6 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	84
T20.2012	12 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	85
T20.2014	4 INCH EPOXY RESIN PAVEMENT MARKINGS YELLOW	85
T20.2020	EPOXY RESIN PAVEMENT ARROW - STRAIGHT, LEFT, RIGHT, OR COMBINED STANDARD 20.1.0	85
T20.2044	EPOXY RESIN PAVEMENT MARKING - HELMETED BICYCLIST SYMBOL WITH ARROW	85
T20.9901	SHARED LANE MARKING TEMPORARY WATERBORNE PAVEMENT MARKING PAINT - 8 MILS	86
T20.9902	BIKE LANE MARKING TEMPORARY WATERBORNE PAVEMENT MARKING PAINT - 8 MILS	86
T20.9903	EPOXY RESIN PAVEMENT MARKING - SHARED LANE MARKING	86
702.0605	PRECAST CATCH BASIN 4' DIAMETER STANDARD 4.4.0	87

Distribution of Quantities

Project Name - Improvements to Dexter Street and Repairs to Bridge #935

Estimate Name - Addendum 1

R.I. Contract No. - 2015-CH-013

FAP Nos: STP-RESF(288)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
020	201.9908 Cont.	21+74 RT		1.00	0006	01
Item 201.9908 Total:				2.00		
021	202.0100	EARTH EXCAVATION	CY			
		DEXTER STREET				
		BRIDGE 935		8.00	0006	01
		CURB AND CURB LOCK		460.00	0006	01
		FROM ITEM CODE 201.0409 (645			0006	01
		SY AT 8" DEPTH)				
		PROJECT WIDE (AS DIRECTED BY		950.00	0006	01
		THE ENGINEER)				
Item 202.0100 Total:				1,418.00		
022	202.0800	GRAVEL BORROW	CY			
		DEXTER STREET				
		BRIDGE		8.00	0006	01
Item 202.0800 Total:				8.00		
023	204.0100	TRIMMING AND FINE GRADING	SY			
		DEXTER STREET				
		FROM ITEM CODE 201.0403		8,504.00	0006	01
		FROM ITEM CODE 201.0409		645.00	0006	01
		FROM ITEM CODE L01.0102		145.00	0006	01
Item 204.0100 Total:				9,294.00		
024	209.9901	INLET SEDIMENT CONTROL DEVICE	EACH			
		DEXTER STREET				
		STATIONS REFERENCED FROM		73.00	0006	01
		ITEM CODE NO. 707.2000 (1/2				
		OF 162 EA)				
Item 209.9901 Total:				73.00		
025	212.2000	CLEANING AND MAINTENANCE OF	LS			

Distribution of Quantities

Project Name - Improvements to Dexter Street and Repairs to Bridge #935
 Estimate Name - Addendum 1
 R.I. Contract No. - 2015-CH-013
 FAP Nos: STP-RESF(288)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
025	212.2000	Cont. EROSION CONTROLS				
		DEXTER STREET				
		DEXTER STREET		1.00	0006	01
				Item 212.2000 Total:		1.00
026	213.0100	PLACEMENT OF MILLINGS BENEATH GUARDRAIL	LF			
		DEXTER STREET				
		61+66RT - 62+64RT		105.00	0006	01
		62+50 LT - 62+68LT		20.00	0006	01
		63+40RT - 63+58RT		20.00	0006	01
		63+44LT - 63+93 LT		55.00	0006	01
				Item 213.0100 Total:		200.00
027	302.0100	GRAVEL BORROW SUBBASE COURSE	CY			
		DEXTER STREET				
		FROM ITEM CODE 201.0409 (645 SY. AT 2' DEPTH)			0006	01
		PROJECT WIDE (AS DIRECTED BY THE ENGINEER)		1,410.00	0006	01
				Item 302.0100 Total:		1,410.00
028	401.3002	CLASS 9.5 HMA FOR LEVELLING	TON			
		DEXTER STREET				
		LEVELLING COURSE		3,200.00	0006	01
				Item 401.3002 Total:		3,200.00
029	401.3005	CLASS 9.5 HMA FOR MISCELLANEOUS WORK	TON			
		DEXTER STREET				
		BACK OF DRIVEWAY AND SIDEWALK PATCH		120.00	0006	01
		CURB LOCK TEMP. PATCH		171.00	0006	01

Distribution of Quantities

Project Name - Improvements to Dexter Street and Repairs to Bridge #935

Estimate Name - Addendum 1

R.I. Contract No. - 2015-CH-013

FAP Nos: STP-RESF(288)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
042	702.0543	Cont.				
		22+74	RT	1.00	0006	01
		23+36	LT	1.00	0006	01
		26+82	LT	1.00	0006	01
		28+67	LT	1.00	0006	01
		33+04	LT	1.00	0006	01
		33+59	LT	1.00	0006	01
		36+22	LT	1.00	0006	01
		38+81	LT	1.00	0006	01
		38+89	RT	1.00	0006	01
		39+05	RT	1.00	0006	01
		41+17	LT	1.00	0006	01
		41+48	RT	1.00	0006	01
		43+74	LT	1.00	0006	01
		44+22	LT	1.00	0006	01
		46+45	RT	1.00	0006	01
		48+50	LT	1.00	0006	01
		60+83	RT	1.00	0006	01
Item 702.0543 Total:				17.00		

043	702.0615	PRECAST CATCH BASIN	6' DIAMETER	EACH		
		STANDARD 4.4.0				
		DEXTER STREET				
		24+67	LT		0006	01
		39+05	RT		0006	01
Item 702.0615 Total:					**DELETED**	

044	702.0713	PRECAST CONCRETE DROP INLET WITH		EACH		
		APRON STONE STANDARD 4.5.1				
		DEXTER STREET				
		22+87	LT	1.00	0006	01
		26+81	LT	1.00	0006	01
		29+44	RT	1.00	0006	01
		38+88	RT	1.00	0006	01

Distribution of Quantities

Project Name - Improvements to Dexter Street and Repairs to Bridge #935
 Estimate Name - Addendum 1
 R.I. Contract No. - 2015-CH-013
 FAP Nos: STP-RESF(288)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
S158	T20.9903	Cont.				
		23+36 RT		1.00	0006	01
		24+21 LT		1.00	0006	01
		25+36 RT		1.00	0006	01
		26+41 LT		1.00	0006	01
		26+93 RT		1.00	0006	01
		28+61 LT		1.00	0006	01
		29+61 RT		1.00	0006	01
		30+88 LT		1.00	0006	01
		31+70 RT		1.00	0006	01
		33+02 LT		1.00	0006	01
		33+63 RT		1.00	0006	01
		35+63 LT		1.00	0006	01
		36+55 RT		1.00	0006	01
		38+12 LT		1.00	0006	01
		39+08 RT		1.00	0006	01
		41+00 LT		1.00	0006	01
		41+65 RT		1.00	0006	01
		43+52 LT		1.00	0006	01
		44+30 RT		1.00	0006	01
		45+94 LT		1.00	0006	01
		46+49 RT		1.00	0006	01
		48+35 LT		1.00	0006	01
		49+12 RT		1.00	0006	01
		50+68 LT		1.00	0006	01
Item T20.9903 Total:				26.00		
159	702.0605	PRECAST CATCH BASIN 4' DIAMETER	EACH			
		STANDARD 4.4.0				
		DEXTER STREET				
		24+67 LT		1.00		
		39+05 RT		1.00		
Item 702.0605 Total:				2.00		