

May 12, 2015

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATION
DEPARTMENT OF ADMINISTRATION

DIVISION OF PURCHASES BID NO. 7549525

RHODE ISLAND DEPARTMENT OF TRANSPORTATION

RHODE ISLAND CONTRACT NO.2015-CR-056

FEDERAL-AID PROJECT NO. FAP Nos: STP-RESF(293)

2015 Rubberized Asphalt Chip Seal

Statewide

CITY/TOWN OF Coventry, Foster, Little Compton, Richmond, South Kingstown, Tiverton, Smithfield

COUNTY OF KENT, PROVIDENCE, NEWPORT, WASHINGTON

NOTICE TO PROSPECTIVE BIDDERS

ADDENDUM NO. 1 Prospective bidders and all concerned are hereby notified of the following changes in the Plans, Specifications, Proposal and Distribution of Quantities for this contract. These changes shall be incorporated in the Plans, Specifications, Proposal and Distribution of Quantities, and shall become an integral part of the Contract Documents.

A. Contract Dates

1. Phase 1 Completion Date
Phase 1 Completion Date Updated To "07/30/2016".
2. Substantial Completion Date
Substantial Completion Date Updated To "10/15/2016".

B. Contract Documents


1. Special Provisions/Construction Specific
Delete page CS-3 in its' entirety and replace with revised page CS-3 (R-1) attached to this addendum. The post placement sweeping applications were added and pavement markings paragraph c. 4. was revised.

C. Specification Change/Addition

1. Job Specific
Delete page JS-2 in its' entirety and replace with revised page JS-2 (R-1) attached to this addendum.

D. Other Item Changes

1. 929.0110 - FIELD OFFICE
Quantity Updated To "7.00".
2. 931.9901 - POST WINTER-CLEANING AND SWEEPING PAVEMENT
Quantity Updated To "1000.00".
3. 412.0100 - RUBBERIZED ASPHALT CHIP SEALING
Quantity Updated To "293040.00".
4. T20.2006 - 6 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE
Quest Item Deleted.
5. T20.2014 - 4 INCH EPOXY RESIN PAVEMENT MARKINGS YELLOW
Quest Item Deleted.



RI Department of Transportation
Chief Engineer

- b. **Utilities and Drainage structures.** Adjustments of all manholes, gates, and catch basins shall be completed prior to application of the surface seal in accordance with Section 707 and 713. All adjustments shall comply with the rules and regulations of the city or town.

Post Placement Sweepings. The following times apply:

1. **Five (5) to seven (7) days after the rubberized asphalt chip sealing operation applies to Rt. 77, Rt. 91 and all statewide roads listed in Table 1;**
2. **Between October 15 and November 15 after the rubberized chip sealing operation applies to Rt. 77 only;**
3. **Starting April 1st at the end of the first winter after the rubberized asphalt chip sealing operation applies to Rt. 77 only.**

c. **Pavement Markings.**

1. It is the Contractor's responsibility to reflect the exact location of all existing pavement markings with new markings, including crosswalks, stop bars, beginning and end of passing and no passing zone markings, edge markers, arrow and "ONLY" markings. The contractor shall make all necessary arrangements to record the existing marking locations before commencing with surface sealing operations.

2. All pavement markings are to be located in accordance with the requirements of the "Manual on Uniform Traffic Control Devices". All existing striping must be replaced to match the traffic markings that existed prior to the application of the rubberized asphalt chip seal unless otherwise detailed in these specifications or directed by the Engineer.

3. Temporary pavement markings are required as part of this contract. Before the end of each workday, any pavement marking that has been covered or partially covered with rubberized asphalt chip sealing, hot mix asphalt or obliterated shall be replaced with an approved temporary pavement marking. These temporary markings shall be installed using fast-drying, waterborne pavement marking paint. During the workday, until the temporary marking is applied, the contractor shall be responsible for providing any necessary traffic control which shall be included in the contract bid item for temporary pavement marking.

4. **Permanent pavement markings are not required as part of this contract.**

d. **Warranty.** The Contractor at no cost to the Department shall replace any material or repair any workmanship found to be defective by the Engineer for up to one year from the date of placement. Upon notification by the Engineer, as soon as weather conditions permit, the Contractor shall repair such defective areas. The repair work shall be in accordance with Section 412.0100. Any item necessary to complete this work, including traffic control, shall be provided by the Contractor at no cost to the Department.

CODE 12.108.1000

PROSECUTION AND PROGRESS

In accordance with **Section 12.108.08, Failure to Complete on Time, Para. a., Phased and Interim Completion** the following defines the Phase and Interim Completion Dates and Associated Liquidated Damages.

Phase 1 Completion: July 30, 2016.

All work shall be completed for the Phase 1 Completion. Completion will be the point at which all work within the phase is complete such that it can be safely and effectively used by the public and when the following criteria are realized: all rubberized asphalt chip sealing work is completed.

Liquidated damages: \$1,200.00 per calendar day.

Substantial Completion: October 15, 2016.

All Contract work shall be completed, as defined by **Section 12.101.71**.

Liquidated damages: \$550.00 per calendar day.

Table of Contents - Distribution of Quantities

Project Name - 2015 Rubberized Asphalt Chip Seal

Estimate Name - Addendum /RACS 15

R.I. Contract No. - 2015-CR-056

FAP Nos: STP-RESF(293)

<u>ItemCode</u>	<u>Description</u>	<u>Page</u>
401.3005	CLASS 9.5 HMA FOR MISCELLANEOUS WORK	1
412.0100	RUBBERIZED ASPHALT CHIP SEALING	1
713.8300	ADJUST GAS GATE BOXES TO GRADE	1
914.5010	FLAGPERSONS	1
914.5020	FLAGPERSONS - OVERTIME	1
929.0110	FIELD OFFICE	1
931.0110	CLEANING AND SWEEPING PAVEMENT	1
931.9901	POST WINTER-CLEANING AND SWEEPING PAVEMENT	2
936.0110	MOBILIZATION	2
T20.0004	4 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	2
T20.0104	4 INCH YELLOW FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	2
T20.1000	REMOVE EXISTING PAVEMENT MARKINGS	2
T20.2006	** ITEM DELETED **	2
T20.2014	** ITEM DELETED **	3
T20.9901	6 INCH BLACK FAST-DRYING WATERBORNE PAVEMENT MARKING PAINT	3

Distribution of Quantities

Project Name - 2015 Rubberized Asphalt Chip Seal
 Estimate Name - Addendum /RACS 15
 R.I. Contract No. - 2015-CR-056
 FAP Nos: STP-RESF(293)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
001	401.3005	CLASS 9.5 HMA FOR MISCELLANEOUS WORK	TON			
		PROJECTWIDE				
		ALL ROADS		1,300.00	0006	01
		Item 401.3005 Total:		1,300.00		
002	412.0100	RUBBERIZED ASPHALT CHIP SEALING	SY			
		PROJECTWIDE				
		ALL ROADS		293,040.00	0006	01
		Item 412.0100 Total:		293,040.00		
003	713.8300	ADJUST GAS GATE BOXES TO GRADE	EACH			
		PROJECTWIDE				
		VARIOUS ROADS		4.00	0006	01
		Item 713.8300 Total:		4.00		
004	914.5010	FLAGPERSONS	MHRS			
		PROJECTWIDE				
		ALL ROADS		700.00	0006	01
		Item 914.5010 Total:		700.00		
005	914.5020	FLAGPERSONS - OVERTIME	MHRS			
		PROJECTWIDE				
		ALL ROADS		180.00	0006	01
		Item 914.5020 Total:		180.00		
006	929.0110	FIELD OFFICE	PMO			
		PROJECTWIDE				
		PROJECTWIDE		7.00	0006	01
		Item 929.0110 Total:		7.00		
007	931.0110	CLEANING AND SWEEPING PAVEMENT	HSY			
		PROJECTWIDE				

Distribution of Quantities

Project Name - 2015 Rubberized Asphalt Chip Seal
 Estimate Name - Addendum /RACS 15
 R.I. Contract No. - 2015-CR-056
 FAP Nos: STP-RESF(293)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
007	931.0110 Cont.	ALL ROADS		6,812.00	0006	01
				Item 931.0110 Total:	6,812.00	
008	931.9901	POST WINTER-CLEANING AND SWEEPING PAVEMENT PROJECTWIDE ALL ROADS	HSY	1,000.00	0006	01
				Item 931.9901 Total:	1,000.00	
009	936.0110	MOBILIZATION PROJECTWIDE PROJECTWIDE	LS	1.00	0006	01
				Item 936.0110 Total:	1.00	
010	T20.0004	4 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT PROJECTWIDE ALL ROADS	LF	201,696.00	0006	01
				Item T20.0004 Total:	201,696.00	
011	T20.0104	4 INCH YELLOW FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT PROJECTWIDE ALL ROADS	LF	201,696.00	0006	01
				Item T20.0104 Total:	201,696.00	
012	T20.1000	REMOVE EXISTING PAVEMENT MARKINGS PROJECTWIDE ALL ROADS	LF	403,392.00	0006	01
				Item T20.1000 Total:	403,392.00	

Distribution of Quantities

Project Name - 2015 Rubberized Asphalt Chip Seal
 Estimate Name - Addendum /RACS 15
 R.I. Contract No. - 2015-CR-056
 FAP Nos: STP-RESF(293)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
013	T20.9900	DEPARTMENTAL				
				158,400.00		
				Item T20.9900 Total:		158,400.00
014	T20.9901	6 INCH BLACK FAST-DRYING WATERBORNE PAVEMENT MARKING PAINT PROJECTWIDE	LF			
				158,400.00		
				Item T20.9901 Total:		158,400.00
015	T20.9901	6 INCH BLACK FAST-DRYING WATERBORNE PAVEMENT MARKING PAINT PROJECTWIDE	LF			
				158,400.00		
				Item T20.9901 Total:		158,400.00