



STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS

Department of Administration
DIVISION OF PURCHASES
One Capitol Hill
Providence, RI 02908-5855

Tel: (401) 574-8100
Fax: (401) 574-8387
Website: www.purchasing.ri.gov

November 18, 2015

ADDENDUM NUMBER THREE

RFQ #7549583

TITLE: Security Camera System for Maximum Security

Closing Date and Time: 12/4/15 at 10:00 AM (NOTE CHANGE)

Per the issuance of this ADDENDUM #3 (3 pages) the following change is noted:

Due to technical difficulties with the Division of Purchasing website bid closing date and time has been changed.

This addendum answers these questions sent in on line and accepted until November 6, 2015 at 5pm (EST).

On drawing E1-1, the camera # 187 is marked as **non WP fixed camera** to be mounted just below the cat walk

On drawing ES-1, the camera # 187 is marked as **WP fixed camera** to be mounted on the cat walk

On drawing E1-1, the camera # 183 is marked as **5 Megapixel non WP fixed camera**

On drawing ES-1, the camera # 183 is marked as **WP fixed camera** to be mounted in vehicle inspection area

Also, the camera # 114 and 205 do not show on the drawings.

Please verify the correct camera type and locations for camera number 114, 183, 187 and 205.

See attached.

END OF QUESTIONS

RHODE ISLAND
195 FRANCES AVENUE, BUILDING 2
CRANSTON, RHODE ISLAND 02910
P: 401-438-7733
F: 401-438-7620



www.cec-engineering.com

MASSACHUSETTS
120 MAPLE STREET, SUITE 304
SPRINGFIELD, MASSACHUSETTS 01103
P: 413-519-7542
F: 413-736-1294

November 12, 2015

Mr. David Cadoret
Chief Buyer
1 Capitol Hill, 2nd Floor
Providence, RI 02908

RE: Maximum Security Camera Upgrades
Solicitation #7549583
CEC Project No. 20140149

Dear Mr. Cadoret:

Please include the following items in your next addendum #3 related to the above referenced project:

Drawings:

Drawing ES-1

- Item #1: The installation of the Cat. 6 cable for camera 91 on tower 4 shall be accomplished as follows:
1. There is an existing 1" conduit going from tower 4 underground to the southwest corner of the building 1, with a 25 pair telephone cable. Once in the building the conduit with cable runs across the building to the electric room in the southeast corner of the building. The contractor must remove the 25 pair cable and provide a 4 pair Cat. 3 twisted pairs and a 6 strand multi-mode loose tube fiber optic cable from the IDF closet in building 1. Terminate the cat. 3 cable at each end to restore telephone service to tower 4. Provide conduit raceways in building 1 as needed for getting the fiber optic cable to the IDF closet shown on drawing E1-4. In tower 4 provide an APC smart U.P.S. 1000 V.A. with LCD, 120 volts and 10 minutes of battery back-up.
- Item #2: Camera 187 is not 5 mega pixels, but it is a weatherproof fixed camera. Camera 183 is also weatherproof fixed camera.

Drawing E1.1

- Item #1: The fixed camera shown as #144 should be #114.
- Item #2: At the northeast corner of the administration building, provide a corner mount, weatherproof PTZ. The camera number for this camera shall be 205.

Mr. David Cadoret
Chief Buyer
RE: Maximum Security Camera Upgrades
November 12, 2015
Page 2

Specifications:

Item #1:

Section 16785-IP CCTV system, page 1 paragraph 1.1.A.1.j: Change the last sentence to read, "Provide all programming and configuration of the existing MTI system to display live camera call up on the new genetic system upon each door or gate being opened".

Item #2:

Section 16785 – IP CCTV System, page 2, add paragraph 1.1.A.1.I. The new camera system shall connect to the existing Genetec federation on the Department of Corrections campus, so each new camera can be viewed on every existing Genetec workstation. Provide Genetec federation licenses for each system.

END OF ADDENDUM

Very truly yours,
Creative Environment Corp.



Greg Driggers
Senior Project Manager

