



Request for Quote

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS
ONE CAPITOL HILL
PROVIDENCE RI 02908

CREATION DATE : 18-SEP-15
BID NUMBER: 7549785,3
TITLE: MODIFICATIONS/REPAIRS TO SIDEWALKS,
WALKWAYS, ENTRYWAYS AND CURBS AT DLT

BLANKET START : 01-OCT-15
BLANKET END : 30-JUN-16
BID CLOSING DATE AND TIME:24-SEP-2015 02:00:00

BUYER: Cadoret, David
PHONE #: N/A

B
I
L
L
L
T
O
DOA CONTROLLER
ONE CAPITOL HILL, 4TH FLOOR
SMITH ST
PROVIDENCE, RI 02908
US

S
H
I
P
T
O
DEPARTMENT OF LABOR AND TRAINING
1511 PONTIAC AVENUE, BLDG. #72
CRANSTON, RI 02920-4407
US

Requisition Number:

Note to Bidders: THERE WILL BE A MANDATORY PRE BID CONFERENCE AS PER ATTACHED.

Amendment Description: THIS ADDENDUM POSTS ANSWER TO QUESTION SENT IN ON LINE.

END OF QUESTIONS.

| Line | Description | Quantity | Unit | Unit Price | Total |
|------|---|----------|-------|------------|-------|
| 1 | MODIFICATIONS/REPAIRS TO SIDEWALKS, WALKWAYS, ENTRYWAYS AND CURBS AS PER ATTACHED SPECIFICATIONS FOR DLT AT CENTER GENERAL COMPLEX, 1511 PONTIAC AVE, CRANSTON AND 1330 MAIN ST, WEST WARWICK. BID AS TOTAL PRICE | 1.00 | Total | | |

Delivery: _____

Terms of Payment: _____

It is the Vendor's responsibility to check and download any and all addenda from the RIVIP. This offer may not be considered unless a signed RIVIP generated Bidder Certification Cover Form is attached and the Unit Price column is completed. The signed Certification Cover Form must be attached to the front of the offer



STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS

Department of Administration
DIVISION OF PURCHASES
One Capitol Hill
Providence, RI 02908-5855

Tel: (401) 574-8100
Fax: (401) 574-8387
Website: www.purchasing.ri.gov

September 18, 2015
ADDENDUM NUMBER THREE
RFQ # 7549785

**TITLE: MODIFICATIONS/REPAIRS TO SIDEWALKS, WALKWAYS, ENTRYWAYS AND
CURBS AT DLT**

Closing Date and Time: 9/24/15 at 2:00 PM

Per the issuance of this ADDENDUM #3 (1 page) the following is noted:

This addendum answers question to addendum #2 sent in on line.

Q. In Addendum #2 it refers to "All sidewalk and poured curbing is the responsibility of the contractor." "Everything is DOT Standard." The Rhode Island Standard Details do not show a poured in place curb and sidewalk. The RI Standard Detail 43.1.0 does show a 4" cement concrete sidewalk and RI Standard Detail 7.1.0 does show precast concrete curb. Would you please indicate if using the above details is the intention at this location?

A. Yes, DOT 43.1.0 & 7.1.0 are the details referenced for the concrete sidewalk & precast concrete curbing, respectively. Please note, in addition to the requirements, to adhere to all DOT standards. The cast in place concrete sidewalks are specified to be a minimum of 5" thick using a minimum of 4000 psi concrete mix.

New precast concrete curbing shall be set in place and locked in with a poured concrete bed and then backfilled and compacted to the standards referenced. Cast in place concrete sidewalks will be installed per the referenced standard independent of the curbing installation.

END OF QUESTIONS