

October 4, 2016

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATION
DEPARTMENT OF ADMINISTRATION

DIVISION OF PURCHASES BID NO. 7550974

RHODE ISLAND DEPARTMENT OF TRANSPORTATION

RHODE ISLAND CONTRACT NO.2016-CH-058

FEDERAL-AID PROJECT NO. FAP Nos: STP-RESF (333)

I-95 Resurfacing (Elmwood Avenue to Eddy Street)

Elmwood Avenue to Eddy Street

CITY/TOWN OF Providence

COUNTY OF PROVIDENCE

NOTICE TO PROSPECTIVE BIDDERS

ADDENDUM NO. 1 Prospective bidders and all concerned are hereby notified of the following changes in the Plans, Specifications, Proposal and Distribution of Quantities for this contract. These changes shall be incorporated in the Plans, Specifications, Proposal and Distribution of Quantities, and shall become an integral part of the Contract Documents.

A. Specifications-Job Specific

1. JS-ii

Delete page JS-ii in its entirety and replace it with revised page JS-ii(R-1) attached to this Addendum No. 1. Rhode Island Diesel Emissions Reduction Program specification has been added to the index.

2. JS-47

Insert new page JS-47 attached to this Addendum No. 1. Rhode Island Diesel Emissions Reduction Program specification has been added to the contract.

B. Distribution of Quantities

1. Index Pages

Delete Pages Index 1 and Index 2 in their entirety and replace them with revised Pages Index 1(R-1) and Index 2(R-1) attached to this Addendum No. 1. Items that have been revised are indicated in bold type.

2. Page 3

Delete Page 3 in its entirety and replace it with revised Page 3(R-1) attached to this Addendum No. 1. The quantities for Item Code 402.9901-Friction Course have been revised.

3. Page 3a

Insert new Page 3a attached to this Addendum No. 1. This page was generated by QUEST.

4. Page 4

Delete Page 4 in its entirety and replace it with revised Page 4(R-1) attached to this Addendum No. 1. The quantities for Item Code 402.9901-Friction Course and Item Code 402.9902-Friction Course for Shoulders have been revised.

5. Page 4a

Insert new Page 4a attached to this Addendum No. 1. This page was generated by QUEST.

6. Pages 11 and 12

Delete Pages 11 and 12 in their entirety and replace them with revised Pages 11(R-1) and 12(R-1) attached to this Addendum No. 1. The quantities for Item Code 914.5010-Flagpersons, Item Code 914.5020, Flagpersons – Overtime, and Item Code 922.0100 - Temporary Construction Signs Standard 29.1.0 and 27.1.1, have been revised.

7. Page 13

Delete Page 13 in its entirety and replace it with revised Page 13(R-1) attached to this Addendum No. 1. The quantities for Item Code 928.9901 - Truck Mounted Attenuator With Truck Mounted Flashing Arrow Board, and Item Code 929.0110 – Field Office, have been revised.

8. Page 17

Delete Page 17 in its entirety and replace it with revised Page 17(R-1) attached to this Addendum No. 1. The quantities for Item Code T20.0006 - 6 Inch White Fast - Drying Waterborne Pavement Marking Paint, and Item Code T20.0012 - 12 Inch White Fast - Drying Waterborne Pavement Marking Paint, have been revised.

9. Page 17a

Insert new Page 17a attached to this Addendum No. 1. This page was generated by QUEST.

10. Page 18

Delete Page 18 in its entirety and replace it with revised Page 18(R-1) attached to this Addendum No. 1. The quantities for Item Code T20.0106 - 6 Inch Yellow Fast - Drying Waterborne Pavement Marking Paint and Item Code T20.1106 6 Inch Waterborne Pavement Markings White have been revised.

11. Page 19

Delete Page 19 in its entirety and replace it with revised Page 19(R-1) attached to this Addendum No. 1. The quantities for Item Code T20.1112 - 12 Inch Temporary Waterborne Paint Pavement Markings White and Item Code T20.1206 6 Inch Temporary Waterborne Paint Pavement Markings Yellow have been revised.



RI Department of Transportation
Chief Engineer *FR*

**INDEX
SPECIFICATIONS – JOB SPECIFIC**

(R-1)

<u>CODE</u>	<u>TITLE</u>	<u>PAGE</u>
T20.9901	Reflectorized Recessed Pavement Marker (Slotted in Pavement) White	JS-45
T20.9902	Reflectorized Recessed Pavement Marker (Slotted in Pavement) Yellow	
T20.9903	Reflectorized Recessed Pavement Marker (Slotted in Pavement) White/Red	
T20.9904	Reflectorized Recessed Pavement Marker (Slotted in Pavement) Yellow/Red	
	Rhode Island Diesel Emissions Reduction Program	JS-47

Table of Contents - Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

ItemCode	Description	Page
201.0401	REMOVE AND DISPOSE GRANITE CURB	1
201.0403	REMOVE AND DISPOSE SIDEWALKS	1
201.0415	REMOVE AND DISPOSE GUARDRAIL AND POST ALL TYPES	1
201.0428	REMOVE AND DISPOSE FRAME AND GRATE OR FRAME AND COVER	1
201.9903	REMOVE AND DISPOSE EXISTING LOOP AND JUNCTION BOX	1
202.0100	EARTH EXCAVATION	1
204.0100	TRIMMING AND FINE GRADING	2
206.9901	INLET SEDIMENT CONTROL DEVICE	2
212.2000	CLEANING AND MAINTENANCE OF EROSION CONTROLS	2
302.0100	GRAVEL BORROW SUBBASE COURSE	3
401.9901	PAY ADJUSTMENTS	3
401.9910	MODIFIED CLASS 9.5 HMA FOR BRIDGE DECKS	3
402.9901	FRICITION COURSE	3
402.9902	FRICITION COURSE FOR SHOULDERS	4
403.0300	ASPHALT EMULSION TACK COAT	4
415.9901	INTELLIGENT COMPACTION FOR HMA	5
601.0300	CLASS A PORTLAND CEMENT CONCRETE	5
702.0516	FRAME AND GRATE, HIGH CAPACITY, STANDARD 6.3.4	5
702.0522	FRAME AND COVER STANDARD 6.2.1	5
704.0100	RECONSTRUCT CATCH BASIN/CORBEL CONES	5
704.0300	RECONSTRUCT CATCH BASIN/VERTICAL WALLS	6
707.1900	ADJUST FRAME & COVER TO GRADE	6
707.2000	ADJUST FRAME AND GRATE TO GRADE	6
708.9040	CLEANING AND FLUSHING PIPE ALL SIZES	6
708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	7
708.9042	CLEANING MANHOLES ALL TYPES AND SIZES	7
808.1675	POLYURETHANE ELASTOMERIC JOINT SEALANT	8
818.9901	PORTLAND CEMENT CONCRETE DECK REPAIRS (PARTIAL DEPTH REMOVAL)	8
821.1690	SAW & SEALING JOINTS IN BITUMINOUS CONCRETE PAVEMENT	8
823.1750	ASPHALTIC EXPANSION JOINT SYSTEM	8
839.0100	PARTIAL-DEPTH REMOVAL AND DISPOSAL OF BITUMINOUS PAVEMENT FROM CONCRETE BRIDGE DECKS	8
839.0200	FULL DEPTH REMOVAL AND DISPOSAL OF BITUMINOUS PAVEMENT FROM CONCRETE BRIDGE DECKS	9
901.0101	GUARDRAIL STEEL BEAM SINGLE FACE EARTH AND ASPHALT	9
901.0198	GUARDRAIL END TREATMENT, NON-ENERGY ABSORBING TERMINAL	9
903.9901	TRAFFIC PVC JUNCTION BOX AND WOODEN MOUNTING POST	9
905.0110	PORTLAND CEMENT SIDEWALK MONOLITHIC STANDARD 43.1.0	10
906.0110	GRANITE CURB, QUARRY SPLIT STRAIGHT, STANDARD 7.3.0	10
906.0700	REMOVE, HANDLE, HAUL TRIM RESET CURB EDGING, STRAIGHT, CIRCULAR ALL TYPES	10
914.5010	FLAGPERSONS	10
914.5020	FLAGPERSONS - OVERTIME	11
922.0100	TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1	11
923.0105	DRUM BARRICADE STANDARD 26.2.0	12
923.0120	PLASTIC PIPE BARRICADE STANDARD 26.3.0	12
923.0200	FLUORESCENT TRAFFIC CONES STANDARD 26.1.0	13
924.0113	ADVANCE WARNING ARROW PANEL	13
925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	13
928.9901	TRUCK MOUNTED ATTENUATOR WITH TRUCK MOUNTED FLASHING ARROW BOARD	13
929.0110	FIELD OFFICE	13
931.0110	CLEANING AND SWEEPING PAVEMENT	13
932.0100	CUTTING AND MATCHING ASPHALT	14
932.0200	FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT	15

Index: 2

Table of Contents - Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
R.I. Contract No. - 2016-CH-058
FAP Nos: STP-RESF (333)

<u>ItemCode</u>	<u>Description</u>	<u>Page</u>
935.0400	REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING	15
936.0100	MOBILIZATION AND DEMOBILIZATION	15
937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	15
942.0200	DETECTABLE WARNING PANEL STANDARD 48.1.0	16
943.0200	TRAINEE MAN-HOURS	16
L01.0102	LOAM BORROW 4 INCHES DEEP	16
L02.0101	GENERAL HIGHWAY SEEDING (TYPE 1)	16
T05.1030	ADJUST HANDHOLE TO GRADE	16
T06.9901	1" FLEXIBLE METALLIC LIQUID TIGHT CONDUIT	17
T13.9901	TRAFFIC DETECTOR - LOOP (DRY CUT)	17
T20.0006	6 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	17
T20.0012	12 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	17
T20.0106	6 INCH YELLOW FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	18
T20.0606	TEMPORARY PAVEMENT MARKING (TAPE) YELLOW AND/OR WHITE - 6 INCH	18
T20.0900	BI-DIRECTIONAL CONTROL DEVICE STANDARD 20.2.0	18
T20.1000	REMOVE EXISTING PAVEMENT MARKINGS	18
T20.1106	6 INCH TEMPORARY WATERBORNE PAINT PAVEMENT MARKINGS WHITE	18
T20.1112	12 INCH TEMPORARY WATERBORNE PAINT PAVEMENT MARKINGS WHITE	19
T20.1206	6 INCH TEMPORARY WATERBORNE PAINT PAVEMENT MARKINGS YELLOW	19
T20.2006	6 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	19
T20.2012	12 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE	20
T20.2016	6 INCH EPOXY RESIN PAVEMENT MARKINGS YELLOW	20
T20.2022	EPOXY RESIN PAVEMENT MARKING WORD "ONLY" STANDARD 20.1.0	21
T20.2042	EPOXY RESIN PAVEMENT MARKING - YIELD LINE SYMBOL	21
T20.2054	EPOXY RESIN PAVEMENT MARKING WORD "EXIT"	21
T20.9901	REFLECTORIZED RECESSED PAVEMENT MARKER (SLOTTED IN PAVEMENT) WHITE	21
T20.9902	REFLECTORIZED RECESSED PAVEMENT MARKER (SLOTTED IN PAVEMENT) YELLOW	22
T20.9903	REFLECTORIZED RECESSED PAVEMENT MARKER (SLOTTED IN PAVEMENT) WHITE/RED	22
T20.9904	REFLECTORIZED RECESSED PAVEMENT MARKER (SLOTTED IN PAVEMENT) YELLOW/RED	22
T20.9957	EPOXY RESIN PAVEMENT MARKING WORD "CURVE AHEAD"	23
T20.9958	THERMOPLASTIC PAVEMENT MARKINGS - ROUTE SHIELD SYMBOL	23

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
010	302.0100	GRAVEL BORROW SUBBASE COURSE	CY			
		RAMPS				
		FROM ITEM 202.0100		14.00	0005	01
		Item 302.0100 Total:		14.00		
011	401.9901	PAY ADJUSTMENTS	EACH			
		I-95				
		PROJECT WIDE		80,000.00	0005	01
		Item 401.9901 Total:		80,000.00		
012	401.9910	MODIFIED CLASS 9.5 HMA FOR BRIDGE DECKS	TON			
		BRIDGES				
		BRIDGE NO. 651		85.00	0005	01
		BRIDGE NO. 652		89.00	0005	01
		BRIDGE NO. 653		74.00	0005	01
		BRIDGE NO. 655		213.00	0005	01
		BRIDGE NO. 658		82.00	0005	01
		BRIDGE NO. 659		272.00	0005	01
		Item 401.9910 Total:		815.00		
013	402.9901	FRICITION COURSE	TON			
		I-95				
		114+30 - 117+90 (NB)		274.00	0005	01
		119+50 - 131+40		1,870.00	0005	01
		1217+00 - 1225+50 (SB)		760.00	0005	01
		132+30 - 188+80		8,615.00	0005	01
		190+20 - 200+90		1,786.00	0005	01
		201+15 - 213+80		1,990.00	0005	01
		214+25 - 216+65		343.00	0005	01
		217+25 - 225+70		1,396.00	0005	01
		FROM ITEM 402.9902		-4,640.00	0005	01
		PROJECT WIDE				

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
013	402.9901	Cont. AS DIRECTED BY THE ENGINEER		700.00	0005	01
		RAMPS				

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
013	402.9901	Cont.				
		AR-5		170.00	0005	01
		AR-6		218.00	0005	01
		BR-5		337.00	0005	01
		BR-6		96.00	0005	01
		BR-7		365.00	0005	01
		ROGER WILLIAMS AVE OFF		205.00	0005	01
Item 402.9901 Total:				14,485.00		
014	402.9902	FRICITION COURSE FOR SHOULDERS	TON			
		I-95 (NB) LT				
		114+20 - 227+00		1,202.00	0005	01
		I-95 (NB) RT				
		121+00 - 170+00		538.00	0005	01
		182+00 - 196+80		150.00	0005	01
		200+50 - 225+00		259.00	0005	01
		I-95 (SB) LT				
		119+90 - 125+70		65.00	0005	01
		131+00 - 165+00		370.00	0005	01
		185+00 - 195+00		121.00	0005	01
		198+00 - 214+00		170.00	0005	01
		214+00 - 1225+00		405.00	0005	01
		I-95 (SB) RT				
		119+50 - 227+00		1,160.00	0005	01
		PROJECT WIDE				
		AS DIRECTED BY ENGINEER		200.00	0005	01
Item 402.9902 Total:				4,640.00		
015	403.0300	ASPHALT EMULSION TACK COAT	SY			
		BRIDGES				
		BRIDGE NO. 651		1,005.00	0005	01
		BRIDGE NO. 652		1,045.00	0005	01
		BRIDGE NO. 653		865.00	0005	01
		BRIDGE NO. 655		2,315.00	0005	01

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
R.I. Contract No. - 2016-CH-058
FAP Nos: STP-RESF (333)

<u>Item</u> <u>No.</u>	<u>Item Code</u>	<u>Description</u>	<u>UM</u>	<u>Qty.</u>	<u>Pay</u> <u>Code</u>	<u>Seq.</u> <u>No.</u>
015	403.0300 Cont.	BRIDGE NO. 658		970.00	0005	01
		BRIDGE NO. 659		2,750.00	0005	01

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
039	914.5010 Cont.	PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		620.00	0005	01
		I-95 RESURFACING WORK		640.00	0005	01
				Item 914.5010 Total:	1,900.00	
040	914.5020	FLAGPERSONS - OVERTIME	MHRS			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		550.00	0005	01
				Item 914.5020 Total:	550.00	
041	922.0100	TEMPORARY CONSTRUCTION SIGNS	SF			
		STANDARD 29.1.0 AND 27.1.1				
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		335.25	0005	01
		E5-1		60.00	0005	01
		E5-2		24.00	0005	01
		G20-2		16.00	0005	01
		M1-1 195		6.25	0005	01
		M1-1 95		10.00	0005	01
		M3-1		4.00	0005	01
		M4-10L		12.00	0005	01
		M4-8		24.00	0005	01
		M4-8A		6.00	0005	01
		M6-2L		8.00	0005	01
		M6-2R B		8.00	0005	01
		M6-3		18.00	0005	01
		R11-2		24.00	0005	01
		R1-2 48X48X48		14.00	0005	01
		R9-11		6.00	0005	01
		R9-9		4.00	0005	01
		RI STD 27.1.1 48X72		192.00	0005	01
		STREET TABS		72.00	0005	01
		W13-1P		12.50	0005	01

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
041	922.0100	Cont.				
		W1-4L 48X48		16.00	0005	01
		W1-4R 48X48		32.00	0005	01
		W20-1 36X36		36.00	0005	01
		W20-1 48X48		160.00	0005	01
		W20-5AL 48X48		64.00	0005	01
		W20-5AR 48X48		64.00	0005	01
		W20-5L 36X36		36.00	0005	01
		W20-5L 48X48		64.00	0005	01
		W20-5R 36X36		36.00	0005	01
		W20-5R 48X48		64.00	0005	01
		W20-7		18.00	0005	01
		W21-5 36X36		18.00	0005	01
		W3-2 48X48		32.00	0005	01
		W4-1 48X48		32.00	0005	01
		W4-2L 48X48		64.00	0005	01
		W4-2R 48X48		64.00	0005	01
		W4-3 48X48		16.00	0005	01
		W5-1 48X48		32.00	0005	01
		W8-1		128.00	0005	01
		W8-15		128.00	0005	01
		W8-15P		40.00	0005	01
Item 922.0100 Total:				2,000.00		
042	923.0105	DRUM BARRICADE STANDARD 26.2.0	B DAY			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		1,000.00	0005	01
Item 923.0105 Total:				1,000.00		
043	923.0120	PLASTIC PIPE BARRICADE STANDARD	EACH			
		26.3.0				
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		4.00	0005	01
Item 923.0120 Total:				4.00		

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
044	923.0200	FLUORESCENT TRAFFIC CONES STANDARD	EACH			
		26.1.0				
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		500.00	0005	01
		Item 923.0200 Total:		500.00		
045	924.0113	ADVANCE WARNING ARROW PANEL	PDAY			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		400.00	0005	01
		Item 924.0113 Total:		400.00		
046	925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	PDAY			
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		70.00	0005	01
		BRIDGE WORK		160.00	0005	01
		RESURFACING		70.00	0005	01
		Item 925.0112 Total:		300.00		
047	928.9901	TRUCK MOUNTED ATTENUATOR WITH	HRS			
		TRUCK MOUNTED FLASHING ARROW BOARD				
		PROJECT WIDE				
		AS DIRECTED BY THE ENGINEER		1,500.00	0005	01
		BRIDGE WORK		1,600.00	0005	01
		RESURFACING		700.00	0005	01
		Item 928.9901 Total:		3,800.00		
048	929.0110	FIELD OFFICE	PMO			
		PROJECT WIDE				
		PROJECT DURATION		18.00	0005	01
		Item 929.0110 Total:		18.00		
049	931.0110	CLEANING AND SWEEPING PAVEMENT	HSY			
		BRIDGES				

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
059	T05.1030 Cont.	GP-12		1.00	0005	01
		GP-2		6.00	0005	01
		GP-3		4.00	0005	01
		GP-4		11.00	0005	01
		GP-5		10.00	0005	01
		GP-6		13.00	0005	01
		GP-7		10.00	0005	01
		GP-8		7.00	0005	01
Item T05.1030 Total:				82.00		
S060	T06.9901	1" FLEXIBLE METALLIC LIQUID TIGHT CONDUIT	LF			
		ROGER WILLIAMS AVE RAMP				
		RAMP		10.00	0005	01
Item T06.9901 Total:				10.00		
S061	T13.9901	TRAFFIC DETECTOR - LOOP (DRY CUT)	LF			
		ROGER WILLIAMS AVE RAMP				
		AS DIRECTED BY THE ENGINEER		78.00	0005	01
Item T13.9901 Total:				78.00		
062	T20.0006	6 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	LF			
		PROJECT WIDE				
		2ND LAYER		60,000.00	0005	01
		FROM ITEM T20.2006		60,000.00	0005	01
Item T20.0006 Total:				120,000.00		
063	T20.0012	12 INCH WHITE FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT	LF			
		PROJECT WIDE				
		2ND LAYER		9,200.00	0005	01
		FROM ITEM T20.2012		9,200.00	0005	01

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
063	T20.0012	Cont.				
Item T20.0012 Total:				18,400.00		

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
064	T20.0106	6 INCH YELLOW FAST - DRYING WATERBORNE PAVEMENT MARKING PAINT PROJECT WIDE	LF			
		2ND LAYER		31,000.00	0005	01
		FROM ITEM T20.2016		31,000.00	0005	01
		Item T20.0106 Total:		62,000.00		
065	T20.0606	TEMPORARY PAVEMENT MARKING (TAPE) YELLOW AND/OR WHITE - 6 INCH PROJECT WIDE	LF			
		AS DIRECTED BY THE ENGINEER		1,000.00	0005	01
		Item T20.0606 Total:		1,000.00		
066	T20.0900	BI-DIRECTIONAL CONTROL DEVICE STANDARD 20.2.0 AS DIRECTED BY THE ENGINEER	EACH			
		RAMP AR-6		4.00	0005	01
		RAMP BR-5		3.00	0005	01
		ROGER WILLIAMS AVE RAMP		1.00	0005	01
		THURBERS AVE		2.00	0005	01
		Item T20.0900 Total:		10.00		
067	T20.1000	REMOVE EXISTING PAVEMENT MARKINGS PROJECT WIDE	LF			
		AS DIRECTED BY THE ENGINEER		1,000.00	0005	01
		Item T20.1000 Total:		1,000.00		
068	T20.1106	6 INCH TEMPORARY WATERBORNE PAINT PAVEMENT MARKINGS WHITE PROJECT WIDE	LF			
		ADDITIONAL FOR JOINTS		75,000.00	0005	01
		FROM ITEM T20.2006		60,000.00	0005	01
		Item T20.1106 Total:		135,000.00		

Distribution of Quantities

Project Name - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 Estimate Name - Addendum No. 1 - I-95 Resurfacing (Elmwood Avenue to Eddy Street)
 R.I. Contract No. - 2016-CH-058
 FAP Nos: STP-RESF (333)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
069	T20.1112	12 INCH TEMPORARY WATERBORNE PAINT PAVEMENT MARKINGS WHITE PROJECT WIDE	LF			
		ADDITIONAL FOR JOINTS		13,600.00	0005	01
		FROM ITEM T20.2012		8,600.00	0005	01
Item T20.1112 Total:				22,200.00		
070	T20.1206	6 INCH TEMPORARY WATERBORNE PAINT PAVEMENT MARKINGS YELLOW PROJECT WIDE	LF			
		ADDITIONAL FOR JOINTS		41,000.00	0005	01
		FROM ITEM T20.2016		31,000.00	0005	01
Item T20.1206 Total:				72,000.00		
071	T20.2006	6 INCH EPOXY RESIN PAVEMENT MARKINGS WHITE I-95 NORTHBOUND	LF			
		113+50-221+30		20,500.00	0005	01
		221+30-227+00		900.00	0005	01
		AS DIRECTED BY THE ENGINEER		3,275.00	0005	01
		I-195 OFF RAMP		800.00	0005	01
		RAMP BR-5		1,600.00	0005	01
		RAMP BR-6		400.00	0005	01
		RAMP BR-7		1,600.00	0005	01
		RAMP C-B		525.00	0005	01
		THURBERS AVENUE		400.00	0005	01
		I-95 SOUTHBOUND				
		1225+00-119+80		21,900.00	0005	01
		221+30-227+00		900.00	0005	01
		AS DIRECTED BY THE ENGINEER		3,400.00	0005	01
		RAMP AR-5		2,200.00	0005	01
		RAMP AR-6		1,000.00	0005	01
		ROGER WILLIAMS AVE RAMP		600.00	0005	01