



State of Rhode Island  
Department of Administration / Division of Purchases  
One Capitol Hill, Providence, Rhode Island 02908-5855  
Tel: (401) 574-8100 Fax: (401) 574-8387

**Solicitation Information**  
**August 10<sup>th</sup>, 2017**

**ADDENDUM # 2**

**RFQ# 7554564**

**TITLE: Electrical Upgrades at Fort Adams State Park**

**Submission Deadline is:**

**Wednesday August 23<sup>rd</sup>, 2017 at 11:00 am (EST)**

**Note to vendors:**

**Question period has been extended to:**

**Monday August 14<sup>th</sup>, 2017 at 5:00 pm (EST)**

**Attached includes:**

- **Updated project plans and specifications**

**Max Righter**

**Buyer II**

*Interested parties should monitor this website, on a regular basis, for any additional information that may be posted*

ELECTRICAL UPGRADES AT FORT ADAMS STATE PARK  
SOLICITATION NUMBER 7554564

A1. DRAWING E-002

DETAIL 5; NEW POWER PEDESTAL DETAIL

REVISE DESCRIPTION “HYPOWER POWERPORT WITH (2) 100 AMP 3 POLE CIRCUIT BREAKERS AND (2) 100 AMP PIH & SLEEVE OUTLETS EACH HP-5W” TO READ; “HYPOWER POWERPORT WITH (2) 50 AMP AND (1) 100 AMP 3 POLE CIRCUIT BREAKERS AND (2) 50 AMP AND (1) 100 AMP PIN AND SLEEVE OUTLETS EACH 4 POLE-5 WIRE – WEATHERPROOF”

DETAIL BL; BOLLARD DETAIL – TYPICAL

NOTE THE FOLLOWING:

BOLLARD SHALL BE 5’ – 0” ABOVE GRADE AND MINIMUM 4’ – 0” BELOW GRADE. FOOTING SHALL BE 12” DIAMETER.

DETAIL TP; UTILITY COMPANY TRANSFORMER PAD DETAIL (TYPICAL)

REVISE CONCRETE TRANSFORMER PAD DIMENSION FROM 10” TO 12”

A2 DRAWING ES-105

DETAIL 1 ELECTRICAL SITE PLAN – MUSEUM OF YACHTING

REVISE “NGRID TRANSFORMER 3-2 TO BE DISCONNECTED AND REMOVED” TO READ; “NGRID TRANSFORMER 3-2 TO REMAIN”

IDENTIFY UNDERGROUND ELECTRICAL FROM EXISTING UTILITY COMPANY MANHOLE TO TRANSFORMER TO BE (2) – 4” PVC CONDUITS PRIMARY CABLE TO BE PROVIDE AND INSTALLED BY UTILITY.

IDENTIFY UNDERGROUND ELECTRICAL FROM TRANSFORMER TO PANELBOARD IN MUSEUM OF YACHTING TO REFERENCE SE/E-002 FOR UNDERGROUND AND TO BE (2) 4” RS – 4 – 350 MCM TO NEW PANELBOARD “MDP”.

MUSEUM OF YACHTING DISTRIBUTION – SINGLE LINE

REVISE, “PRIMARY SERVICE WIRING BY NGRID” TO READ “PRIMARY SERVICE WIRING BY NGRID, (2) – 4” PVC UNDERGROUND CONDUITS BY CONTRACTOR.

REVISE, “NEW SERVICE ENTRANCE WIRING 2 SETS OF 4 – 350 KCMIL” TO READ, “NEW SERVICE ENTRANCE WIRING 2 SETS OF 4 – 350 KCMIL IN 4” C”