



STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS

Department of Administration  
DIVISION OF PURCHASES  
One Capitol Hill  
Providence, RI 02908-5855

Tel: (401) 574-8100  
Fax: (401) 574-8387  
Website: [www.purchasing.ri.gov](http://www.purchasing.ri.gov)

**November 27, 2018**  
**ADDENDUM NUMBER TWO**  
**RFQ # 7597618**

**TITLE: EMERGENCY GENERATORS AT STEDMAN CENTER AND HARRINGTON HALL**

**Closing Date and Time: 12/7/18 AT 10:00AM**

**Per the issuance of this ADDENDUM #2 (1 page) the following is noted:**

This addendum posts clarification/notes from pre-bid conference.

**Stedman Building**

1. Drawing ST-E-2
  - a. Proposed one line, indicate new Panel A to be wired from existing MSB1/MSB2. Provide 1 1/2" C with 4 #3, 1 # 8 Gnd from MSB1/MSB2. Provide new 3 pole 100 ampere circuit breaker in MSB1/MSB2 (existing Siemens). Panel shall be located opposite the main panels. Panelboard A shall have 100 ampere main lugs with 16 – 1P- 20 amp breakers and 2 – 1P 30 amp circuit breakers.
  - b. Add note 4 to read, "Raceways between the generator and storm switch shall be route via the driveway area. Provide heavy duty highway rated handhole if required.

**Harrington Hall**

1. Drawing 00-E-3
  - a. B Elevation New Padmount Switch 4A, "revise to read, "B Elevation New Padmount Switch 4." All reference to 4A shall be revised to 4.
  - b. C Elevation New Padmount Switch 4B, "revise to read, "C Elevation New Padmount Switch 5." All reference to 4B shall be revised to 5.
  - c. Remove all kirk key switches on both padmount switches.

**Harrington and Stedman**

**General Requirements:**

The shutdown for both locations needs to be off normal hours.

Provide a generator capable of running the building or panels that will support the necessary equipment life safety and heat for the duration of the outage.