



STATE OF RHODE ISLAND AND PROVIDENCE PLANTATIONS

Department of Administration
DIVISION OF PURCHASES
One Capitol Hill
Providence, RI 02908-5855

Tel: (401) 574-8100
Fax: (401) 574-8387
Website: www.purchasing.ri.gov

January 8, 2019

ADDENDUM NUMBER FIVE

RFQ # 7597626

**TITLE: MASONRY RESTORATION & NEW ROOF ASSEMBLY FOR ARMORY OF MOUNTED
COMMANDS SHED BLDG**

Closing Date and Time: 1/23/19 AT 11:00am (NOTE CHANGE)

Per the issuance of this ADDENDUM #5 (1 page) the following is noted:

Bid Closing Date and Time is changed from:

1/29/19 at 11am

To 1/23/19 at 11am

This addendum posts additional information regarding the antennas on the roof.

This addendum posts additional work that must be included in your base bid.

This addendum changes the bid closing date and time.

Antenna information:

Pre-construction:

The agency will remove the two small antennas on the roof.

The agency will remove abandoned antenna/IT wires associated with the three antennas.

The agency will relocate the large antennas existing wires and emergency radios to the

TOC.

Post construction:

If needed, the agency will reinstall and connect the small antennas.

The agency will reconnect the large antenna connections.

Additional work to be included in base bid:

Contractor shall include in the Base Bid, the costs associated with providing new 2"-diameter exterior galvanized-metal conduit, powder-coated "Brick Red" color. Conduit shall be run exposed from roof surface (threaded end capped); up the face of the PVC membrane-covered parapet wall, secured with 1" wide 60-mil PVC wide heat-welded straps at 36" on-center; over parapet wall cap and down the face of the North side of the building, secured into brick mortar joints with galvanized-metal straps (powder-coated "Brick Red" color) at 60" on-center. Conduit shall be run vertically at the 90-degree corner of the nearest exterior brick-masonry column. Conduit shall penetrate the solid brick-masonry/ plaster-lathe exterior wall (assume 24" thick) at the 1st floor level of the Tactical Operations Center (TOC). This room is located above the entrance door to the Basement level at the North side of the building. Provide all backer rod, sealant, LB conduit fitting, interior surface (wall)-mounted electrical box, etc. for a complete and weathertight installation. Assume 75 linear feet total conduit run with twelve (12) bends. Exact locations shall be coordinated with the Owner.