DEMOLITION NOTES:

1. THE EXISTING CONDITIONS INFORMATION SHOWN &/or INDICATED ON THE DRAWINGS WAS OBTAINED FROM LIMITED EXISTING DRAWINGS PREPARED BY OTHERS; FIELD REVIEW; FIELD MEASUREMENT; &/or OTHER AVAILABLE DOCUMENTATION &/or OBSERVATION BY OTHERS. NOT ALL EXISTING CONDITIONS &/or ACTUAL CONSTRUCTION MAY BE INDICATED &/or KNOWN.
2. CONTRACTOR TO VERIFY ALL EXISTING, CONDITIONS, CONNECTIONS, LOCATIONS, SIZES, ETC. IN THE FIELD AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE STARTING DEMOLITION WORK.
3. CONTRACTOR TO COORDINATE EXTENTS OF ALL DEMOLITION WORK WITH ALL NEW WORK AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE STARTING DEMOLITION WORK.
4. FULL EXTENT OF BUILDING MATERIALS IS UNKNOWN. EXISTING BUILDING CONSTRUCTION MAY CONTAIN MATERIALS THAT REQUIRE ABATEMENT. IF POTENTIAL MATERIALS ARE DISCOVERED, CONTRACTOR TO NOTIFY OWNER & ARCHITECT BEFORE PROCEEDING WITH WORK.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETE SECURITY OF THE AREA UNDER CONSTRUCTION & DEMOLITION.
6. REFER TO MECHANICAL, ELECTRICAL, FIRE PROTECTION & PLUMBING DRAWINGS FOR SPECIFIC DEMOLITION NOTES REGARDING THESE DISCIPLINES. ALL MECHANICAL, ELECTRICAL, FIRE PROTECTION & PLUMBING ITEMS REMOVED SHALL BE CAPPED AND APPROPRIATELY IDENTIFIED.
7. CONTRACTOR TO PROVIDE ALL OSHA and/or BUILDING CODE REQUIRED SAFETY PROTECTION TO PROTECT WORKERS FROM FALLS, CRUSHING, ELECTROCUTION, IMPACT FROM ABOVE, ETC.
8. PATCH/REPAIR/REFINISH ALL SURFACES EXPOSED BY DEMOLITION WORK.
9. CONTRACTOR SHALL DISPOSE OF DEMOLITION MATERIAL(S) IN A SAFE, LEGAL MANNER.

1 / SKA-01

EXISTING HAZ-MAT TRAILER DEMO

Scale: 1/4" = 1'-0"

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RI ARMY NATIONAL GUARD ADDITION TO BUILDING P-6

520 READ SCHOOL HOUSE RD COVENTRY, RI

Contents

EXISTING HAZ-MAT TRAILER DEMOLITION

Project No. 6366	Drawing No. **SKA-01**
Checked by RJJ	
Issued 19-Feb-19	Sheet of