RHODE ISLAND
ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

50 Holden Street · Providence, Rhode Island 02908
(401) 272-1730 · www.rgb.net

Architecture · Project Management · Interior Design

RGB architects

THE ROBINSON GREEN BERETTA CORPORATION

ARCHITECTURE, PROJECT MANAGEMENT & INTERIOR DESIGN

CONSULTANTS

BUILDING ENGINEERING RESOURCES, INC.

MECHANICAL, ELECTRICAL & PLUMBING

LIST OF DRAWINGS

SHEET #	SHEET NAME
A000	COVER SHEET
ARCHITECTURAL	
G001	ABBREVIATION & SYMBOLS
G002	MATERIAL LIST
A010	CODE REVIEW
A030	CONSTRUCTION TYPES
D100	BUILDING 1 DEMOLITION PLAN
D101	BUILDING 3 DEMOLITION PLAN
A100	BUILDING 1 FLOOR PLAN
A101	BUILDING 3 FLOOR PLAN
A600	REFLECTED CEILING PLAN - BUILDING 1
A601	REFLECTED CEILING PLAN - BUILDING 3
A700	INTERIOR ELEVATIONS - BUILDING 1
A701	INTERIOR ELEVATIONS - BUILDING 3
A910	DOOR & FRAME SCHEDULE
MECHANICAL	
M000	MECHANICAL LEGENDS, ABBREVIATIONS AND NOTES
M001	MECHANICAL SCHEDULES
MD100	BUILDING 1 - DUCTWORK DEMOLITION PLAN
MD101	BUILDING 1 - PIPING DEMOLITION PLAN
MD200	BUILDING 3 - DUCTWORK DEMOLITION PLAN
MD201	BUILDING 3 - PIPING DEMOLITION FLOOR PLAN
M100	BUILDING 1 - DUCTWORK RENOVATION FLOOR PLAN
M101	BUILDING 1 - PIPING RENOVATION PLAN
M200	BUILDING 3 - DUCTWORK RENOVATION FLOOR PLAN
M201	BUILDING 3 - PIPING RENOVATION FLOOR PLAN
M300	MECHANICAL DETAILS
ELECTRICAL	
E001	ELECTRICAL - LEGEND, NOTES & SCHEDULES
ED101	BUILDING 1 ELECTRICAL - DEMOLITION PLAN
ED102	BUILDING 3 ELECTRICAL - DEMOLITION PLAN
E101	BUILDING 1 ELECTRICAL - LIGHTING PLAN
E102	BUILDING 1 ELECTRICAL - POWER PLAN
E103	BUILDING 3 ELECTRICAL - LIGHTING PLAN
E104	BUILDING 3 ELECTRICAL - POWER PLAN
FA100	BUILDING 1 FIRE ALARM PLAN
FA101	BUILDING 3 FIRE ALARM PLAN
PLUMBING	
P001	LEGEND, NOTES, DETAILS & SCHEDULES - PLUMBING
P100	BUILDING 1 DEMOLITION PLAN SANITARY, WASTE & VENT- PLUMBING
P101	BUILDING 1 DEMOLITION PLAN DOMESTIC WATER - PLUMBING
P102	BUILDING 3 DEMOLITION PLAN SANITARY, WASTE & VENT - PLUMBING
P103	BUILDING 3 DEMOLITION PLAN DOMESTIC WATER - PLUMBING
P104	BUILDING 1 NEW FLOOR PLAN SANITARY, WASTE & VENT - PLUMBING
P105	BUILDING 1 NEW FLOOR PLAN DOMESTIC WATER - PLUMBING
P106	BUILDING 3 NEW FLOOR PLAN SANITARY, WASTE & VENT - PLUMBING
P107	BUILDING 3 NEW FLOOR PLAN DOMESTIC WATER - PLUMBING
FIRE PROTECTION	
FP001	LEGEND, NOTES & DETAILS - FIRE PROTECTION
FP100	BUILDING 1 DEMOLITION PLAN - FIRE PROTECTION
FP102	BUILDING 1 NEW FLOOR PLAN - FIRE PROTECTION

RIARNG- WARWICK LATRINE MODERNIZATION - 6356

DANIEL L. DESNOYERS No. 2152 REGISTERED ARCHITECT

4/19/18

STATUS: CONSTRUCTION DOCUMENTS

DATE: MARCH 20 2018

ABBREVIATIONS

AFF	ABOVE FINISHED FLOOR
AF	ABOVE FLOOR
ACP	ACCESS PANEL
ACC	ACCESSORY, ACCESSORIES
ACOUS	ACOUSTICAL
ACT	ACOUSTIC CEILING TILE
ADH	ADHESIVE
ADJ	ADJUSTABLE
AGG	AGGREGATE (S)
A/C	AIR CONDITIONING
AVB	AIR/VAPOR BARRIER
AC	ALTERNATING CURRENT
ALT	ALTERNATE
ALUM	ALUMINUM
AT	ALUMINUM THRESHOLD
ANC	ANCHOR (S) ANCHORAGE (S)
AB	ANCHOR BOLTS
∟∡	ANGLE
ANOD	ANODIZED
ANT	ANTENNA (E)
APP	APPROVED, APPROVAL
APPROX	APPROXIMATE
AD	AREA DRAIN
@	AT
ATT	ATTACH, ATTACHMENT
ALD	AUTOMATIC LOUVER DAMPER
AVE	AVENUE
AVG	AVERAGE
BTB	BACK TO BACK
BM	BEAM
BMK	BENCH MARK
BG	BEARING
BPL	BEARING PLATE
BIT	BITUMINOUS
BC	BOTTOM OF CURB
BLK	BLOCK
BLKG	BLOCKING
BD	BOARD
BF	BOTTOM OF FOOTING
BO	BOTTOM OF
BOC	BOTTOM OF CURB
BS	BOTH SIDES
BW	BOTH WAYS
BOT	BOTTOM
BKT	BRACKET
BK	BRICK
BRG	BRIDGING, BRIDGE (D)
BTU	BRITISH THERMAL UNIT
BLDG	BUILDING
BUR	BUILT-UP ROOFING
CK	CHALK
CBT, CAB	CABINET
CPT	CARPET
CI	CAST IRON
CB	CATCH BASIN
CLG	CEILING
CTR	CENTER
CL, ℄	CENTERLINE
CTC	CENTER TO CENTER
C	CENTIGRADE (CELSIUS)
CT	CERAMIC TILE
CLF	CHAIN-LINK FENCE
CB	CHALKBOARD
CH, [	CHANNEL
CM	CENTIMETER
CV	CHECK VALVE
CHWR	CHILLED WATER RETURN
CHWS	CHILLED WATER SUPPLY
CKT	CIRCUIT
CO	CLEANOUT
CLR	CLEAR, CLEARANCES
CLS	CLOSURE
CW	COLD WATER
C,COL	COLUMN
COMP	COMPRESS (ED),(ION),(IBLE)
CONC	CONCRETE (PORTLAND CEMENT)
CMU	CONCRETE MASONRY UNITS
COND	CONDUIT
CX	CONNECTION
CONT	CONTINUOUS
CLL	CONTRACT LIMIT LINE
CONTR	CONTRACTOR
CJ	CONTROL JOINT
CFL	COUNTERFLASHING (S)
CS	COUNTERSINK, COUNTERSUNK
CU	CUBIC
CU	COPPER
CFM	CUBIC FEET PER MINUTE
CFS	CUBIC FEET PER SECOND
CF	CUBIC FEET
CU IN	CUBIC INCH
CY	CUBIC YARD
CYL	CYLINDER, CYLINDRICAL
DPR	DAMPER
DP	DAMPPROOF (ED),(ING)
DL	DEAD LOAD
DB	DECIBEL
DEG	DEGREE
DEM	DEMOLISH, DEMOLITION
DEP	DEPRESSED
DET	DETAIL
DIA or Φ	DIAMETER
DIAG	DIAGONAL
DIM	DIMENSION
DC	DIRECT CURRENT
DCX	DISCONNECT (ION)
DPN	DISPENSER
DPL	DISPOSAL, DISPOSABLE
DR	DOOR
DBL	DOUBLE
DH	DOUBLE-HUNG
DTA	DOVETAIL ANCHOR
DTS	DOVETAIL ANCHOR SLOT
DN	DOWN
DS	DOWNSPOUT
D	DRAIN, DRAINAGE LINE
DI	DRAIN INLET
DT	DRAIN TILE
DWG,DRWG	DRAWING (S)
DF	DRINKING FOUNTAIN
DMH	DROP MANHOLE
EIFS	EXT. INSUL FINISH SYSTEM
EW	EACH WAY
EA	EACH
EFF	EFFICIENCY
E, ELECT.	ELECTRIC, ELECTRICAL
EP	ELECTRIC PANEL
EWC	ELECTRIC WATER COOLER
EL, ELEV	ELEVATION
ENC	ENCLOSE, ENCLOSURE
EQ, =	EQUAL (TO)
EQP, EQUIP	EQUIPMENT
EXH	EXHAUST
ED	EXHAUST DUCT
EF	EXHAUST FAN
EH	EXHAUST HOOD
EXIST.	EXISTING
EXP	EXPANSION
EXP	EXPOSED
EB	EXPANSION BOLT
EJ	EXPANSION JOINT
ET	EXTENDED, EXTENSION
EPS	EXTRUDED POLYSTYRENE
EXT	EXTERIOR
FAB	FABRICATE
FO	FACE OF
FS, FOS	FACE OF STUD
FAS	FASTEN, FASTENER
FPM	FEET PER MINUTE
FPS	FEET PER SECOND
FNDR	FEMININE NAPKIN DISPENSER UNIT
FNDP	FEMININE NAPKIN DISPOSAL UNIT
FF	FINISH FLOOR
FBD	FIBERBOARD
FGL	FIBERGLASS
FIL	FILLER (S)
FIN	FINISH
FFE	FINISH FLOOR ELEVATION
FFL	FINISH FLOOR LINE
FTR	FINNED TUBE RADIATION
FA	FIRE ALARM STATION
FDC	FIRE DEPARTMENT CONNECTION
FE	FIRE EXTINGUISHER
FEC, FXC	FIRE EXTINGUISHER CABINET
FHC	FIRE HOSE CABINET
FHR	FIRE HOSE RACK
FH	FIRE HYDRANT
FPN	FIRE MAIN
FP	FIREPROOF (ING)
FR	FIRE RESISTANT
FRC	FIRE-RESISTANT COATING
FRT	FIRE-RETARDANT TREATMENT
FSP	FIRE STANDPIPE
FXD	FIXED
FXT	FIXTURE
FLG	FLASHING
FHCS	FLAT HEAD COUNTERSUNK SCREW
FHWS	FLAT HEAD WOOD SCREW
FLX	FLEXIBLE
FLR	FLOOR, FLOORING
FD	FLOOR DRAIN
FGR	FLOOR GRILLE (REGISTER)
FLU	FLUORESCENT
FL	FLOW LINE
FT	FOOT, FEET
FC	FOOTCANDLES
FTG	FOOTING
FWK	FORMWORK
FND, FDW	FOUNDATION (WALL)
FR	FRAME (D),(ING)
FBO	FURNISHED BY OTHERS
F & I	FURNISH & INSTALL
FURR	FURRING
FUT	FUTURE
FAI	FRESH AIR INTAKE
FRP	FIBER REINFORCED PLASTIC
FSL	FUSIBLE LINK
GAL	GALLON (S)
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
GPS	GALLONS PER SECOND
GALV	GALVANIZED
GI	GALVANIZED IRON
GST	GALVANIZED STEEL
G	GAS
GKT	GASKET (ED)
GAV	GATE VALVE
GA	GAUGE
GLB	GLASS BLOCK
GMU	GLAZED MASONRY UNITS
GB	GRAB BARS
GRD	GRADE, GRADING
GRT	GRANITE
GVL	GRAVEL
GR	GRILLE
GD	GROUND (ED)
GT	GROUT (ED)
GYP. BD.	GYPSUM WALLBOARD
GWB	GYPSUM WALLBOARD
GYL	GYPSUM LATH
GFRC	GLASS FIBER REINF. CONC.
GPL	GYPSUM PLASTER
HH	HAND HOLD
HA	HANGER
HBD	HARDBOARD
HC	HANDICAP(PED)
HDN	HARDENER (ED)
HDW	HARDWARE
HWD	HARDWOOD
HD	HEAD
HDR	HEADER
HDE	HEAT DETECTOR
HTG	HEATING
HAC	HEATING & AIR CONDITIONING
H & V	HEATING & VENTILATING
HVAC	HEATING, VENTILATING & AIR CONDITIONING
HVC	HEATING, VENTILATING, COOLING
Hz	HERTZ (CYCLES PER SECOND)
HPL	HIGH PRESSURE LAMINATE
HV	HIGH VOLTAGE
HWY	HIGHWAY
HO	HOLD OPEN
HCWD	HOLLOW CORE WOOD
HM	HOLLOW METAL
HMD	HOLLOW METAL DOOR
HMF	HOLLOW METAL FRAME
HK	HOOK (S)
HR	HOUR
HOR, HORZ.	HORIZONTAL
HP	HORSEPOWER
HB	HOSE BIBB
HW	HOT WATER
HWR	HOT WATER RETURN
HWC	HOT WATER, CIRCULATOR
HWF	HOT WATER FAUCET
HWH	HOT WATER HEATING
HWT	HOT WATER TANK
HYD	HYDRANT
IN	INCH
INCL	INCLUDING (ED),(SIVE)
INFO	INFORMATION
ID	INSIDE DIAMETER
INSL	INSULATE (D),(ATION)
IMC	INSULATED METAL CLAD
INT	INTERIOR, INTERNAL
INV	INVERT
IE	INVERT ELEVATION
IDM	ISOLATE DISC. METALS
JAN	JANITOR
JT	JOINT
JF	JOINT FILLER
JS	JOINT SEALER
J	JOIST
JCT	JUNCTION
JB	JUNCTION BOX
KVA	KILOVOLT-AMPERE
KW	KILOWATT
K	KIP
KD	KNOCK DOWN
LAB	LABORATORY
LAD	LADDER
LAM	LAMINATE (D)
LAT	LATERAL
LAV	LAVATORY
LB	LAG BOLT
LBL	LABEL
LBS, #	POUND'S
LCC	LEAD COATED COPPER
LDR	LEADER
LH	LEFT-HAND
LWOD	LESS WIDTH OF DOOR
LIN	LINEN
LP	LIGHT PROOF
LS	LIMESTONE
LTL	LINTEL
LL	LIVE LOAD
LW	LIGHT WEIGHT
LP	LOW PRESSURE
LOC	LOCATION
LKR	LOCKER
LG	LONG, LENGTH
LONG	LONGITUDINAL
L or LH	LONG SPAN STEEL JOIST
LVR	LOUVER
LV	LOW VOLTAGE
MB	MACHINE BOLT
MH	MANHOLE
MFD,MFR'D	MANUFACTURED
MFR	MANUFACTURER
MFG	MANUFACTURING
MBL	MARBLE
MK	MARK
MAS	MASONRY
MCJ	MASONRY CONTROL JOINT
MJ	MASONRY JOINT
MO	MASONRY OPENING
MTL	MATERIAL (S)
MAX	MAXIMUM
MC	MEDICINE CABINETS
MED	MEDIUM
MDF	MEDIUM DENSITY FIBERBOARD
MBR	MEMBER
MMB,MEMB	MEMBRANE
MTL	METAL
METC	METAL CLAD
ME	METAL EDGE
MRE	METAL ROOF DECK(ING)
M	METER (S)
MEZZ	MEZZANINE
MIC	MICROPHONE
MM	MILLIMETER
MWK	MILLWORK
MIN	MINIMUM
MIR	MIRROR
MIS	MISCELLANEOUS
MXV	MIXING VALVE
MOD	MODULAR
MLD	MOLDING
MDO	MEDIUM DENSITY OVERLAY
MT	MOUNT (ED), (ING)
MHT	MOUNTING HEIGHT
MUL	MULLION
NL	NAILABLE
NAT	NATURAL (FINISH)
NRC	NOISE-REDUCTION CO-EFFICIENT
NOM	NOMINAL
NC	NON-CORROSIVE
NIC	NOT IN THIS CONTRACT
NTS	NOT TO SCALE
NO,#	NUMBER
OC	ON-CENTER
K,L,H	OPEN-WEB STEEL JOIST
OPG, OPNG	OPENING
OPR	OPERATOR
OPP	OPPOSITE
O.H.,OPH	OPPOSITE HAND
OHS	OPPOSITE HAND SIMILAR
OSB	ORIENTED STRAND BOARD
OAE	OR APPROVED EQUAL
OZ	OUNCE (S)
OD	OUTSIDE DIAMETER
OA	OVERALL
OH	OVERHEAD
OHB	OVERHEAD BRACED
OHD	OVERHEAD DOOR
OF	OWNER FURNISHED
OFI	OWNER FURNISHED & INSTALLED
OFCI	OWNER FURNISH-CONTRACTOR INSTALL
OX	OXYGEN
PT	"P" TRAP
PNT, PTD	PAINT, PAINTED
PR	PAIR
PNL	PANEL
PAR, //	PARALLEL
PBD	PARTICLE BOARD
PTN	PARTITION
PCT or %	PERCENT (AGE)
PF	PERFORATED (D)
PERIM	PERIMETER
PERP, ⊥	PERPENDICULAR
P	PHASE
PLAS	PLASTER
PL	PLATE
PLUMB	PLUMBING
PLYWD	PLYWOOD
PNU	PNEUMATIC
POL	POLISH (ED)
PE	PORCELAIN ENAMEL
PCF	POUNDS PER CUBIC FOOT
PLF	POUNDS PER LINEAR FOOT
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PIC	POURED INPLACE CONCRETE
PDF	POWER DRIVEN FASTENER (ING)
PCC	PRECAST CONCRETE
PREFAB	PREFABRICATED
PRN	PREFINISH (ED)
PRF	PREFORMED
PM	PREMOLDED
PMTL	PRESSED METAL
PVT	PRIVATE
PROJ	PROJECT
PL, ℙ	PROPERTY LINE
PUB	PUBLIC
PA	PUBLIC ADDRESS SYSTEM
PB	PULL BOX
PU	PULL, PULL CHAIN
PP	PUMP
PD	PUMP DISCHARGE
PIV	POST INDICATOR VALUE
PC	PHYSICALLY CHALLENGED
PVC	POLY VINYL CHLORIDE
QT	QUARRY TILE
RW	RACEWAY
RAD	RADIATOR, RADIATION
RA, R	RADIUS
R	RISER
RL	RAIL, RAILING
RR	RAILROAD
RECP	RECEPTACLE
REF	REFERENCE
RFL	REFLECTIVE
RE	REFER TO
REG	REGISTER
RFC	REINFORCE (D) (ING)
RC	REINFORCED CONCRETE
REQ,REQ'D	REQUIRE(ED), REQUIREMENTS
R & S	REMOVE AND SALVAGE
R & D	REMOVE AND DISPOSE
R & R	REMOVE AND REINSTALL
RESIL	RESILIENT
RTN	RETAIN (ED) (ER) (ING)
RVS, REV	REVERSE (SIDE)
REV	REVISE (ED), REVISION
RPM	REVOLUTIONS PER MINUTE
RPS	REVOLUTIONS PER SECOND
RH	RIGHT HAND
ROW	RIGHT-OF-WAY
RD	ROOF DRAIN
RFG	ROOFING
RM	ROOM
RO	ROUGH OPENING
RU	RUBBER
RP	RUSTPROOF (ING)
SDL	SADDLE
SAN	SANITARY (SEWER)
SCN	SCREEN
SLT	SEALANT
SLR	SEALER
STG	SEATING
SEC	SECTION
SEL	SELECT (OR)
SPT	SEPTIC TANK
SVC	SERVICE
SSK	SERVICE SINK
STH	SHEATHING
SHT	SHEET
SH	SHELF, SHELVING
S & R	SHELF & ROD
SHR	SHOWER RECEPTOR
SIM	SIMILAR (TO)
SH	SINGLE HUNG
SK	SINK
SKL	SKYLIGHT
SL	SLEEVE
SDE, SD	SMOKE DETECTOR
SMV	SMOKE-VENTING HATCH
SCWD	SOLID CORE WOOD
SSM	SOLID SURFACE MATERIAL
SP	SOUNDPROOF
SPK	SPEAKER
SPEC	SPECIFICATIONS
SPF	SPECIFIED
SPR	SPRINKLER
SQ, ⧈	SQUARE
SF	SQUARE FOOT (FEET)
SY	SQUARE YARD
STAG	STAGGER
SS	STAINLESS STEEL
STD	STANDARD
ST	STEEL
STIFF	STIFFENER
STN	STONE
STO	STORAGE
SD	STORM DRAIN
ST	STREET
S	STRUCTURAL
SIP	STRUCTURAL INSULATED PANEL
SUP	SUPPORT
SUSP	SUSPENDED
SAT	SUSPENDED ACOUSTIC TILE
SUSP CEIL	SUSPENDED CEILING
SYM	SYMMETRY (ICAL)
SYS	SYSTEM
TB	TACKBOARD
TEL	TELEPHONE
TV	TELEVISION
TMP, TEMP	TEMPER (ED)
TCV	TEMPERATURE CONTROL VALVE
TP	TEST PIT
TZ	TERRAZZO
THM	THERMOMETER
THS	THERMOSTAT
TH	THICK, THICKNESS
THR	THRESHOLD
TCL	TIME CLOCK
TOL	TOLERANCE
TG, T & G	TONGUE AND GROOVE
TO	TOP OF
TOC	TOP OF CONCRETE / CURB
TOS, TS	TOP OF STEEL
TOW	TOP OF WALL
TRANS	TRANSFORMER
TR	TRANSOM
TJI	TRUSS JOIST 'I' SECTION
TP	TURNING POINT
TYP	TYPICAL
TOM	TOP OF MASONRY
UHF	ULTRAHIGH FREQUENCY
UF	UNDERFLOOR (DUCT)
UG	UNDERGROUND
UL	UNDERWRITERS LABORATORY
UNF	UNFINISHED
UNO	UNLESS NOTED OTHERWISE
UH	UNIT HEATER
UK	UNIT KITCHEN
UV	UNIT VENTILATOR
UAS	UPWARD ACTING SECTIONAL
VJ	V-JOINTED
VA	VACUUM
VAB	VACUUM BREAKER
VB	VAPOR BARRIER
VP	VAPORPROOF
VNR	VENEER
VE	VENT
VR, VTR	VENT THROUGH ROOF
VTR	VENTILATOR
VER, VERT	VERTICAL
VHF	VERY HIGH FREQUENCY
VLF	VERY LOW FREQUENCY
VI	VIBRATION ISOLATOR
VNL	VINYL
VCT	VINYL COMPOSITION TILE
VB	VINYL BASE
VF	VINYL FABRIC
VQT	VINYL QUARTZ TILE
VS	VINYL SHEET
VT	VINYL TILE
VIT	VITREOUS
VC	VITRIFIED CLAY
V	VOLT (AGE)
VWC	VINYL WALLCOVERING
WN	WAINSCOT
WH	WALL-HUNG
WHY	WALL HYDRANT
WTW	WALL TO WALL
W	WASTE
WR	WASTE RECEPTACLES
WC	WATER CLOSET
WHA	WATER HAMMER ARRESTOR
WP	WATERPROOF (ED), (ING)
WPT (WP)	WORK (ING) POINT
WST	WEATHERSTRIPPING
WE	WEEPHOLE
WWF	WELDED WIRE FABRIC
WID	WIDE, WIDTH
WF,WF	WIDE-FLANGE BEAM
WG	WIRE GLASS
WM	WIRE MESH
W, W/	WITH
W/IN	WITHIN
WO, W/O	WITHOUT
WD	WOOD
WB	WOOD BASE
WBM	WOOD BEAM
WBO	WORK BY OTHERS
WBOR	WORK BY OWNER
WBT	WORK BY TENANT
WK	WORK
WKRM	WORKROOM
WI	WROUGHT IRON
XR	X-RAY
Y	WYE FITTING
Z	ZONE
ZC	ZINC COATED
ZS	ZEE STUD

SYMBOLS

TITLE MARK

DETAIL MARK

SECTION MARK

INTERIOR ELEVATION

EXTERIOR ELEVATION

DOOR TAG

DOOR # = FIRST 3 NUMBERS DENOTE ROOM WHERE DOOR IS LOCATED
DECIMAL # INDICATES DOOR IN ROOM

WINDOW TAG

INDICATES WINDOW TYPE: IF LETTER, THEN INTERIOR IF NUMBER, THEN EXTERIOR

WORK NOTES

XXX — NOTES WITHOUT ARROW INDICATE ENTIRE SPACE/AREA

XXX — NOTES WITH ARROWS INDICATE SPECIFIC AREAS &/OR ITEMS

— MATERIAL NOTE

RE: G002 FOR LIST OF MATERIALS

PHYSICALLY CHALLENGED AND/OR HANDICAPPED ACCESSIBLE

PROJECT NORTH ARROWS

ROOM TAG

WALL CONSTRUCTION TAG

RE: DRAWING SHEET A030 FOR DESCRIPTION, DETAIL & MATERIAL

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB ARCHITECTS

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

ABBREVIATION & SYMBOLS

Project Number. 6356

Drawing No.

G001

Sheet of

Site Work

20 LAYER OF COMPACTED STONE/GRAVEL 6" U.N.O.
21 FINISH GRADE (Re: Civil Dwgs)
21A PAVING (CONCRETE OR ASPHALT) (Re: Civil Dwgs)
21B EARTH / LANDSCAPE / BEDDING (Re: Civil Dwgs)
22 not used
23 FENCING
23A GALV CHAIN LINK FENCING SYSTEM
23B ORNAMENTAL FENCING SYSTEM (Re: Civil Dwgs)
24 BELOW GRADE DRAINAGE SYSTEM
24A FOUNDATION 6" DIA HIGH DENSITY PERFORATED POLYETHELYENE PIPING W/ FILTER FABRIC WRAP
24B BELOW SLAB 6" DIA HIGH DENSITY PERFORATED POLYETHELYENE PIPING W/ FILTER FABRIC WRAP
24C FILTER FABRIC
24D SURFACE CLEANOUT IN 18" SQ X 6 CONC. PAD (Re: Civil Dwgs)
25 UNIT PAVERS FINISH SYSTEM

Concrete

30 CAST IN PLACE CONCRETE FOUNDATION SYSTEM (Re: Struct. Drwgs)
30A CONCRETE FOOTING (Re: Struct. Drwgs)
30B CONCRETE WALL (Re: Struct. Drwgs)
30C CONCRETE PIER (Re: Struct. Drwgs)
30D REINFORCING BAR (Re: Struct. Drwgs)
31 CAST IN PLACE CONCRETE SLAB (Re:Struct. Drwgs or as noted)
31A CONCRETE SLAB ON GRADE w/ W.W.F.
31B CONCRETE FLOOR SLAB W/ REINFORCING (Re: Struct. Drwgs)
31C CONCRETE MUD SLAB 3" MIN THICKNESS U.N.O.
31D CONCRETE SLAB ON METAL DECK (Re: Struct Drwgs)
32 CAST IN PLACE CONCRETE SIDEWALK w/ W.W.F (Re:Site Drwgs or as noted)
32A CONCRETE PAD w/ W.W.F. (Re:Site Drwgs or as noted)
33 PRECAST CONCRETE STRUCTURAL SYSTEM (Re: Struct. Drwgs)
33A PRECAST CONCRETE PLANK (Re: Struct. Drwgs)
34 CAST IN PLACE CONCRETE STRUCTURAL SYSTEM (Re: Struct. Drwgs)
34A CAST IN PLACE WALL (Re: Struct. Drwgs)
34B CAST IN PLACE BEAM (Re: Struct. Drwgs)
34C CAST IN PLACE COLUMN (Re: Struct. Drwgs)
35 ACCESSORIES
35A FIBROUS EXPANSION JOINT MATERIAL, 3/8" R-2 Min U.N.O.
36 GROUT, NON-SHRINK, NON METALLIC, 6000 PSI (Re: Struct. Drwgs)
37 ARCHITECTURAL PRECAST CONCRETE (Re: Struct. Drwgs)
38 GFRC GLASS FIBER REINFORCED CONCRETE SYSTEM
39 NOT USED

Masonry

40 BRICK
40A BRICK TYPE/ COLOR #1
40B BRICK TYPE/ COLOR #2
41 CMU
41A 4" CMU
41B 6" CMU
41C 8" CMU
41D 10" CMU
41E 12" CMU
41F 2" SOAP
42 GLAZED CMU
43 GROUND FACED CMU
44 STONE VENEER SYSTEM
44A SYNTHETIC
44B DOLOMITIC LIMESTONE
45 MASONRY ACCESSORIES
45A VENEER TIES @ 16" o.c.e.w. U.N.O.
45B VENEER TIES, SINGLE POST, @ 16" o.c.e.w. U.N.O.
45C HORIZONTAL JOINT REINFORCING @ 16" o.c. vert. U.N.O.
45D TIE / STRAP SECURED TO BEAM OR COLUMN @ 16" o.c. U.N.O.
45E ROD REINFORCING, 1/8" DIA Min. U.N.O.
45F ANCHOR STRAPS, 1/8" Min THICKNESS x 1" U.N.O.
45G DOVE TAIL ANCHOR SLOTS, CAST IN CONCRETE BACKUP @ 16" o.c. U.N.O.
45H BOND BREAKER, 30# FELT Min. U.N.O.
45J COMPRESSIBLE FILLER STRIP, 1/2" Min THICKNESS U.N.O.
45K EXTRUDED RUBBER CONTROL JOINT
45L WEEP HOLES, RECTANGULAR, PLASTIC, INSECT RESISTANT SPACING @ 24" O.C. @ BRICK AND 32" O.C. @ CMU U.N.O.
45M DRAINAGE NETTING SYSTEM VARY DEPTHS 6" TO 8" IN EACH 30" LENGTH
46 MASONRY LINTEL SYSTEM
46A CMU BOND BEAM w/ REINF. BARS Size as noted or Re: Struct. Drwgs
47 FLASHING SYSTEMS
47C COPPER LAMINATED FABRIC
47M SELF ADHERING MEMBRANE FLASHING
47S STAINLESS STEEL
48 GROUT CELL/VOIDS SOLID w/ 2500 PSI Min U.N.O. Re: Struct or as noted
48A PROVIDE W/ REINFORCING BAR #5 Min U.N.O. Re: Struct or as noted
49 not used

Metal

50 STRUCTURAL STEEL (Re: Structural Drwgs)
50B BEAM
50C COLUMN
50G GIRDER
50J JOIST
50T TRUSS
51 METAL DECK
51A ROOF DECK
51B FLOOR DECK (Re: Structural Drwgs)
51C CLOSURE ANGLE (POUR STOP) (Re: Structural Drwgs or as noted)
52 not used
53 MISCELLANEOUS SHAPES (size/shape as noted or Re: Struct. Drwgs)
53A ANGLE
53B BENT PLATE
53C CHANNEL
53D PLATE
53E TUBE
53F PIPE
53G SUPPORT ROD ALTHREAD ROD
53H ANCHOR BOLT
53J NELSON STUDS (size/shape as noted or Re: Struct. Drwgs)
54 LIGHT GAUGE FRAMING SYSTEM (Re: Struct or as noted)
54A STUD (Re: Struct or as noted)
54B JOIST / RAFTER (Re: Struct or as noted)
54C TRUSS SYSTEM (Re: Struct or as noted)
54D BRIDGING (Re: Struct or as noted)
55 MISCELLANEOUS METAL ITEMS, SIZE/SHAPE AS NOTED (shop painted)
55A METAL LADDER SHAPE & SIZE AS NOTED (GALV or shop primed/field painted)
55B GALV BOLLARD, 4000 PSI CONC. FILLED (GALV or shop primed/field painted)
55C METAL RAILING SYSTEM, SIZE AS NOTED
55E ROOF BLOCKING ATTACHMENT BOLTS THROUGH STEEL 3/8"x @ 12" O.C. w/ 2" WASHERS AT WOOD
55F ROOF BLOCKING ANCHOR BOLTS INTO CMU or MASONRY SYSTEM 3/8"x 6" (PLUS HOOK) @ 24" O.C. w/ 2" WASHERS (size as noted)
55H UNISTRUT SUPPORT SYSTEM
56 PREFABRICATED EXPANSION JOINT SYSTEM
56A FLOOR
56B WALL
56C CEILING
57 METAL STAIR SYSTEM, PAINTED, CONCRETE PAN FILLED
57A PIPE RAILING, HANDRAIL 1-1/4" I.D. U.N.O.
57B STRINGER 3/8" PLATE MIN U.N.O. (shape & size as noted)
57C STRINGER 'C' CHANNEL 12 X 20.7 MIN U.N.O. (shop primed/field painted)
57D METAL GUARD RAILING SYSTEM
57E NYLON WIRE PANEL SYSTEM 2"x2" MAX OPNG U.N.O.

Wood and Plastic

60 WOOD STUD &/or JOIST
60A 2 x 4 @ 16" o.c. U.N.O.
60B 2 x 6 @ 16" o.c. U.N.O.
60C 2 x 8 @ 16" o.c. U.N.O.
60D 2 x 10 @ 16" o.c. U.N.O.
60E 2 x 12 @ 16" o.c. U.N.O.
61 WOOD BLOCKING (size &/or spacing as shown or noted)
62 PRESSURE TREATED WOOD, 2 x MIN (size &/or spacing as shown or noted)
62A ROOF PERIMETER EDGE 5 1/2" MIN. (depth of insulation plus underlayment)xCont
62B FIRE RETARDANT TREATED WOOD (FRT) (size as noted)
62C WOOD CANT 3"x3"xCONT, U.N.O.
63 STRUCTURAL WOOD MEMBERS (Re: Struct. or as noted)
63A WOOD COLUMN
63B WOOD BEAM
63C LAMINATED TIMBER
63D LAMINATED VENEER LUMBER
63F FLITCH PLATE BEAM
63J WOOD JOIST
63T WOOD TRUSS (Re: Struct. or as noted)
64 PLYWOOD, EXTERIOR GRADE
64A 5/8" EXTERIOR GRADE
64B 3/4" EXTERIOR GRADE
64C 3/4" FRT, EXTERIOR GRADE
64D 3/4" MDO
64E 3/4" MDO W/ EDGE BAND
64M 3/4" MARINE GRADE
64R ROOF SHEATHING T & G
65 INTERIOR BOARD
65A 1/2"PLYWOOD
65B 3/4" PLYWOOD
65C 3/4" T & G PLYWOOD
65D PARTICLE BOARD (size as noted)
65E FLOORING UNDERLAYMENT (size as noted)
66 MILLWORK CUSTOM DESIGN (Species/finish as noted and/or specified)
66A WOOD FINISH, STAINED
66B WOOD FINISH, PAINTED
67 WOOD TRIM, INTERIOR
67A TRIM, STAINED
67B TRIM, PAINTED
68 EXTERIOR WOOD FINISH
68A SIDING
68B CLAPBOARD
68C TRIM (Species/finish as noted and/or specified)
68D PREFINISHED SIDING (finish & size as noted)
68F PLASTIC EXTERIOR TRIM WOOD (finish & size as noted)
69 SOLID SURFACE

Thermal & Moisture Protection

70 ROOFING SYSTEM (coordinate w/roof construction type(s))
70A MEMBRANE (by roofing manufacturer)
70B BATTEN STRIP, METAL (by roofing manufacturer)
70C CAP FLASHING (by roofing manufacturer)
70D WALL FLASHING (by roofing manufacturer)
70E DECK UNDERLAYMENT
70F DECK PROTECTION BOARD (by roofing manufacturer)
70G ROOF CRICKET STRUCTURE/SYSTEM
70H CANT STRIP
70J ROOF WALKING PADS (by roofing manufacturer)
70K ROOF VAPOR BARRIER SYSTEM COORDINATE DESIGN & TYPE w/ ROOFING MFR.
70L ROOFING EXPANSION JOINT ASSEMBLY/SYSTEM
70M COMPRESSIBLE FOAM ROD, 1" NOMINAL DIA. U.N.O.
70N FIBERGLASS ROOF SHINGLE SYSTEM, HURRICANE NAILING PATTERN
71 WEATHER/WATERPROOFING SYSTEMS
71A DAMPPROOFING MASTIC
71B AIR BARRIER (COMMERCIAL GRADE)
71C AIR/VAPOR BARRIER SYSTEM
71D VAPOR BARRIER (10 MIL POLY MIN U.N.O.)
71E FELT PAPER 30# MIN U.N.O.
71F ROOFING, WATERPROOF UNDERLAYMENT MEMBRANE (VALLEY, RIDGE, RAKE & EAVE) NON SLIP, 40 MIL. SELF ADHESIVE MEMBRANE
71G PARAPET CAP UNDERLAYMENT MEMBRANE, 40 MIL SELF ADHESIVE MEMBRANE
71H GUTTER LINER MEMBRANE, WATERPROOF, 30 MIL min. U.N.O.
71J BENTONITE WATERPROOFING PANELS & DRAINAGE SYSTEM
71K WATERPROOFING, 60 MIL SELF ADHESIVE MEMBRANE W/PROTECTION BOARD
71L FILTER FABRIC & DIMENSIONAL SYSTEM (HYDROSTATIC RELIEF)
71M IRONITE WATERPROOFING (FOR ELEVATOR PIT INTERIOR)
72 INSULATION, THERMAL, SOUND AND FIRE PROTECTION
72A 1" R- 5 min. EXTRUDED POLYSTYRENE INSULATION
72B 2" R-10 min. EXTRUDED POLYSTYRENE INSULATION
72C 2 1/8" +/- R-12 min. EXTRUDED POLYSTYRENE High R-value CAVITY INSULATION
72D 2" R-11 MIN. POLYISOCYANURATE INSULATION (ROOF INSULATION)
72F BATT INSULATION, R-13 (3 5/8" Thickness)
72G BATT INSULATION, R-21 (6" Thickness)
72H BATT INSULATION, R-24 (8" Thickness)
72J BATT INSULATION, R-30 (10" Thickness)
72K BATT INSULATION, R-36 (12" Thickness)
72L BATT INSULATION, W/CLASS 1 FOIL FACING VAPOR BARRIER
72M MINERAL WOOL INSULATION &/or FIRE SAFING UL RATED FOR INSTALLATION SHOWN
72N SOUND ATTENUATION INSULATION SIZE AS NOTED &/OR INDICAED
72P SPRAY ON FIRE PROTECTON SYSTEM, U.L. RATED AS INDICATED
72R RIGID FIRE PROTECTION SYSTEM, U.L. RATED AS INDICATED
72S SPRAY APPLIED THERMAL/ACOUSTICAL INSULATION
72T CONCEALED MINERAL WOOL FIBER Non-Combustible SEMI-RIGID INSULATION BOARD R-VALUE &/or THICKNESS AS NOTED
72Z LOW EXPANSION POLYURETHANE FOAM INSULATION. 2#/DENSITY CLASS 1 FINISH FIRE RATING. FILL VOID OR AS INDICATED.
73 SEALANT, INTERIOR, EXTERIOR &/OR FIRE RATED SYSTEMS
73A BACKER ROD/ROPE
73B 3/8" +/- SHIM SPACE DRAFT STOP W/LOW EXPANSION POLYURETHANE FOAM
73C SEALANT w/ BACKER ROD /ROPE
73D SEALANT & TERMINATION BAR
73E FIRE CAULKING SYSTEM, UL RATED AS INDICATED FOR APPLICATION SHOWN
74 TRIMS & FASCIAS, PARAPET CAPS, COPPINGS, MISC. METAL FLASHINGS (or as noted)
74A ZINC COATED COPPER 16oz MIN U.N.O.
74B COPPER 20oz MIN U.N.O.
74C HOLD DOWN CLEATS, CONTINUOUS
74D GALV METAL, SIZE AS NOTED
74E GALV METAL, THRU SHEATHING FLASHING
74M SELF ADHERING MEMBRANE FLASHING
75 PREFINISHED METAL (ALUMINUM) SYSTEMS
75A PREFINISHED STANDING SEAM METAL ROOF SYSTEM
75B PREFINISHED, CONCEALED FASTENER METAL PANELS, SIDING SYSTEM
75C SUBFRAMING (GIRTS, CHANNELS, STUDS, JOIST, etc) (size or noted or shown)
75D SOFFIT PANEL SYSTEM PREFINISHED, CONCEALED FASTENER (size as noted or shown)
75E LANCED/VENTED PANELS (10sq IN/LF)
75F PREFINISHED TRIM PIECES
75G METAL CORNICE SYSTEM & SUPPORTS
75H PREFINISHED, CONCEALED FASTENER, INSULATED METAL PANEL SYSTEM
75J COMPOSITE PANEL SYSTEM (size as noted or shown)
76 PREFINISHED METAL (ALUMINUM)
76A FASCIA, PARAPET CAP, GRAVEL STOP
76B FLASHING &/or COUNTER FLASHING, REGLETS (profile & size as noted or shown)
76C CONTINUOUS HOLD DOWN CLIPS (size/color/finish as noted or shown)
76D METAL GUTTER SYSTEM
76E DOWNSPOUT, RECTANGULAR, CORRUGATED
77 EXTERIOR INSULATION FINISH SYSTEM (EIFS)
77A EIFS, 1" RIGID INSULATION
77B EIFS, 2" RIGID INSULATION
77C EIFS, 3" RIGID INSULATION
77D MESH, STANDARD DUTY
77E MESH , HEAVY DUTY
77G SYSTEM WEEPS/FLASHING TERMINATION
78 MISCELLANEOUS ITEMS/MATERIALS/ACCESSORIES
78A ROOF ACCESS HATCH

Doors & Windows

80 DOOR
80A INSULATED METAL CLAD (size/type as noted in door schedule)
80B HOLLOW METAL DOOR
80C WOOD DOOR, SOLID CORE
80E OVERHEAD UPWARD ACTING SECTIONAL
80F OVERHEAD COILING
80G OVERHEAD COILING COUNTER
80H OVERHEAD COILING GRILLE
80J ACOUSTICAL DOOR SYSTEM
81 DOOR FRAME/JAMB
81A HOLLOW METAL FRAME
81B ACOUSTICAL METAL FRAME
81C DOOR GUIDES, BETWEEN JAMB MOUNTING
81D DOOR GUIDES, FACE OF JAMB MOUNTING
82 ACCESS DOOR
82A ACCESS DOOR (U.L. rated in rated assemblies)
82B FLOOR ACCESS DOOR
82C CEILING ACCESS DOOR
83 WINDOW SYSTEMS
83A ALUMINUM WINDOW (size & glazing as noted in window schedule)
83H HOLLOW METAL FRAME (shop primed / field paint)
83S STEEL FRAME WINDOW (size & glazing as noted in window schedule)
83W WOOD WINDOW stained U.N.O. (size & glazing as noted in window schedule)
84 ALUMINUM STOREFRONT &/or CURTAIN WALL WINDOW SYSTEMS
84A ALUMINUM STOREFRONT SYSTEM (size & glazing as noted in window schedule)
84B ALUMINUM STOREFRONT SYSTEM DOOR
84C ALUMINUM CURTAIN WALL SYSTEM (size & glazing as noted in window schedule)
84D ALUMINUM WINDOW, OPERABLE, IN STOREFRONT/CURTAIN WALL SYSTEM
84E ALUMINUM SILL TRIM 0.060 min. U.N.O. (color to match 84A or 84C)
84F ALUMINUM TRIM &/or FLASHING 0.040 min. U.N.O (color to match 84A or 84C)
84G ALUMINUM SUB SILL &/or HEAD RECEIVER (color to match 84A or 84C)
84H CURTAIN WALL STRUCTURAL ATTACHMENT (design by curtain wall mfr)
84J MISC WINDOW EXTENSION TRIM (match window finish)
85 GLAZING (size & type as noted in window schedule)
85A SINGLE PANE (tempered where required by code)
85B INSULATED (tempered where required by code)
85C SPANDREL (tempered where required by code)
85D SPANDREL, INSULATED (tempered where required by code)
85E FIRE RATED
85F WIRE
85G BULLET RESISTANT
85L LAMINATED (with manufacturer etched ID)
87 HARDWARE (Refer Door Schedule)
87A THRESHOLD, SET IN MASTIC
87B THRESHOLD, SET IN GROUT
87C RAIN HOOD/SHIELD
87D KEY CABINET, SURFACE MOUNTED, 100 KEY MIN
87E KNOX BOX; PER LOCAL FIRE DEPT. REQUIREMENTS, RECESS MOUNTED

Finishes

90 WALL BOARD (as noted or shown, Re: Construction Types)
90A 5/8" TYPE 'X' GYP. BD.
90B 1/2" TYPE 'X' GYP. BD.
90C 1/2" TILE BACKER BD.
91 SHEATHING BOARD
91A 5/8" TYPE 'X' FIBERGLASS FACED (water resistant) GYPSUM SHEATHING
91B 1/2" TYPE 'X' FIBERGLASS FACED (water resistant) GYPSUM SHEATHING
91C 1/2" CEMENT BOARD
92 METAL STUD (size & type to match construction type required)
92A 4"x 18 GAUGE @ 16" o.c. U.N.O. (as noted or shown, Re: Construction Types)
92B 6"x 18 GAUGE @ 16" o.c. U.N.O.
92C 2"x 2" x CONT x 20 GAUGE CLIP ANGLE U.N.O.
92D 7/8" FURRING CHANNEL @ 16" o.c. U.N.O.
92E 1/2" RESILIENT FURRING CHANNEL @ 16" o.c. U.N.O.
92F 2" ZEE STUD @ 24" O.C. horiz. U.N.O. (as noted or shown, Re: Construction Types)
92G 2"x 20 GAUGE STRAP
93 DRYWALL ACCESSORIES
93A CASING BEAD
93B CORNER BEAD
93C CONTROL JOINT
93J J BEAD
93L L BEAD
94 not used
95 CEILING, SUSPENDED
95A LAY-IN TILE
95B 5/8" TYPE 'X' GYP. BD. W/ CONCEALED SUSPENSION SYSTEM
95C GYPSUM BOARD
96 FLOOR FINISH
96A TILE, CERAMIC or PORCELAIN (Re: Finish Schedule/Reflected Ceiling Plan)
96B SHEET FLOORING
96C CARPET
96D VCT
96E RUBBER TILE (Re: Finish Schedule)
96F TERRAZZO
96H ATHLETIC: SYNTHETIC
96J ATHLETIC: WOOD
96K AEROBIC/DANCE: WOOD
96L EPOXY FLOOR FINISH
96M RUBBER TREADS &/or NOSING
96N BRASS ANGLE @ TILE EDGES
96P STONE (Re: Finish Schedule)
97 WALL FINISH
97A TILE, CERAMIC or PORCELAIN (size & shape as noted)
97B TILE TRIM PIECE
97C VINYL WALL COVERING
97D PAINT
97E TUB/SHOWER ENCLOSURE PANEL
97F PLASTIC / LAMINATE / CORK PANELS
97G FIBERGLASS REINFORCED PANELS (FRP)
97H WALL PROTECTION (Re: Finish Schedule)
98 BASE (match floor finish material)
98A TILE, COVE U.N.O.
98B VINYL
98C CARPET
98D WOOD
98E RUBBER
98F EPOXY COVE

Specialties

100 TOILET PARTITION, FLOOR MOUNTED, OVERHEAD BRACED
100A URINAL SCREEN
100B PARTITION, DOOR 24" WIDE
100C PARTITION, DOOR 34" WIDE
101 TOILET ACCESSORIES (Re: Toilet Accessory Schedule)
102 MISCELLANEOUS SPECIALTIES
102A FIRE EXTINGUISHER
102E PACKAGE PASS THRU UNIT
102F FLAGPOLE
102G TACKBOARD
102H CHALKBOARD
102K WHITE BOARD (Re: Color Schedule)
102L PROJECTION SCREEN
102M MAILBOX UNIT
102N METAL SHELVING
103 WOVEN WIRE PARTITION SYSTEM (For layout Re: Drwgs)
103A GATE, SWING
103B GATE, SLIDING
104 ARCHITECTURAL EXTERIOR LOUVER (For size, depth, type Re:Drwgs)
104A SUB SILL
105 METAL LOCKER SYSTEM (For size & depth Re: Drwgs)
106 SIGNAGE (For size & type Re: Drwgs)
106A SIGNAGE, INTERIOR
106B SIGNAGE, EXTERIOR
107 OPERABLE WALL PARTITION SYSTEM
107A HEAD TRACK ASSEMBLY (As shown or detailed)
107B TRACK SUPPORT STRUCTURE (size as noted & shown)
107C POCKET DOOR

Equipment

110 PROJECT UNIQUE EQUIPMENT (Re: Equipment Schedule)
111 KITCHEN EQUIPMENT RESTAURANT/COMMERCIAL (Re: Equipment Schedule)
112 RESIDENTIAL KITCHEN EQUIPMENT
112A REFRIGERATOR
112B UNDER COUNTER REFRIGERATOR
112C OVEN
112D COOKTOP
112E EXHAUST HOOD
112F MICROWAVE
112G DISHWASHER
112H RANGE
113 TRASH REMOVAL SYSTEM
113A COMPACTOR
113B CHUTE
113C ROOF VENT/RELIEF
113D DUMPSTER
114 PARKING EQUIPMENT
114A TICKET DISPENSER
114B CARD READER
114C GATE
114D ATTENDANT BOOTH
115 ATHLETIC EQUIPMENT
116 LOADING DOCK EQUIPMENT
116A DOCK BUMPER
116B DOCK SEAL
116C DOCK SHELTER
116D DOCK LEVELER, PIT MOUNT
116E WORK LIGHT
116F IMPACT DOOR
117 not used

Furnishings

120 FLOOR GRILLE w/ EDGE TRIM (Re: Furnishings Drwgs)
120A FLOOR GRILLE (SURFACE, SET IN TILE)
120B WALK OFF CARPET MAT
121 RESIDENTIAL CABINETRY, PREFINISHED, PREFABRICATED
121A BACKSPLASH, 4" U.N.O.
121B FINISHED END PANEL, FACE
121C HARDWARE, PULLS
121D OPEN SHELF, (NO DOOR PANEL)
121E COUNTERTOP & EDGE
121F END SPLASH
122 not used
123 not used
124 not used
125 WINDOW TREATMENT/COVERING
125A BLINDS VERTICAL
125B BLINDS HORIZONTAL
125C CURTAINS (Re: Furnishings Drwgs)
125D SHADES

Division 13 Special Construction

130 PREMANUFACTURED METAL BUILDING SYSTEM
130A STRUCTURAL FRAME
130B WIND FRAMING COLUMN
130C PURLIN OR GIRTS
130E METAL PANEL, CONCEALED FASTENERS, PREFINISHED
130F METAL PANEL, LINER SYSTEM, PREFINISHED
130G TRIM SYSTEM

Conveying Systems

140 ELEVATOR
140A DOOR FRAME SYSTEM
140B DOOR SYSTEM
140C EQUIPMENT
140D ACCESSORIES (Position Indicator, Call Button, etc.)
140E HOIST BEAM
140F SILL PIECE
140G RAIL SUPPORT BEAM
141 not used
142 ESCALATOR
142A GUARD RAIL, GLAZED
142B GUARD RAIL, METAL
142C MISC. TRIM &/OR CLOSURES
143 not used

Mechanical

150 PLUMBING FIXTURES (Re: Plumbing Drwgs)
150A PIPING
150B MISC. ITEM
151 SPRINKLER SYSTEM (Re: Fire Protection Drwgs)
152 STANDPIPE SYSTEM (Re: Fire Protection Drwgs)
153 not used
154 not used
155 HVAC EQUIPMENT &/or ITEM (Re: Mechanical Drwgs)
155A UNIT HEATER
155B BASE BOARD
155C CABINET UNIT
155D DUCTWORK
156 HVAC LOUVER (Re: Mechanical Drwgs)

Electrical

160 ELECTRICAL ITEM (Re: Electrical Drwgs)
160A LIGHTSWITCH
160B RECEPTACLE POWER, DATA &/or COMMUNICATION
161 MAIN ELECTRICAL DISTRIBUTION SYSTEM
162 CIRCUIT PANEL
163 not used
164 not used
165 SECURITY SYSTEM EQUIPMENT
165A CAMERA
165B CARD SWIPE, READER, etc.
165C KEY PAD (Re: Electrical Drwgs)
166 not used

NOTE:
THIS IS A STANDARD SHEET. SOME ITEMS MAY NOT APPLY TO THIS PROJECT. FOR ADDITIONAL INFORMATION RE.: SPECIFICATIONS

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

DAVID L. DECLAUSTRO No. 2152 REGISTERED ARCHITECT

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7158

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB ARCHITECTS

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

MATERIAL LIST

Project Number. 6356

Drawing No.

G002

Sheet of

CODE DATA

I. BUILDING & Fire CODE DATA

RHODE ISLAND STATE BUILDING CODES

SBC-01-2013	BUILDING CODE	IBC-2012 plus RI Amendments 2013 07 01
SBC-02-2013	RESIDENTIAL CODE	IRC-2012 plus RI Amendments 2013 07 01
SBC-03-2013	PLUMBING CODE	IPC-2012 plus RI Amendments 2013 07 01
SBC-04-2013	MECHANICAL CODE	IMC-2012 plus RI Amendments 2013 07 01
SBC-05-2014	ELECTRIC CODE	NFPA 2014 plus RI Amendments 2014 07 01
SBC-08-2013	ENERGY CONSERVATION CODE	IECC-2012 plus RI Amendments 2013 07 01
SBC-19-2010	FUEL GAS CODE	IFGC-2012 plus RI Amendments 2013 07 01

RI ACCESSIBILITY REGULATIONS
SBC-1 IBC-2012 Chapter 11;
ICC/ANSI A117.1 2009 plus RI Amendments 2010 07 01
AMERICANS w/ DISABILITIES ACT (ADA - 2010)

SRC-01-2002 RI State Rehabilitation Building & Fire Code for Existing Buildings & Structures 2002 05 01

RHODE ISLAND FIRE SAFETY CODE (RIFSC - 2013)

RHODE ISLAND FIRE LAWS (RIFL)
TITLE 23, CHAPTERS 28.1 - 28.39

RULES & REGULATIONS PROMULGATED BY the Board of Appeals & Review
SECTIONS 1 THRU 15

RHODE ISLAND UNIFORM FIRE CODE (RIUFC - 2012)
NFPA 1-2012 plus RI AMENDMENTS

RHODE ISLAND LIFE SAFETY CODE (RILSC - 2012)
NFPA 101-2012 plus RI AMENDMENTS

ADDITIONAL APPLICABLE NFPA STANDARDS
NFPA 10 2013 PORTABLE FIRE EXTINGUISHERS
NFPA 13 2013 INSTALLATION OF SPRINKLER SYSTEMS
NFPA 14 2013 STANDPIPES
NFPA 72 2010 NATIONAL FIRE ALARM CODE PLUS RI AMENDMENTS
NFPA 220 2012 STANDARD OF TYPES OF BUILDING CONSTRUCTION
NFPA 701 1999 STANDARD METHOD OF FIRE TESTS FOR FLAME PROPAGATION OF TEXTILES

A. OCCUPANCY & USE (IBC CHAPTERS 3 & 4)

EXISTING BUILDING w/ PRIMARY BUSINESS USE w/ SECONDARY ASSEMBLY USE.
RENOVATION SCOPE OF WORK WITHIN BUSINESS AREA.,

B. CONSTRUCTION TYPES & SEPARATION REQUIREMENTS - CHAPTER 5

NON-SEPARATED MIXED USE IF SPRINKLERED, 0 HR RATING BETWEEN USES REQUIRED PER IBC TABLE 508.3.3

CONSTRUCTION TYPE: IIA* (IBC TABLE 503) II(III) NFPA 220
*IBC CONSTRUCTION TYPE REDUCED FROM IB TO IIA PER 403.3.1 (2)

BUILDING ELEMENT	RATING IN HOURS	
	IBC (table 601) IIA	NFPA 220 (table 4.1.1) II(III)
STRUCTURAL FRAME	1	1
BEARING WALLS		
EXTERIOR	1	1
INTERIOR	1	1
NON BEARING WALLS AND PARTITIONS EXTERIOR	0*	0
NON BEARING WALLS AND PARTITIONS INTERIOR	0	0
FLOOR CONSTRUCTION INCLUDING SUPPORTING BEAMS AND JOISTS	1	1
ROOF CONSTRUCTION INCLUDING SUPPORTING BEAMS AND JOISTS	1	1

*IBC TABLE 602 (>30' = 0)

D. FIRE RESISTANCE-RATED CONSTRUCTION
-STAIR & ELEVATOR SHAFTS WILL BE 2HR RATED MASONRY CONSTRUCTION
-SHAFTS CONNECTING 4 LEVELS OR MORE WILL BE 1HR RATED CONSTRUCTION w/ SPRINKLERS AT ALTERNATING LEVELS.
-EXIST ACCESS CORRIDORS WILL NOT BE RATED PER IBC ----- & NFPA 38.3.6.1(3)

E. INTERIOR FINISHES
-CLASS B OR BETTER FINISHES WILL BE PROVIDED IN ALL STAIRS, ELEVATORS, CORRIDORS & LOBBIES PER IBC TABLE 803.5 & NFPA 38.3.3.2.1

F. FIRE PROTECTION
1. AUTOMATIC FIRE SUPPRESSION - NFPA 13
2. FIRE ALARM SYSTEM
RI UNIFORM FIRE CODE 13.7 & 13.8 & NFPA 72 RI LIFE SAFETY CODE REQUIRES A FIRE ALARM SYSTEM.

G. OCCUPANCY LOADS

1. OCCUPANCY LOAD TYPES

	IBC TABLE 1004.1.2	NFPA 101 TABLE 7.3.1.2
BUSINESS	100 SF./PERSON GROSS	100 SF./PERSON
ASSEMBLY (UNCONCENTRATED)	15 SF./PERSON GROSS	15 SF./PERSON

2. OCCUPANCY LOAD PER FLOOR

	AREA (GROSS)	OCCUPANCY
BUILDING 1		
BUSINESS	23,099 GSF	231 OCCUPANTS
ASSEMBLY	5,876 GSF	392 OCCUPANTS
	28,975 GSF	623 OCCUPANTS
BUILDING 3		
BUSINESS	18,106 GSF	182 OCCUPANTS
	18,106 GSF	182 OCCUPANTS

H. EGRESS REQUIREMENTS

1. LENGTH OF TRAVEL - NFPA 101 TABLE 12.1.6 & SECTION 12.2.6 - IBC TABLE 1016.1
B BUSINESS (w/ SPRINKLER SYSTEM)
IBC 300 LF
NFPA 101 300 LF

2. COMMON PATH - NFPA 101 TABLE A.7.6 - IBC SECTION 1014.3
B BUSINESS (w/ SPRINKLER SYSTEM)
IBC 100 LF
NFPA 101 100 LF

DEAD END CORRIDOR - NFPA 101 TABLE A.7.6 - IBC 1017.3
B BUSINESS (w/ SPRINKLER SYSTEM)
IBC 50 LF
NFPA 101 50 LF

3. MEANS OF EGRESS - IBC Section 1005.1 & 1018.4

NUMBER AND WIDTH REQUIRED

DOOR WIDTH (w/ SPRINKLER SYSTEM)
IBC 0.2"/PERSON (32" MIN. CLEAR WIDTH)
NFPA 101 0.2"/PERSON (32" MIN. CLEAR WIDTH)
STAIR WIDTH (w/ SPRINKLER SYSTEM)
IBC 0.3"/PERSON (48" MIN. CLEAR WIDTH FOR ACCESSIBLE)
NFPA 101 0.3"/PERSON (44" MIN. CLEAR BETWEEN GUARDS)

TOTAL EXITS REQUIRED, IBC TABLE 1019.1 = 2 EXITS PER FLOOR

EGRESS WIDTHS REQUIRED, (MORE STRINGENT OF ABOVE)

DOORS:
TOTAL WIDTH REQUIRED FOR DOORS = .2 x 384 PEOPLE = 76.8 IN.
TOTAL WIDTH PROVIDED FOR DOORS = 66 IN.
STAIRS:
TOTAL WIDTH REQUIRED FOR DOORS = .3 x 384 PEOPLE = 115.2 IN.
TOTAL WIDTH PROVIDED FOR DOORS = 96 IN.

I. PLUMBING FIXTURE ANALYSIS (BASED ON IBC chapter 29; Table 2902.1; IPC TABLE 403.1)

BUSINESS - BASED ON 231 OCCUPANTS

	FIXTURES	CODE REQUIREMENT				PROJECT DESIGN PROVIDED			
			MALE	FEMALE	TOTAL	MALE	FEMALE	UNISEX	TOTAL
BUILDING 1	WATER CLOSETS	1/25 (1ST 80) 1/50	6		6	4	6	1	11
	URINALS	NOT MORE THAN 50%				5	NA	0	5
	LAVATORIES	1/40 (1ST 80) 1/80	4		4	5	5	1	11
	DRINKING FOUNTAINS	1/100			3				(EX.) 2
	SERVICE SINK	1			1				1

ASSEMBLY - BASED ON 392 OCCUPANTS

	FIXTURES	CODE REQUIREMENT			
			MALE	FEMALE	TOTAL
BUILDING 1	WATER CLOSETS	1/75 (M) 1/40 (F)	3	5	8
	URINALS	NOT MORE THAN 50%			
	LAVATORIES	1/200 (M) 1/150 (F)	1	2	3
	DRINKING FOUNTAINS	1/100			3
	SERVICE SINK	1			1

BUSINESS - BASED ON 182 OCCUPANTS

	FIXTURES	CODE REQUIREMENT				PROJECT DESIGN PROVIDED			
			MALE	FEMALE	TOTAL	MALE	FEMALE	UNISEX	TOTAL
BUILDING 3	WATER CLOSETS	1/25 (1ST 80) 1/50	5		5	4	5	0	9
	URINALS	NOT MORE THAN 50%				4	NA	0	4
	LAVATORIES	1/40 (1ST 80) 1/80	4		4	6	6	0	12
	DRINKING FOUNTAINS	1/100			2				
	SERVICE SINK	1			1				

KEY

OCCUPANT LOAD INDICATOR

EGRESS ELEMENT LOAD INDICATOR

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL
Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

CODE REVIEW

Project Number. 6356

Drawing No.

A010

Sheet of

'F1' DESIGNATION INDICATES: FIRE RATED -
THIS WALL IS A PORTION OF A 1 HR RATED ASSEMBLY SIM TO U.L. U420

A2 or A2/F1 2 1/2" MTL STUDS

A3 or A3/F1 3 5/8" MTL STUDS

A6 or A6/F1 6" MTL STUDS

'F1' DESIGNATION INDICATES: 1 HR FIRE RATED U.L. U419
SOUND RATINGS:
STC 38 (C2) STC 47 (C2Z)
STC 40 (C3) STC 49 (C3Z)

C2 or C2/F1 2 1/2" MTL STUDS

C3 or C3/F1 3 5/8" MTL STUDS

C6 or C6/F1 6" MTL STUDS

NO RATING REQUIRED STC 49	1 HOUR RATING REQUIRED U.L. U906 STC 49	2 HOUR RATING REQUIRED U.L. U906 STC 49
M8 8" CMU	M8/F1 8" CMU	M8/F2 8" CMU TYPE D-2 CMU

PER WALL TYPE

S1 3 5/8" MTL STUDS

TYPICAL SHOWER PARTITION

R1 7/8" MTL 'HAT'

R2 TILE WALL

S1 3 5/8" MTL STUDS

TYPICAL SHOWER PARTITION

1 / A030 INTERIOR WALL CONSTRUCTION TYPES

Scale: 1 1/2" = 1'-0"

INTERIOR WALL DESIGNATIONS:

"M" INDICATES MASONRY WALL
"CL" INDICATES PROTECTED COLUMN ASSEMBLY - SEE COLUMN FIREPROOFING NOTES THIS SHEET

EXAMPLE - WALL "A2"
"A" - WALL TYPE
"2" - STUD THICKNESS

EXAMPLE - WALL TYPE "M4"
"M" - MASONRY WALL
"4" - CMU THICKNESS

METAL STUDS	WOOD STUDS	MASONRY WALLS
1 = 1 5/8" STUDS	3 = 2 X 3 STUDS	2 = 1 5/8" SOAP
2 = 2 1/2" STUDS	4 = 2 X 4 STUDS	4 = 4" BLOCK
3 = 3 5/8" STUDS	6 = 2 X 6 STUDS	6 = 6" BLOCK
4 = 4" STUDS		8 = 8" BLOCK
6 = 6" STUDS		10 = 10" BLOCK
		12 = 12" BLOCK

TYPICAL CONTROL JOINTS

GENERAL NOTES:

1. ALL GYPSUM SHEATHING/WALL BOARD IS TYPE 'X'.
2. PROVIDE METAL STUD GAUGE AS RECOMMENDED BY STUD MFG. FOR WALL LIVE LOAD OF 7 psf FOR HEIGHT OF THE UNBRACED WALL VERTICAL SPAN. MAXIMUM DEFLECTION 1/360 OF THE SPAN.
3. FOR NON-LOAD BEARING WALLS THAT SEAL TO ROOF STRUCTURE ABOVE, PROVIDE SUITABLE STUD TRACK TO ALLOW FOR MINIMUM ROOF DEFLECTION OF 1" WITHOUT TRANSFERING LOAD TO METAL STUDS RE: STRUCTURAL DWGS FOR MORE STRINGENT DEFLECTION INFORMATION. (NOT REQUIRED @ PERIMETER EXTERIOR WALLS UNLESS NOTED OTHERWISE)
4. HOLD BOTTOM OF GWB @ 1/4" ABOVE CONCRETE FLOOR TYPICAL (TO PREVENT MOISTURE WICKING)
5. PROVIDE TYPE 'X' MOISTURE RESISTANT GYPSUM WALL BOARD AT ALL TOILET ROOMS, SPRINKLER ROOMS AND JANITOR CLOSETS UNLESS NOTED OTHERWISE.
6. PROVIDE 20 GA METAL STUDS MIN. AT CEMENT BOARD WALLS & WALLS TO RECEIVE STONE VENEER.
7. PROVIDE FIRE RATED CAULKING AT TOP OF ALL FIRE RATED WALLS THAT SEAL TO UNDERSIDE OF STRUCTURE. (i.e. BETWEEN METAL DECK FLUTES.)
8. ALL EXPOSED INTERIOR MASONRY WALLS TO HAVE 1" BULLNOSE CORNERS @ EXTERIOR CORNERS AND WINDOW/DOOR JAMBS UNLESS NOTED OTHERWISE.
9. STC RATINGS FOR WALL CONSTRUCTION TYPES ARE BASED ON USG CORPORATION SELECTOR GUIDE TO SOUND-RATED PARTITIONS (SA100).
10. ALL WALL SYSTEM 'R' & 'U' VALUES ARE BASED ON:
    - 6" METAL STUD
    - 8" NORMAL WEIGHT CMU
    - 8" NORMAL WEIGHT CONCRETE
11. ALL VAPOR BARRIERS ARE TO BE 10MIL POLY MIN. U.N.O.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

CONSTRUCTION TYPES

Project Number. 6356

Drawing No.

A030

Sheet of

1 BUILDING 1 - EXISTING OVERALL DEMOLITION FLOOR PLAN

D100 Scale: 1/16" = 1'-0"

2 ENLARGED DEMOLITION PLAN - A

D100 Scale: 1/4" = 1'-0"

3 ENLARGED LATRINES DEMOLITION PLAN - B

D100 Scale: 1/4" = 1'-0"

DEMOLITION NOTES:

1. THE SCOPE OF THIS DEMOLITION PACKAGE IS TO PROVIDE A NEW LATRINE, LOCKER AND SHOWER ROOM LAYOUTS FOR AN INCREASE SQUARE FOOTAGE OF THE EXISTING MEN AND WOMEN'S LATRINE.
2. THE EXISTING CONDITIONS INFORMATION SHOWN &/or INDICATED ON THE DRAWINGS WAS OBTAINED FROM LIMITED EXISTING DRAWINGS PREPARED BY OTHERS, [WHEN AVAILABLE]; FIELD REVIEW; FIELD MEASUREMENT; &/or OTHER AVAILABLE DOCUMENTATION &/or OBSERVATION BY OTHERS. NOT ALL EXISTING CONDITIONS &/or ACTUAL CONSTRUCTION MAY BE INDICATED &/or KNOWN.
3. CONTRACTOR TO VERIFY ALL EXISTING, CONDITIONS, CONNECTIONS, LOCATIONS, SIZES, ETC. IN THE FIELD AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE STARTING DEMOLITION WORK.
4. CONTRACTOR TO COORDINATE EXTENTS OF ALL DEMOLITION WORK WITH ALL NEW WORK AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE STARTING DEMOLITION WORK.
5. CONTRACTOR TO PROPERLY DE-ENERGIZE, SHUT OFF & CAP ALL UTILITIES (ELECTRICAL, GAS, WATER, SEWER, TELEPHONE, ETC.) BACK TO THE EXISTING EXTERIOR WALLS, ROOF DECK, AND/OR TO SLAB OR GRADE. U.N.O. COORDINATE W\ MEP DEMOLITION DWGS & LOCAL UTILITY COMPANIES.
6. FULL EXTENT OF BUILDING MATERIALS IS KNOWN. EXISTING BUILDING CONSTRUCTION MAY CONTAIN MATERIALS THAT REQUIRE ABATEMENT. IF POTENTIAL MATERIALS ARE DISCOVERED, CONTRACTOR TO NOTIFY OWNER & ARCHITECT BEFORE PROCEEDING WITH WORK.
7. CONTRACTOR TO PROVIDE ALL OSHA and/or BUILDING CODE REQUIRED SAFETY PROTECTION TO PROTECT WORKERS FROM FALLS, CRUSHING, ELECTROCUTION, IMPACT FROM ABOVE, ETC.
8. CONTRACTOR TO MAINTAIN BUILDING IN A SAFE AND SECURE MANNER AND TO ELIMINATE THE APPEARANCE OF AN ATTRACTIVE NUISANCE. MAINTAIN PHYSICAL BARRIER TO PREVENT BUILDING/ SITE ACCESS BY CHILDREN AT A MINIMUM.
9. CONTRACTOR TO PROTECT ALL EXISTING WORK TO REMAIN DURING DEMOLITION.
10. CONTRACTOR TO FURNISH AND INSTALL ALL SHORING AND/OR BRACING TO SUPPORT ALL EXISTING WALLS, FLOORS/ROOFS, ETC. PRIOR TO REMOVALS OF EXISTING CONSTRUCTION.
11. EXISTING BUILDING CONSTRUCTION DEFICIENCIES NOT INDICATED ON THE DRAWINGS, BUT UNCOVERED &/or DISCOVERED BY CONTRACTOR'S CONSTRUCTION ACTIVITIES SHALL BE REPORTED TO THE ARCHITECT FOR REVIEW PRIOR TO INSTALLATION OF NEW WORK. ADDITIONAL DETAILS WILL BE FURNISHED AS NECESSARY. TYPICAL.

DEMOLITION LEGEND:

EXISTING WALL/ITEM TO REMAIN

EXISTING WALL/ITEM TO BE REMOVED

R&D = REMOVE & DISPOSE OF
R&S = REMOVE & SALVAGE

DEMOLITION WORK NOTES:

- XXX — NOTES WITHOUT AN ARROW INDICATE AN ENTIRE SPACE/AREA.
- XXX — NOTES WITH AN ARROW(S) INDICATE SPECIFIC AREAS &/or ITEMS.
- D1 — R&D EXISTING INTERIOR WALL IN ITS ENTIRETY & PREP FOR NEW WORK. (TYP.)
- D2 — R&D DOOR, FRAME & HARDWARE.
- D3 — R&D LAVATORY FIXTURE AND PLUMBING. RE. PLUMBING DRAWINGS.
- D4 — R&D EXISTING TOILET PARTITIONS
- D5 — R&D GANG SHOWER FIXTURES. RE. PLUMBING DRAWINGS.
- D6 — R&D URINAL FIXTURES. RE. PLUMBING DRAWINGS.
- D7 — R&D HEATING REGISTER AND PIPING TO SOURCE.
- D8 — R&D EXISTING CEILING
- D9 — SELECTIVE DEMOLITION AND TRENCHING OF EXISTING CONCRETE SLAB REQUIRED, COORDINATE EXTENT OF TRENCHING w/ PLUMBING DRAWINGS FOR ALL REQUIRED PIPE RUNS, DRAINS. (TYP)

KEY PLAN
Scale: N.T.S.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

DAVID L. DECUATTIS No. 2152 REGISTERED ARCHITECT

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 DEMOLITION PLAN

Project Number. 6356

Drawing No.

D100

Sheet of

1 / D101 BUILDING 3 - EXISTING OVERALL DEMOLITION FLOOR PLAN

Scale: 1/16" = 1'-0"

2 / D101 BUILDING 3 - ENLARGED LATRINES DEMOLITION PLAN - A

Scale: 1/4" = 1'-0"

DEMOLITION NOTES:

1. THE SCOPE OF THIS DEMOLITION PACKAGE IS TO PROVIDE A NEW LATRINE, LOCKER AND SHOWER ROOM LAYOUTS FOR AN INCREASE SQUARE FOOTAGE OF THE EXISTING MEN AND WOMEN'S LATRINE.
2. THE EXISTING CONDITIONS INFORMATION SHOWN &/or INDICATED ON THE DRAWINGS WAS OBTAINED FROM LIMITED EXISTING DRAWINGS PREPARED BY OTHERS, (WHEN AVAILABLE); FIELD REVIEW; FIELD MEASUREMENT; &/or OTHER AVAILABLE DOCUMENTATION &/or OBSERVATION BY OTHERS. NOT ALL EXISTING CONDITIONS &/or ACTUAL CONSTRUCTION MAY BE INDICATED &/or KNOWN.
3. CONTRACTOR TO VERIFY ALL EXISTING, CONDITIONS, CONNECTIONS, LOCATIONS, SIZES, ETC. IN THE FIELD AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE STARTING DEMOLITION WORK.
4. CONTRACTOR TO COORDINATE EXTENTS OF ALL DEMOLITION WORK WITH ALL NEW WORK AND NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE STARTING DEMOLITION WORK.
5. CONTRACTOR TO PROPERLY DE-ENERGIZE, SHUT OFF & CAP ALL UTILITIES (ELECTRICAL, GAS, WATER, SEWER, TELEPHONE, ETC.) BACK TO THE EXISTING EXTERIOR WALLS, ROOF DECK, AND/OR TO SLAB OR GRADE. U.N.O. COORDINATE W\ MEP DEMOLITION DWGS & LOCAL UTILITY COMPANIES.
6. FULL EXTENT OF BUILDING MATERIALS IS KNOWN. EXISTING BUILDING CONSTRUCTION MAY CONTAIN MATERIALS THAT REQUIRE ABATEMENT. IF POTENTIAL MATERIALS ARE DISCOVERED, CONTRACTOR TO NOTIFY OWNER & ARCHITECT BEFORE PROCEEDING WITH WORK.
7. CONTRACTOR TO PROVIDE ALL OSHA and/or BUILDING CODE REQUIRED SAFETY PROTECTION TO PROTECT WORKERS FROM FALLS, CRUSHING, ELECTROCUTION, IMPACT FROM ABOVE, ETC.
8. CONTRACTOR TO MAINTAIN BUILDING IN A SAFE AND SECURE MANNER AND TO ELIMINATE THE APPEARANCE OF AN ATTRACTIVE NUISANCE. MAINTAIN PHYSICAL BARRIER TO PREVENT BUILDING/ SITE ACCESS BY CHILDREN AT A MINIMUM.
9. CONTRACTOR TO PROTECT ALL EXISTING WORK TO REMAIN DURING DEMOLITION.
10. CONTRACTOR TO FURNISH AND INSTALL ALL SHORING AND/OR BRACING TO SUPPORT ALL EXISTING WALLS, FLOORS/ROOFS, ETC. PRIOR TO REMOVALS OF EXISTING CONSTRUCTION.
11. EXISTING BUILDING CONSTRUCTION DEFICIENCIES NOT INDICATED ON THE DRAWINGS, BUT UNCOVERED &/or DISCOVERED BY CONTRACTOR'S CONSTRUCTION ACTIVITIES SHALL BE REPORTED TO THE ARCHITECT FOR REVIEW PRIOR TO INSTALLATION OF NEW WORK. ADDITIONAL DETAILS WILL BE FURNISHED AS NECESSARY. TYPICAL.

DEMOLITION LEGEND:

EXISTING WALL/ITEM TO REMAIN

EXISTING WALL/ITEM TO BE REMOVED

R&D = REMOVE & DISPOSE OF
R&S = REMOVE & SALVAGE

DEMOLITION WORK NOTES:

- XXX — NOTES WITHOUT AN ARROW INDICATE AN ENTIRE SPACE/AREA.
- XXX — NOTES WITH AN ARROW(S) INDICATE SPECIFIC AREAS &/or ITEMS.
- D1 — R&D EXISTING INTERIOR WALL IN ITS ENTIRETY & PREP FOR NEW WORK. (TYP.)
- D2 — R&D DOOR, FRAME & HARDWARE.
- D3 — R&D LAVATORY FIXTURE AND PLUMBING. RE. PLUMBING DRAWINGS.
- D4 — R&D EXISTING TOILET PARTITIONS
- D5 — R&D GANG SHOWER FIXTURES. RE. PLUMBING DRAWINGS.
- D6 — R&D URINAL FIXTURES. RE. PLUMBING DRAWINGS.
- D7 — R&D HEATING REGISTER AND PIPING TO SOURCE.
- D8 — R&D EXISTING CEILING
- D9 — SELECTIVE DEMOLITION AND TRENCHING OF EXISTING CONCRETE SLAB REQUIRED, COORDINATE EXTENT OF TRENCHING w/ PLUMBING DRAWINGS FOR ALL REQUIRED PIPE RUNS, DRAINS. (TYP)

KEY PLAN
Scale: N.T.S.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 DEMOLITION PLAN

Project Number. 6356

Drawing No.

D101

Sheet of

1 BUILDING 1 - EXISTING OVERALL FLOOR PLAN

A100 Scale: 1/16" = 1'-0"

2 ENLARGED LATRINE FLOOR PLAN - B

A100 Scale: 1/4" = 1'-0"

3 ENLARGED LATRINE FLOOR PLAN - A

A100 Scale: 1/4" = 1'-0"

4 ENLARGED CLOSET PLAN - C

A100 Scale: 1/4" = 1'-0"

GENERAL PLAN NOTES:

1. COORDINATE ALL NEW WORK w/ CIVIL, STRUCTURAL, PLUMBING, MECHANICAL, ELECTRICAL, &/or OTHER DRAWGINS. NOTIFY ARCHITECT OF ANY DISCREPANCIES BEFORE PROCEEDING WITH WORK.
2. ALL DIMENSIONS TO NEW CONSTRUCTION ARE TO FACE OF STUD AND FACE OF MASONRY U.N.O.
3. ALL DIMENSIONS TO EXISTING CONSTRUCTION ARE TO FACE OF FINISH U.N.O.
4. ALL NEW INTERIOR WALLS ARE TO EXTEND TO THE UNDERSIDE OF ROOF &/or FLOOR STRUCTURE ABOVE U.N.O.
5. ALL NEW DOOR FRAMES SHALL BE A MINIMUM OF 4" CLEAR FROM THE FACE OF ADJACENT WALL TO DOOR JAMB, U.N.O.

LEGEND:

EXIST. WALL TO REMAIN.

NEW WALLS

PLAN WORK NOTES:

XXX	NOTES WITHOUT AN ARROW INDICATE AN ENTIRE SPACE/AREA.
XXX	NOTES WITH AN ARROW(S) INDICATE SPECIFIC AREAS &/or ITEMS.
A#.#	PLAN WORK NOTE
A1	EXISTING CONCRETE SLAB TO BE SCARIFIED. POURED EPOXY FLOORING WITH INTEGRAL MOISTURE MITIGATION, DURAGLAZE MVP, TO BE APPLIED OVER EXISTING FLOOR, PREPPED PER MANUFACTURER'S REQUIREMENTS. DURA QUARTZ FLOORING TO INCLUDE 6" FLASHED COVE BASE INTEGRAL TO SYSTEM, TYP.
A2	SOLID PHENOLIC PARTITIONS, TYPICAL.
A3	XLERATOR HAND DRYER. RE: ELECTRICAL DRAWINGS.
A4	LAV FIXTURE WITH INTEGRAL COUNTER. RE: PLUMBING DRAWINGS
A5	H.C. LAV FIXTURE. RE: PLUMBING DWGS & A700 FOR ADA REQUIREMENTS.
A6	CHANGING AREA AT WOMEN'S SHOWERS WITH (2) PRIVACY CURTAINS.
A7	ALL CMU OUTSIDE CORNERS TO BE BULL NOSE, TYP.
A8	STAINLESS STEEL SHOWER ROD AND CURTAIN, TYP.
A9	CONCRETE SLAB INFILL AT SHOWER AREAS TO BE COORDINATED WITH SLOPED FLOOR TO DRAIN.
A10	LOCKER AREA BENCH WITH STAINLESS STEEL PEDESTAL BASE ANCHORED TO SLAB. RE: SPECIFICATIONS.
A11	NEW SLOP SINK. RE: PLUMBING DRAWINGS
A12	STAINLESS STEEL TRANSITION STRIP AT FLOORING TRANSITION
A13	ALL SHOWER FIXTURES AND ACCESSORIES SHOWN TO BE NEW, RE:A700 & PLUMBING DRAWINGS.
A14	ALL TOILET ROOM FIXTURES AND ACCESSORIES SHOWN TO BE NEW, RE:A700 & PLUMBING DRAWINGS.
A15	NEW THICKENED SLAB ON GRADE. REFER TO DETAIL 4/A400 , TYPICAL AT ALL NEW CMU WALLS.
A16	JANITORS SPIGOT. RE: PLUMBING DRAWINGS.

KEY PLAN

Scale: N.T.S.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 FLOOR PLAN

Project Number. 6356

Drawing No.

A100

Sheet of

1 BUILDING 3 - EXISTING OVERALL FLOOR PLAN

A101 Scale: 1/16" = 1'-0"

2 BUILDING 3 - ENLARGED LATRINES FLOOR PLAN - A

A101 Scale: 1/4" = 1'-0"

GENERAL PLAN NOTES:

1. COORDINATE ALL NEW WORK w/ CIVIL, STRUCTURAL, PLUMBING, MECHANICAL, ELECTRICAL, &/or OTHER DRAWGINS. NOTIFY ARCHITECT OF ANY DISCREPANCIES BEFORE PROCEEDING WITH WORK.
2. ALL DIMENSIONS TO NEW CONSTRUCTION ARE TO FACE OF FINISH AND FACE OF MASONRY U.N.O.
3. ALL DIMENSIONS TO EXISTING CONSTRUCTION ARE TO FACE OF FINISH U.N.O.
4. ALL NEW INTERIOR WALLS ARE TO EXTEND TO THE UNDERSIDE OF ROOF &/or FLOOR STRUCTURE ABOVE U.N.O.
5. ALL NEW DOOR FRAMES SHALL BE A MINIMUM OF 4" CLEAR FROM THE FACE OF ADJACENT WALL TO DOOR JAMB, U.N.O.

LEGEND:

- EXIST. WALL TO REMAIN. REFER TO FLOOR WORK NOTES FOR ADDITIONAL INFO.
- NEW WALLS

PLAN WORK NOTES:

- XXX — NOTES WITHOUT AN ARROW INDICATE AN ENTIRE SPACE/AREA.
- XXX — NOTES WITH AN ARROW(S) INDICATE SPECIFIC AREAS &/or ITEMS.
- A#.# — PLAN WORK NOTE
- A1 — EXISTING CONCRETE SLAB TO BE SCARIFIED. POURED EPOXY FLOORING WITH INTEGRAL MOISTURE MITIGATION, DURAGLAZE MVP, TO BE APPLIED OVER EXISTING FLOOR, PREPPED PER MANUFACTURER'S REQUIREMENTS. DURA QUARTZ FLOORING TO INCLUDE 6" FLASHED COVE BASE INTEGRAL TO SYSTEM, TYP.
- A2 — SOLID PHENOLIC PARTITIONS, TYPICAL.
- A3 — XLERATOR HAND DRYER. RE: ELECTRICAL DRAWINGS.
- A4 — LAV FIXTURE WITH INTEGRAL COUNTER. RE: PLUMBING DRAWINGS
- A5 — H.C. LAV FIXTURE. RE: PLUMBING DWGS & A700 FOR ADA REQUIREMENTS.
- A6 — CHANGING AREA AT WOMEN'S SHOWERS WITH (2) PRIVACY CURTAINS.
- A7 — ALL CMU OUTSIDE CORNERS TO BE BULL NOSE, TYP.
- A8 — STAINLESS STEEL SHOWER ROD AND CURTAIN, TYP.
- A9 — CONCRETE SLAB INFILL AT SHOWER AREAS TO BE COORDINATED WITH SLOPED FLOOR TO DRAIN.
- A10 — LOCKER AREA BENCH WITH STAINLESS STEEL PEDESTAL BASE ANCHORED TO SLAB. RE: SPECIFICATIONS.
- A11 — NEW SLOP SINK. RE: PLUMBING DRAWINGS
- A12 — STAINLESS STEEL TRANSITION STRIP AT FLOORING TRANSITION
- A13 — ALL SHOWER FIXTURES AND ACCESSORIES SHOWN TO BE NEW, RE:A700 & PLUMBING DRAWINGS.
- A14 — ALL TOILET ROOM FIXTURES AND ACCESSORIES SHOWN TO BE NEW, RE:A700 & PLUMBING DRAWINGS.
- A15 — NOT USED
- A16 — JANITORS SPIGOT. RE: PLUMBING DRAWINGS.

KEY PLAN
Scale: N.T.S.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 FLOOR PLAN

Project Number. 6356

Drawing No.

A101

Sheet of

1 BUILDING 1 - EXISTING OVERALL FLOOR PLAN
A100 Scale: 1/16" = 1'-0"

2 ENLARGED LATRINES CEILING PLAN - B
A600 Scale: 1/4" = 1'-0"

1 ENLARGED EXISTING LATRINES CEILING PLAN - A
A600 Scale: 1/4" = 1'-0"

REFLECTED CEILING PLAN NOTES:

1. NOT ALL CEILING MOUNTED &/or SUSPENDED ITEMS, COMPONENTS, &/or WORK MAY BE SHOWN. CONTRACTOR TO COORDINATE w/ ALL DRAWINGS INCLUDING THE STRUCTURAL, PLUMBING, MECHANICAL & ELECTRICAL DRAWINGS. NOTIFY THE ARCHITECT OF ANY ADDITIONAL ITEMS &/or DISCREPANCIES BEFORE STARTING WORK.
2. ALL CEILING MOUNTED ITEMS ARE TO BE CENTERED IN CEILING TILES U.N.O.
3. SPRINKLER HEAD LAYOUT IS APPROXIMATE AND NOT ALL HEADS MAY BE SHOWN. COORDINATE w/ SPRINKLER DWGS AND NOTIFY ARCHITECT OF ANY DISCREPANCIES BEFORE STARTING WORK.
4. PROVIDE WHITE GROMMET TRIM @ ALL SUPPORT CABLE &/or WIRING PENETRATIONS FOR SUSPENDED ELEMENTS.
5. EXISTING CEILING HEIGHT 9'-0". TO COORDINATE WITH MEP ENGINEER FOR REQUIRED CLEARANCE FOR DIFFUSERS, DUCTWORK, LIGHT FIXTURES, ETC.

REFLECTED CEILING PLAN LEGEND:

- NEW GYPSUM BOARD SOFFIT OR GYPSUM BOARD CEILING
- NEW CEILING GRID
- 2X2 CEILING LIGHT. COORDINATE w/ ELECTRICAL DWGS
- NEW CEILING MOUNTED HVAC SUPPLY DIFFUSER COORDINATE w/ MECHANICAL DWGS
- NEW CEILING MOUNTED HVAC RETURN DIFFUSER. COORDINATE w/ MECHANICAL DWGS.
- RECESSED OR SURFACE MOUNTED FLUORESCENT LIGHT FIXTURE. COORDINATE w/ ELECTRICAL DWGS
- NEW WALL MOUNTED UP/DN. LIGHT FIXTURE COORDINATE w/ ELECTRICAL DWGS
- NEW CEILING MOUNTED LIGHT COORDINATE w/ ELECTRICAL DWGS

REFLECTED CEILING PLAN WORK NOTES:

- XXX — NOTES WITHOUT AN ARROW INDICATE AN ENTIRE SPACE/AREA.
- XXX — NOTES WITH AN ARROW(S) INDICATE SPECIFIC AREAS &/or ITEMS.
- RCP — CEILINGS
- RCP1 — 2'X2' ACT SYSTEM ALL ACT CEILINGS @ 9'-0" A.F.F. U.N.O.
- RCP2 — GWB CEILING @ 9'-0", EPOXY PAINTED

KEY PLAN
Scale: N.T.S.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL
Checked by RJJ
Revised on

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project
RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status
CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents
REFLECTED CEILING PLAN - BUILDING 1

Project Number. 6356

Drawing No.
A600

Sheet of

1 BUILDING 3 - EXISTING OVERALL FLOOR PLAN

A101 Scale: 1/16" = 1'-0"

2 BUILDING 3 - ENLARGED EXISTING LATRINES CEILING PLAN - A

A601 Scale: 1/4" = 1'-0"

REFLECTED CEILING PLAN NOTES:

1. NOT ALL CEILING MOUNTED &/or SUSPENDED ITEMS, COMPONENTS, &/or WORK MAY BE SHOWN. CONTRACTOR TO COORDINATE w/ ALL DRAWINGS INCLUDING THE STRUCTURAL, PLUMBING, MECHANICAL & ELECTRICAL DRAWINGS. NOTIFY THE ARCHITECT OF ANY ADDITIONAL ITEMS &/or DISCREPANCIES BEFORE STARTING WORK.
2. ALL CEILING MOUNTED ITEMS ARE TO BE CENTERED IN CEILING TILES U.N.O.
3. SPRINKLER HEAD LAYOUT IS APPROXIMATE AND NOT ALL HEADS MAY BE SHOWN. COORDINATE w/ SPRINKLER DWGS AND NOTIFY ARCHITECT OF ANY DISCREPANCIES BEFORE STARTING WORK.
4. PROVIDE WHITE GROMMET TRIM @ ALL SUPPORT CABLE &/or WIRING PENETRATIONS FOR SUSPENDED ELEMENTS.
5. EXISTING CEILING HEIGHT 9'-0". TO COORDINATE WITH MEP ENGINEER FOR REQUIRED CLEARANCE FOR DIFFUSERS, DUCTWORK, LIGHT FIXTURES, ETC.

REFLECTED CEILING PLAN LEGEND:

- NEW GYPSUM BOARD SOFFIT OR GYPSUM BOARD CEILING
- NEW CEILING GRID
- 2X2 CEILING LIGHT. COORDINATE w/ ELECTRICAL DWGS
- NEW CEILING MOUNTED HVAC SUPPLY DIFFUSER COORDINATE w/ MECHANICAL DWGS
- NEW CEILING MOUNTED HVAC RETURN DIFFUSER. COORDINATE w/ MECHANICAL DWGS.
- RECESSED OR SURFACE MOUNTED FLUORESCENT LIGHT FIXTURE. COORDINATE w/ ELECTRICAL DWGS
- NEW WALL MOUNTED UP/DN. LIGHT FIXTURE COORDINATE w/ ELECTRICAL DWGS
- NEW CEILING MOUNTED LIGHT COORDINATE w/ ELECTRICAL DWGS

REFLECTED CEILING PLAN WORK NOTES:

- XXX — NOTES WITHOUT AN ARROW INDICATE AN ENTIRE SPACE/AREA.
- XXX — NOTES WITH AN ARROW(S) INDICATE SPECIFIC AREAS &/or ITEMS.
- RCP — CEILINGS
- RCP1 — 2'X2' ACT SYSTEM ALL ACT CEILINGS @ 9'-0" A.F.F. U.N.O.
- RCP2 — GWB CEILING @ 9'-0", EPOXY PAINTED

KEY PLAN
Scale: N.T.S.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

REFLECTED CEILING PLAN - BUILDING 3

Project Number. 6356

Drawing No.

A601

Sheet of

1 A700 INTERIOR ELEVATIONS- WOMEN'S LATRINE (147)

Scale: 1/4" = 1'-0"

2 A700 INTERIOR ELEVATIONS- MEN'S LATRINE (146)

Scale: 1/4" = 1'-0"

3 A700 FAMILY RR (148)

Scale: 1/4" = 1'-0"

4 A700 WOMEN'S LATRINE (128)

Scale: 1/4" = 1'-0"

5 A700 MEN'S SUPPORT LATRINE (129)

Scale: 1/4" = 1'-0"

MATERIALS:

CEILING, SUSPENDED
- (95A) LAY-IN TILE
- (95B) 5/8" TYPE 'X' GYP. BD W/CONCEALED SUSPENSION SYSTEM
- (95C) GYPSUM BOARD, 5/8" TYPE 'X' GYP. BD

FLOOR FINISH
- (96L) EPOXY FLOOR FINISH SW CVII DECORATIVE MOSAIC

WALL FINISH
- (97A) TILE, CERAMIC OR PORCELAIN - WOOD DALTILE ACACIA VALLEY, (AV13), 9" x 36"
- (97B) TILE, CERAMIC OR PORCELAIN - WHITE BESTILE JAZZMAN 4" x 16"
- (97D) PAINT

BASE
- (98F) EPOXY COVE

BUILDING 1 - ROOM FINISH SCHEDULE

MARK	ROOM NAME	FLOOR	BASE	WALLS	CEILING MATL	CEILING HEIGHT	REMARKS	MARK
BUILDING 1								
121	STORAGE CLOSET	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING	TO INCLUDE METAL SHELVING	121
128	WOMEN'S LATRINE	96L	98F	97A, 97D	95C	MATCH EXISTING	--	128
129	MEN'S LATRINE	96L	98F	97A, 97D	95C	MATCH EXISTING	--	129
146	MEN'S LATRINE	96L	98F	97A, 97B, 97D	95C	MATCH EXISTING	--	146
147	WOMEN'S LATRINE	96L	98F	97A, 97B, 97D	95C	MATCH EXISTING	--	147
148	FAMILY RR	96L	98F	97A, 97D	95C	MATCH EXISTING	--	148
	CORRIDOR	MATCH EXISTING	MATCH EXISTING	MATCH EXISTING	95A	MATCH EXISTING	--	

TOILET ACCESSORY SCHEDULE

1	GRAB BAR BOBRICK #B6806 SERIES
2	SHOWER CURTAIN & ROD BOBRICK B6107-36 & B202-2 & B240-1
3	PAPER TOWEL DISPENSER
4A	MIRROR BOBRICK #B165
4B	A.D.A TILT MIRROR BOBRICK #B294
5	HAND DRYER XLERATOR
6	LOCKERS: 18" x 18" x 72" METAL LOCKERS. POWDERCOAT FINISH COLOR TBD
7	TOILET PAPER DISPENSER BOBRICK #B4388
8	ROBE HOOK- DOUBLE BOBRICK #B672

CONTRACTOR TO FURNISH & INSTALL FRT WOOD BLOCKING FOR ALL TOILET ACCESSORIES PER MANUFACTURER'S REQUIREMENTS.

NOTE: REFER TO A701 FOR TYPICAL FIXTURE AND ACCESSORY MOUNTING HEIGHTS.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

DAVID A. DESCIANO No. 2152 REGISTERED ARCHITECT

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

INTERIOR ELEVATIONS - BUILDING 1

Project Number. 6356

Drawing No.

A700

Sheet of

1 / A700 INTERIOR ELEVATIONS- WOMEN'S LATRINE (321)

Scale: 1/4" = 1'-0"

2 / A700 INTERIOR ELEVATIONS- MEN'S LATRINE (318)

Scale: 1/4" = 1'-0"

NOTE: REFER TO A700 FOR TOILET ACCESSORY SCHEDULE

6 / A301 TYPICAL H.C. TOILET STALL & LAVATORY

Scale: 1/4" = 1'-0"

BUILDING 3 - ROOM FINISH SCHEDULE								
MARK	ROOM NAME	FLOOR	BASE	WALLS	CEILING MATL	CEILING HEIGHT	REMARKS	MARK
BUILDING 3								
321	WOMEN'S LATRINE	96L	98F	97A, 97B, 97D,	95C	MATCH EXISTING	--	321
318	MEN'S LATRINE	96L	98F	97A, 97B, 97D	95C	MATCH EXISTING	--	318
	IT CLOSET	96D	98B	97D	95A	MATCH EXISTING	AREA TO BE PROVIDED W/ COOLING. RE. MEP	

MATERIALS:

CEILING, SUSPENDED
- (95A) LAY-IN TILE
- (95B) 5/8" TYPE 'X' GYP. BD W/CONCEALED SUSPENSION SYSTEM
- (95C) GYPSUM BOARD, 5/8" TYPE 'X' GYP. BD

FLOOR FINISH
- (96D) VCT
- (96L) EPOXY FLOOR FINISH

WALL FINISH
- (97A) TILE, CERAMIC OR PORCELAIN- WOOD
- (97B) TILE, CERAMIC OR PORCELAIN- WHITE
- (97D) PAINT, COLOR TBD
- (97E) TUB/SHOWER ENCLOSURE PANEL

BASE
- (98B) VINYL
- (98F) EPOXY COVE

7 / A301 TYPICAL H.C. SHOWER

Scale: 1/4" = 1'-0"

7 / A301 TYPICAL H.C. SHOWER

Scale: 1/4" = 1'-0"

8 / A301 TYPICAL FIXTURE & ACCESSORY MOUNTING HEIGHTS - ADULTS

Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction of buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL

Checked by RJJ

Revised on

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB ARCHITECTS

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents

INTERIOR ELEVATIONS - BUILDING 3

Project Number. 6356

Drawing No.

A701

Sheet of

DOOR & FRAME SCHEDULE

MARK	DOOR SIZE	DOOR TYPE	DOOR MATL	FRAME DEPTH	FRAME TYPE	FRAME MATL	DETAIL HEAD	DETAIL JAMB	DETAIL SILL	DETAIL MULL	REQUIRED FIRE RATING	HARDWARE	REMARKS	MARK
BUILDING 1														
146A	3'-0" x 6'-8" x 1 3/4	1	HM	8 5/8"	1	MTL	3/A910	4/A910	7/A910	--	--	HARDWARE SET #1	--	146A
147A	3'-0" x 6'-8" x 1 3/4	1	HM	8 5/8"	1	MTL	3/A910	4/A910	7/A910	--	--	HARDWARE SET #1	--	147A
148A	3'-0" x 6'-8" x 1 3/4	1	HM	8 5/8"	1	MTL	3/A910	4/A910	7/A910	--	--	HARDWARE SET #2	--	148A
128A	3'-0" x 6'-8" x 1 3/4	1	HM	8 5/8"	1	MTL	3/A910	4/A910	7/A910	--	--	HARDWARE SET #1	--	128A
129A	3'-0" x 6'-8" x 1 3/4	1	HM	8 5/8"	1	MTL	3/A910	4/A910	7/A910	--	--	HARDWARE SET #1	--	129A
BUILDING 3														
318A	3'-0" x 6'-8" x 1 3/4	1	HM	8 5/8"	1	MTL	3/A910	4/A910	7/A910	--	--	HARDWARE SET #1	--	318A
318B	3'-0" x 6'-8" x 1 3/4	1	HM	8 5/8"	1	MTL	3/A910	4/A910	7/A910	--	--	HARDWARE SET #1	--	318B
321A	3'-0" x 6'-8" x 1 3/4	1	HM	8 5/8"	1	MTL	3/A910	4/A910	7/A910	--	--	HARDWARE SET #1	--	321A
321B	3'-0" x 6'-8" x 1 3/4	1	HM	8 5/8"	1	MTL	3/A910	4/A910	7/A910	--	--	HARDWARE SET #1	--	321B

REMARK NOTES:

1. PROVIDE SURFACE MOUNTED CLOSER ON EXISTING DOOR.
2. HARDWARE BY DOOR MANUFACTURER & /OR SUPPLIER U.N.O.
3. FIELD VERIFY HEIGHT &/OR WIDTH OF MASONRY OPENING.
4. PROVIDE SIGNAGE MEETING ADA REQUIREMENTS MOUNTED @ 48" MIN. & 60" MAX. A.F.F. ON WALL ADJACENT TO LATCH SIDE OF DOOR.
5. WHERE EXISTING DOOR IS BEING REPLACED WITH IN EXISTING FRAME TO REMAIN. VIF FINAL DOOR DIMENSIONS.

HARDWARE SET:

HARDWARE SET #1

1 EA CONTINUOUS HINGE	CFM883SLF-HDI		(HC-1) PEMKO
1 EA PULL PLATE	4" x 16"	US32D	(PP-1) ROCKWOOD
1 EA PUSH PLATE	4" x 16"	US32D	(PP-2) ROCKWOOD
1 EA SURFACE CLOSER	4011H	AL	(CL-4) LCN CLOSER
1 EA KICK PLATE	K1050 8" x 34" CSK	US32D	(KP-2) ROCKWOOD
1 EA DOOR STOP	471 EXP	US32D	(ST-1) ROCKWOOD
3 EA SILENCER	Q146		(SI-1) IVES

HARDWARE SET #2

		BHMA 626	(F76) SARGENT
1 EA SURFACE CLOSER	4011H	AL	(CL-4) LCN CLOSER
1 EA KICK PLATE	K1050 8" x 34" CSK	US32D	(KP-2) ROCKWOOD
1 EA DOOR STOP	471 EXP	US32D	(ST-1) ROCKWOOD
3 EA SILENCER	Q146		(SI-1) IVES

GENERAL NOTES:

GENERAL:

1. FOR DOOR HEAD, JAMB, & THRESHOLD DETAILS RE: A910 UNO.
2. WINDOW DIMENSIONS SHOWN ARE ROUGH OPENING &/or MASONRY OPENINGS.
3. REFER TO SPECIFICATIONS FOR HARDWARE SETS.

DOORS:

1. INTERIOR DOOR FINISHES:
   A. HOLLOW METAL: FACTORY PRIMED FOR FIELD PAINTING UNO
2. PRE-ASSEMBLIED FRAMES FULLY WELDED KNOCK DOWN FRAMES MEETING THE REQUIRED UL FIRE RATINGS REQUIRED ARE ACCEPTABLE FOR USE ON THIS PROJECT IF APPROVED PRIOR BY ARCHITECT IN WRITING.
3. FRAME PROFILE DEPTH DIMENSION GIVEN INCLUDES THE THROAT DIMENSION PLUS 1" [1/2" RETURNS BOTH SIDES] UNO RE: 1/A920

HARDWARE:

1. HARDWARE & ACCESSORY LIST SCHEDULE ESTABLISHES GENERAL SCOPE REQUIREMENTS. CONTRACTOR, SUPPLIERS &/or MANUFACTURERS TO PROVIDE ALL NECESSARY ACCESSORIES, SCREWS, SEX BOLTS, STRIKES, COVER PLATES, TOOLS, ETC. FOR A COMPLETED INSTALLATION OF HARDWARE FOR A FULLY FUNCTIONAL SYSTEM FOR THE INTENDED USE.
2. TYPICAL HARDWARE FINISH REQUIREMENTS FOR INTERIOR DOORS:
   HARDWARE FINISH: US4
   KICK PLATES METAL FINISH: US4
   WASH & TOILET ROOMS: US4

   HARDWARE FOR STOREFRONT DOORS PROVIDED BY CURTAINWALL/STOREFRONT MFG. FINISH TO MATCH ADJACENT FRAMES.

   CLOSERS, THRESHOLDS, ETC TO APPROXIMATE DOOR HARDWARE FINISH NOTED ABOVE.

   CYLINDER FINISH IS TO MATCH FINISH OF ITEM IN WHICH CYLINDER IS INSTALLED IN UNO. (IE. STOREFRONT FRAME COLOR, EXIT DEVICE FINISH, LOCKSET FINISH, etc.
3. PROVIDE LEVER HANDLES @ ALL LATCHSETS, LOCKSETS, PANIC DEVICES, DUMMY LATCHSETS TYPICAL UNO.
4. PROVIDE DOOR SILENCERS @ ALL DOORS
   SINGLE DOORS PROVIDE 3
5. PROVIDE ALUMINUM THRESHOLDS BY DOOR(S) WIDTH WHERE SHOWN ON PLANS, IN SILL DETAILS, &/or WHERE NOTED. TYPICAL.

1 A910 TYP. HM HEAD @ STUD
Scale: 1 1/2" = 1'-0" (SECTION DETAIL)

3 A910 TYP. HM HEAD @ CMU
Scale: 1 1/2" = 1'-0" (SECTION DETAIL)

5 A910 DOOR TYPES
Scale: 1/4" = 1'-0"

6 A910 FRAME TYPES
Scale: 1/4" = 1'-0"

2 A910 TYP. HM JAMB @ STUD
Scale: 1 1/2" = 1'-0" (PLAN DETAIL)

4 A910 TYP. HM JAMB @ CMU
Scale: 1 1/2" = 1'-0" (PLAN DETAIL)

7 A910 TYP. INTERIOR DOOR SILLS
Scale: 1 1/2" = 1'-0" (SECTION DETAILS)

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by TPL
Checked by RJJ
Revised on

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB ARCHITECTS
Architecture · Project Management · Interior Design

Project
RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

CONSTRUCTION DOCUMENTS

Issued On 20 MARCH 2018

Sheet Contents
DOOR & FRAME SCHEDULE

Project Number. 6356

Drawing No.
A910

Sheet of

DUCTWORK PLAN GENERAL NOTES

1. UOI, DUCTWORK SHALL BE MOUNTED AS HIGH AS POSSIBLE, EXCEPT THAT DUCTWORK HEIGHT SHALL BE ADJUSTED AS NECESSARY FOR THE PROPER INSTALLATION OF EQUIPMENT, PIPING, AND CONDUIT
2. UOI, FLEXIBLE DUCTS ARE ALLOWED ONLY AT CONNECTIONS TO DIFFUSERS AND GRILLES. FLEXIBLE DUCTS SHALL BE MAXIMUM 5'–0" LONG, SHALL BE LOCATED ABOVE ACCESSIBLE CEILINGS ONLY, AND SHALL BE SUSPENDED OFF OF THE CEILING.
3. WHERE BRANCH DUCT SIZES TO DIFFUSERS AND GRILLES ARE NOT INDICATED, SEE THE BRANCH DUCT COLUMN OF THE DIFFUSER AND GRILLE SCHEDULE
4. WHERE VOLUME DAMPERS ARE INACCESSIBLE, PROVIDE WORM GEAR DRIVE AND CABLE ASSEMBLIES SIMILAR TO METROPOLITAN AIR TECHNOLOGIES ROTOTWIST MODEL RT–200/250 SERIES WITH MODEL RT–CCR CEILING CAP. TO THE GREATEST EXTENT POSSIBLE, GROUP CEILING CAPS IN SPACES SUCH AS STORAGE ROOMS, CLOSETS, JANITORS ROOMS, MECHANICAL/ELECTRICAL ROOMS, ETC.
5. DUCTWORK VISIBLE THROUGH THE FACE OF DIFFUSERS, GRILLES, AND LOUVERS SHALL BE PAINTED BLACK
6. EXPOSED ROUND DUCTWORK SHALL BE SPIRAL LOCKSEAM TYPE
7. DUCTWORK DIMENSIONS INDICATED ARE INSIDE CLEAR DIMENSIONS

PIPING PLAN GENERAL NOTES

1. UOI, BRANCH PIPES TO TERMINAL UNITS SHALL BE AS FOLLOWS:

GPM	BRANCH PIPES	GPM	BRANCH PIPES
0.0 TO 3.0	3/4"	19.1 TO 40.0	2"
3.1 TO 7.0	1"	40.1 TO 70.0	2–1/2"
7.1 TO 12.0	1–1/4"	70.1 TO 120.0	3"
12.1 TO 19.0	1–1/2"	120.1 TO 250.0	4"

2. GRAVITY DRAIN COOLING COIL CONDENSATE PIPING SHALL BE PITCHED DOWNWARD TO DRAIN AT MINIMUM 1/4" PER FOOT. COOLING COIL CONDENSATE PIPING WITHIN THE BUILDING SHALL TERMINATE ABOVE AN INDIRECT WASTE RECEIVER, WITH A MINIMUM 2" AIR GAP ABOVE THE FLOOD RIM OF THE RECEIVER. JANITORS SINKS AND LAUNDRY TUBS MAY BE USED AS RECEIVERS. WHERE THERE ARE NO JANITORS SINKS OR LAUNDRY TUBS WITHIN THE VICINITY FOR PROPER GRAVITY DRAINAGE, PROVIDE TRAPPED, VENTED, AND PRIMED INDIRECT WASTE RECEIVERS CONNECTED TO THE BUILDING PLUMBING SYSTEM AS REQUIRED.

HVAC DEMOLITION GENERAL NOTES

1. ALL DEMOLITION WORK PERFORMED SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE NATIONAL, STATE AND LOCAL CODES, LAWS AND ORDINANCES.
2. THIS CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND FILING ALL PLANS, SPECIFICATIONS AND OTHER DOCUMENTS, PAY ALL REQUISITE FEES AND SECURE ALL PERMITS, INSPECTIONS AND APPROVALS NECESSARY FOR THE LEGAL INSTALLATION AND OPERATION OF THE SYSTEM AND/OR EQUIPMENT FURNISHED UNDER THIS SECTION OF THE SPECIFICATIONS.
3. INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, APPLIANCES AND SERVICES NECESSARY TO REMOVE AND DISPOSE OF ALL EXISTING HVAC SYSTEM
4. PRIOR TO SUBMITTING BID, THE CONTRACTOR SHALL VISIT THE PROJECT SITE TO BECOME FAMILIAR WITH ALL EXISTING CONDITIONS AND TO DETERMINE THE EXTENT OF WORK TO REMOVE THE EXISTING HVAC SYSTEM COMPLETELY. IF DISCREPANCIES EXIST BETWEEN DRAWINGS AND/OR SITE CONDITIONS, THE HVAC CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE OWNER PRIOR TO SIGNING OF CONTRACT. REQUESTS FOR COMPENSATION FOR EXTRA WORK, WHICH WOULD HAVE BEEN EVIDENT BY COMPLIANCE WITH THE PREVIOUS STATEMENT, WILL NOT BE CONSIDERED.
5. EQUIPMENT AND DUCTWORK LAYOUTS ON THIS DRAWING ARE DIAGRAMMATIC ONLY AND SHALL NOT BE CONSTRUED AS BEING 100% ACCURATE. WHERE ITEMS ARE SHOWN TO BE DEMOLISHED OR ALTERED ON THESE PLANS THAT ARE NOT REPRESENTED ACCURATELY, THE DEMOLITION SUBCONTRACTOR SHALL ISSUE FORMAL RFI'S AS REQUIRED PRIOR TO COMPLETING THE REQUIRED WORK.
6. REFER TO ARCHITECTURAL DEMOLITION DRAWINGS FOR DEMOLITION WORK. CONTRACTOR SHALL COORDINATE WITH CONSTRUCTION PHASE PRIOR TO REMOVING ANY PIECE OF EQUIPMENT OR PIPING.
7. WHERE VOIDS OR OPENINGS IN THE DUCTWORK ARE FOUND AND ARE NOT SPECIFICALLY SHOWN TO BE CAPPED OR PATCHED, IT SHALL BE THE INTENT OF THIS DEMOLITION PLAN THAT CAPPING AND PATCHING IS COMPLETED TO PROVIDE A CLOSED/SEALED SUPPLY AIR SYSTEM TO ACCOMMODATE THE NEW WORK.
8. DEMOLITION OF ALL OTHER COMPONENTS SHALL INCLUDE PLACEMENT INTO CONTAINER, REMOVAL FROM SITE AND PROPER DISPOSAL OF, WITH PERMITS AND FEES INCLUDED. REFER TO NEW FLOOR PLANS FOR EXISTING SYSTEMS BEING USED UNDER THE NEW CONSTRUCTION. ALL SYSTEMS FOUND TO BE ABANDONED ARE TO BE REMOVED.
9. COORDINATE ALL SHUT–DOWNS, TIE–INS, ETC., WITH THE G.C. ELECTRICAL MAKE–SAFE OF HVAC EQUIPMENT REQUIRING DEMOLITION SHALL BE COMPLETED BY THE ELECTRICAL SUBCONTRACTOR.
10. DEMOLITION SUBCONTRACTOR MUST PROTECT EXISTING SLAB, WALL, FENCING AND BUILDING STRUCTURE DURING DEMOLITION PHASE. DAMAGE TO EXISTING STRUCTURE SHALL BE REPAIRED AT DEMOLITION SUBCONTRACTORS EXPENSE.
11. PRIOR TO START OF DEMOLITION WORK, THE CONTRACTOR SHALL COORDINATE WITH THE OWNER TO DETERMINE IF ANY EQUIPMENT CALLED TO BE DISPOSED ON THE PLAN SHALL BE RETURNED TO THE OWNER AND STORED PER OWNERS REQUEST.

ABBREVIATIONS

ABBREVIATION	DESCRIPTION
AD	ACCESS DOOR
AFF	ABOVE FINISHED FLOOR
AP	ACCESS PANEL
AH	AIR HANDLER
AHJ	AUTHORITY HAVING JURISDICTION
AHU	AIR HANDLING UNIT
APD	AIR PRESSURE DROP
AS	AIR SEPARATOR
ATC	AUTOMATIC TEMPERATURE CONTROL
AWT	AVERAGE WATER TEMPERATURE
B	BOILER
BHP	BREAK HORSEPOWER
BTU	BRITISH THERMAL UNIT
BTUH	BTU/HOUR
BMS	BUILDING MANAGEMENT SYSTEM
CAP	CAPACITY
CFM	CUBIC FEET PER MINUTE
CH	CHILLER
CNV	CONVECTOR
COP	COEFFICIENT OF PERFORMANCE
CRD	CEILING RADIATION DAMPER
CT	COOLING TOWER
CU	CONDENSING UNIT
CUH	CABINET UNIT HEATER
dB	DECIBELS
DAH	DUCTLESS AIR HANDLER
DHP	DUCTLESS HEAT PUMP
DN	DOWN
DX	DIRECT EXPANSION
EAT	ENTERING AIR TEMPERATURE (DRY BULB)
EBB	ELECTRIC BASEBOARD
E.C.	ELECTRICAL CONTRACTOR
EDB	ENTERING DRY BULB TEMPERATURE
EER	ENERGY EFFICIENCY RATIO
EF	EXHAUST FAN
EH	ELECTRIC HEATER
ESP	EXTERNAL STATIC PRESSURE
ET	EXPANSION TANK
ETR	EXISTING TO REMAIN
EWB	ENTERING WET BULB TEMPERATURE
EWT	ENTERING WATER TEMPERATURE
°F	DEGREES FAHRENHEIT
FD	FIRE DAMPER
FN	FURNACE
FSD	COMBINATION FIRE/SMOKE DAMPER
FT	FEET
FT WG	FEET WATER GAUGE
FLA	FULL LOAD AMPS
FPM	FEET PER MINUTE
G.C.	GENERAL CONTRACTOR
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
HEPA	HIGH EFFICIENCY PARTICULATE ARRESTANCE
HP	HORSEPOWER
HSPF	HEATING SEASON PERFORMANCE FACTOR
HW	HOT WATER
IN	INCHES
IPLV	INTEGRATED PART LOAD VALUE
IN WG	INCHES WATER GAUGE
KW	KILOWATTS
L	LOUVER
LAT	LEAVING AIR TEMPERATURE
LDB	LEAVING DRY BULB
LWB	LEAVING WET BULB
LWT	LEAVING WATER TEMPERATURE
MAX	MAXIMUM
MBH	THOUSANDS OF BTU / HOUR
M.C.	MECHANICAL CONTRACTOR
MCA	MINIMUM CIRCUIT AMPACITY
MIN	MINIMUM
MOP	MAXIMUM OVERCURRENT PROTECTION
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
NTS	NOT TO SCALE
OA	OUTSIDE AIR
OAT	OUTSIDE AIR TEMPERATURE (DRY BULB)
ODB	OUTSIDE DRY BULB TEMPERATURE
OWB	OUTSIDE WET BULB TEMPERATURE
P	PUMP
PH	PHASE
PRV	PRESSURE REDUCING VALVE
PSIG	POUNDS PER SQUARE INCH GAUGE
QTY	QUANTITY
RE	REMOVE EXISTING
RF	RETURN FAN
RPM	REVOLUTIONS PER MINUTE
RPZB	REDUCED PRESSURE ZONE BACKFLOW PREVENTER
RTU	ROOFTOP UNIT
SD	SMOKE DAMPER
SEER	SEASONAL ENERGY EFFICIENCY RATIO
SF	SUPPLY FAN
SP	STATIC PRESSURE
SPD	STATIC PRESSURE DROP
SST	SATURATED SUCTION PRESSURE
TF	TRANSFER FAN
TSP	TOTAL STATIC PRESSURE
TYP	TYPICAL
UH	UNIT HEATER
UOI	UNLESS OTHERWISE INDICATED
VAV	VARIABLE AIR VOLUME
VD	VOLUME DAMPER
VFD	VARIABLE FREQUENCY DRIVE
VRF	VARIABLE REFRIGERANT FLOW
WPD	WATER PRESSURE DROP

MECHANICAL LEGEND

SYMBOL	DESCRIPTION
	DUCTWORK (DOUBLE LINE)
	DUCTWORK WITH ACOUSTICAL LINING (DOUBLE LINE)
	DUCTWORK (SINGLE LINE)
	DUCTWORK WITH ACOUSTICAL LINING (SINGLE LINE)
	FLEXIBLE DUCTWORK
	DUCTWORK, PIPING AND EQUIPMENT TO BE DEMOLISHED
	RECTANGULAR/ROUND SUPPLY AIR DUCTWORK UP
	RECTANGULAR/ROUND RETURN AIR DUCTWORK UP
	RECTANGULAR/ROUND EXHAUST AIR DUCTWORK UP
	RECTANGULAR/ROUND SUPPLY AIR DUCTWORK DOWN
	RECTANGULAR/ROUND RETURN AIR DUCTWORK DOWN
	RECTANGULAR/ROUND EXHAUST AIR DUCTWORK DOWN
	VOLUME DAMPER
	CONTROL DAMPER
	FIRE DAMPER OR CEILING RADIATION DAMPER
	SMOKE DAMPER
	COMBINATION FIRE/SMOKE DAMPER
	GRAVITY BACKDRAFT DAMPER
HWS	HOT WATER SUPPLY PIPING
HWR	HOT WATER RETURN PIPING
	ELBOW UP
	ELBOW DOWN
	TEE DOWN
	TEE UP
	PIPE GUIDE
	PIPE ANCHOR
	FLOW DIRECTION
	PIPE CLEANOUT
	CONNECT TO EXISTING
	AIR ENTERING OPENING
	AIR LEAVING OPENING
T	THERMOSTAT OR TEMPERATURE SENSOR
	CONTROL CONNECTION

TAG LEGEND

EQUIPMENT (REQUIRING POWER)	– / –	EQUIPMENT DESIGNATION NUMBER
EQUIPMENT (NON–POWERED)	– / –	EQUIPMENT DESIGNATION NUMBER
REGISTERS, GRILLES & DIFFUSERS	T– / – / ––	TYPICAL FOR # DESIGNATION BALANCE TO CFM INDICATED
SECTION CALL–OUT	# / #–#	DESIGNATION DRAWING REFERENCE

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by LDC

Checked by R□□

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com

100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

MECHANICAL LEGENDS, ABBREVIATIONS AND NOTES

Project Number.

Drawing No.

M000

Sheet of

DIFFUSER AND GRILLE SCHEDULE

GENERAL	PHYSICAL		REMARKS		
TAG	BLOW PATTERN	MANUFACTURER MODEL	TYPE	FEATURES	INSTALL
S2W	2W	PRICE MODEL AMX	1	1 2	1 2 3
S3W	3W	PRICE MODEL AMX	1	1 2	1 2 3
S4W	4W	PRICE MODEL AMX	1	1 2	1 2 3
R-1	RETURN	PRICE MODEL 635	2	1	1 2 3

1. LOUVERED HIGH INDUCTION DIRECTIONAL CEILING DIFFUSER, SQUARE/ RECTANGULAR NECK & FACE, ALUMINUM CONSTRUCTION, WHITE FINISH.
2. RETURN/EXHAUST GRILLE, 45° FIXED BLADES ON 1/2" CENTERS, BLADES PARALLEL TO LONG DIMENSION, ALUMINUM, WHITE

1. CEILING MOUNT, PROVIDE LAY-IN T-BAR PANEL FOR LOUVERED DIFFUSERS, REGISTERS AND GRILLES IN ACT CEILINGS, REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR MOUNTING TYPE
2. INSULATED BACK PAN

1. REFER TO ARCHITECTURAL DRAWINGS TO CONFIRM MOUNTING TYPE
2. PROVIDE A DUCT MOUNTED VOLUME DAMPER
   EXCEPTIONS:
   - TRANSFER AIR APPLICATIONS (GRILLE IS NOT CONNECTED BY A DUCTWORK SYSTEM TO A FAN)
   - EXHAUST AND RETURN GRILLES WHERE ONLY ONE GRILLE SERVES THE FAN/AIR HANDLING SYSTEM
3. REFER DETAIL

PATTERN LEGEND

TAG LEGEND

FAN SCHEDULE

GENERAL			PERFORMANCE					ELECTRICAL				PHYSICAL		REMARKS			
TAG	LOCATION	SERVICE	CFM	ESP (IN WG)	FAN RPM	BHP	SONES	FLA	HP	VOLTAGE	PHASE	WEIGHT (LBS)	MANUFACTURER MODEL	TYPE	RATINGS	FEATURES	INSTALL
EF-2	BUILDING 1 ROOF	TOILET EXHAUST	1025	.50	1505	–	8.5	5.8	1/4	115	1	63.0	GREENHECK G-103-A	1	–	1 2 3 4 5	1
EF-4	BUILDING 3 SIDEWALL	TOILET EXHAUST	975	.75	1591	–	9.6	8.5	1/4	115	1	58.0	GREENHECK CW-101-A	2	–	2 3 4 5	1
EF-9	BUILDING 1 ROOF	JANITOR CLOSET EXHAUST	75 –	.25	1382	–	2.8	–	1/60	115	1	33.0	GREENHECK G-060-D	1	–	1 2 3 4 5	1
EF-10	BUILDING 1 ROOF	TOILET EXHAUST	250	.25	1478	–	4.1	–	1/30	115	1	34.0	GREENHECK G-070-D	1	–	1 2 3 4 5	1

1. CENTRIFUGAL ROOF EXHAUSTER, DOWNBLAST, DIRECT DRIVE
2. CENTRIFUGAL WALL EXHAUSTER, DIRECT DRIVE

1. AIR PERFORMANCE CERTIFIED IN ACCORDANCE TO AMCA 211
2. SOUND PERFORMANCE CERTIFIED IN ACCORDANCE TO AMCA 311

1. ROOF CURB WITH RUBBER SEAL
2. NON-FUSED DISCONNECT SWITCH
3. GRAVITY BACKDRAFT DAMPER
4. BIRDSCREEN
5. UNIT MOUNTED SPEED CONTROLLER

1. INSTALL PER MANUFACTURERS INSTRUCTIONS

HYDRONIC FIN TUBE SCHEDULE

GENERAL		PERF.	PHYSICAL										REMARKS			
TAG	LOCATION	BTUH PER FOOT	ENCLOSURE WIDTH (IN)	ENCLOSURE HEIGHT (IN)	MOUNTING HEIGHT (IN)	TIERS NUMBER	TIERS CENTERS (IN)	ELEMENT TUBE SIZE (IN)	ELEMENT FIN WIDTH (IN)	ELEMENT FIN HEIGHT (IN)	ELEMENT FINS PER FT	MANUFACTURER MODEL	TYPE	RATINGS	FEATURES	INSTALL
FTR-1	FAMILY RR-148	630	3-1/8"	10-11/16"	–	1.0	–	3/4"	2-3/4"	2-1/2"	60	STERLING LB2	1	1	–	1 2

1. LIGHT COMMERCIAL SLOPE TOP

1. 170°F AVERAGE WATER TEMPERATURE

1. COPPER TUBE, 0.010" THICK ALUMINUM FINS
2. 16 GAUGE STEEL ENCLOSURE WITH FULL BACK PLATE
3. BAKED ENAMEL FINISH, COLOR SELECTABLE BY ARCHITECT

1. SEE DETAIL ON THIS DRAWING
2. INSTALL PER MANUFACTURERS INSTRUCTIONS

SYMBOL DESCRIPTION

CABINET UNIT HEATER SCHEDULE

GENERAL		PERFORMANCE						ELECTRICAL				PHYSICAL	REMARKS			
TAG	LOCATION	MBH	GPM	WPD (FT WG)	LAT (°F)	CFM	FAN SPEED	WATTS	HP	VOLTAGE	PHASE	MANUFACTURER MODEL	TYPE	RATINGS	FEATURES	INSTALL
CUH-1	WOMAN'S LATRINE 147	11.8	.50	.02	119.0	185	LOW	–	1/15	115	1	STERLING RC-1200-02	1	1	1 2 3	1 2
CUH-2	WOMAN'S LATRINE 147	11.8	.50	.02	119.0	185	LOW	–	1/15	115	1	STERLING RC-1200-02	1	1	1 2 3	1 2
ADD ALTERNATE #1 CUH-3	CORRIDOR	16.2	1.50	.15	125.0	230	LOW	–	1/15	115	1	STERLING F-1000-02	2	1	1 2 3	1 2
CUH-4	MEN'S LATRINE 146	11.8	.50	.02	119.0	185	LOW	–	1/15	115	1	STERLING RC-1200-02	1	1	1 2 3	1 2
CUH-5	MEN'S LATRINE 146	11.8	.50	.02	119.0	185	LOW	–	1/15	115	1	STERLING RC-1200-02	1	1	1 2 3	1 2

1. RECESSED CEILING, BOTTOM INLET GRILLE, BOTTOM DISCHARGE GRILLE
2. FLOOR MODEL, BOTTOM INLET GRILLE, TOP DISCHARGE GRILLE

1. 180° EWT, 160°F LWT, 60°F EAT

1. EXTRUDED ALUMINUM GRILLE INLET & OUTLET
2. BAKED ENAMEL FINISH, COLOR SELECTABLE BY ARCHITECT
3. DPST DISCONNECT SWITCH

1. SEE DETAIL ON THIS DRAWING
2. INSTALL PER MANUFACTURERS INSTRUCTIONS

DUCTLESS SPLIT AIR CONDITIONING SYSTEM AIR HANDLER SCHEDULE

GENERAL			PERFORMANCE							ELECTRICAL				PHYSICAL	REMARKS			
TAG	LOCATION	MATCHED COND. UNIT	NOMINAL TONS	TOTAL COOLING MBH	TOTAL HEATING MBH	FAN CFM	FAN ESP (IN WG)	FAN SPEED	SOUND PRESSURE DBA	MCA	MOP	VOLTAGE	PHASE	MANUFACTURER MODEL	TYPE	RATINGS	FEATURES	INSTALL
AH-1	IT SERVER ROOM	CU-1	1.0	12,000	11,800	380	–	HIGH	42	0.2	15.0	208	1	CARRIER 40MAQB12-3	1	1	1 2 3	1 2 3
AH-2	MEN'S LATRINE 318	CU-2	6.0	76,800	85,200	2,048	–	HIGH	45	3.80	15.0	208	1	TRANE 4TVA0076B100N	2	1	1 2 3	1 2 3
AH-3	WOMAN'S LATRINE 321	CU-3	6.0	76,800	85,200	2,048	–	HIGH	45	3.80	15.0	208	1	TRANE 4TVA0076B100N	2	1	1 2 3	1 2 3

1. HIGH WALL MOUNTED UNIT
2. CONCEALED DUCTED UNIT

1. RATED PER AHRI

1. HARD WIRED WALL MOUNTED PROGRAMMABLE THERMOSTAT
2. BUILT-IN CONDENSATE PUMP
3. HARD WIRED CONTROLLER

1. REFRIGERANT PIPING, CONDENSATE PIPING, CONTROL WIRING AND CONDUIT, POWER WIRING AND CONDUIT, RELAYS AND OTHER DEVICES SHALL BE CONCEALED.. LOCATE DEVICES REQUIRING ACCESS IN ACCESSIBLE LOCATIONS. COORDINATE LOCATIONS WITH ARCHITECT AND PROVIDE ACESSPANELS WHERE REQUIRED.
2. AH-1, 2, & 3. THE DEDICATED THERMOSTAT SHALL BE SET TO MAINTAIN SPACE TEMPERATURE DETERMINED BY THE OWNER.
3. INDOOR UNIT POWERED BY OUTDOOR UNIT.

DUCTLESS SPLIT AIR CONDITIONING SYSTEM CONDENSING UNIT SCHEDULE

GENERAL			PERFORMANCE		ELECTRICAL				PHYSICAL		REMARKS			
TAG	LOCATION	MATCHED AIR HANDLER	NOMINAL TONS	EER	MCA	MOP	VOLTAGE	PHASE	WEIGHT (LBS)	MANUFACTURER MODEL	TYPE	RATINGS	FEATURES	INSTALL
CU-1	ROOF	SEE PLAN	1.0	12.5	9.0	15.0	208	1	91.50	CARRIER 38MAQB12R-3	1	1	1 2	1
CU-2	ROOF	SEE PLAN	12.0	10.8	52.6	70.0	208	3	646.0	TRANE 4TVH0144	2	1	1 2	1

1. SINGLE INDOOR UNIT HEAT PUMP SYSTEM (R-410A)
2. MULT-HEAD HEAT PUMP SYSTEM

1. COOLING OPERATION BASED ON AHRI CONDITIONS: 95°F ODB AND INDOOR: 80°F EDB, 67°F EWB

1. WIND BAFFLE (LOW AMBIENT COOLING DOWN TO 0 DEGREES)
2. DISCONNECT SWITCH

1. PROVIDE SPLIT SYSTEM REFRIGERANT PIPING BETWEEN AIR HANDLER AND MATCHED CONDENSING UNIT, SIZED AND CONFIGURED PER THE MANUFACTURER'S RECOMMENDATIONS, ROUTE PIPING CONCEALED TO THE GREATEST EXTENT POSSIBLE. SEAL ROOF PIPING PENETRATIONS WATERTIGHT.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by LDC

Checked by R

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.8500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

MECHANICAL SCHEDULES

Project Number.

Drawing No.

M001

Sheet of

BUILDING 1 - OVERALL KEY PLAN

Scale: 1/16" = 1'-0"

DEMOLITION PLAN LEGEND	
SYMBOL	DESCRIPTION
	EXISTING TO BE DEMOLISHED (SHOWN IN HEAVY DASHED LINES)
	EXISTING TO REMAIN (SHOWN IN LIGHT LINES)
ETR	EXISTING TO REMAIN AS INSTALLED.

MECHANICAL DEMOLITION KEYED NOTES:

1. REMOVE & DISCARD EXISTING ROOF MOUNTED EXHAUST FAN, DUCTWORK, AND ALL ASSOCIATED APPURTENANCES TO POINT INDICATED ON DRAWING.
2. REMOVE & DISCARD EXISTING PLENUM RETURN GRILLES.
3. REMOVE & DISCARD EXISTING TRANSFER DUCTWORK, HANGERS, AND ALL ASSOCIATED APPURTENANCES IN ITS ENTIRETY.
4. REMOVE & DISCARD EXISTING SUPPLY GRILLE, AND DUCTWORK TO THE POINT INDICATED ON DRAWING IN ITS ENTIRETY.

2 M100 ENLARGED LATRINES DUCTWORK DEMOLITION PART PLAN

Scale: 1/4" = 1'-0"

1 M100 ENLARGED LATRINES DUCTWORK DEMOLITION PART PLAN

Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by LDC

Checked by R

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.8205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 - DUCTWORK DEMOLITION PLAN

Project Number.

Drawing No.

MD100

Sheet of

BUILDING 1 - OVERALL KEY PLAN

Scale: 1/16" = 1'-0"

DEMOLITION PLAN LEGEND	
SYMBOL	DESCRIPTION
	EXISTING TO BE DEMOLISHED (SHOWN IN HEAVY DASHED LINES)
	EXISTING TO REMAIN (SHOWN IN LIGHT LINES)
ETR	EXISTING TO REMAIN AS INSTALLED.

MECHANICAL DEMOLITION KEYED NOTES:

1. REMOVE & DISCARD EXISTING CABINET UNIT HEATER, PIPING, CONTROL VALVES AND ALL ASSOCIATED APPURTENANCES TO POINT INDICATED ON DRAWINGS. REFER TO DRAWING M101 FOR MORE INFORMATION.
2. REMOVE AND DISCARD EXISTING FIN-TUBE RADIATION, PIPING AND CONTROL VALVES WHERE SHOWN ON DRAWING.
3. ADD ALT #1 – REMOVE & DISCARD EXISTING CABINET UNIT HEATER. EXISTING PIPING, CONTROL VALVES AND ALL OTHER ASSOCIATED APPURTENANCES SHALL REMAIN AS INSTALLED. REFER TO DRAWING M101 FOR MORE INFORMATION.

2 M100 ENLARGED LATRINES PIPING DEMOLITION PART PLAN

Scale: 1/4" = 1'-0"

1 M100 ENLARGED LATRINES PIPING DEMOLITION PART PLAN

Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by LDC

Checked by R□□

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.8500
F 401.228.8205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 - PIPING DEMOLITION PLAN

Project Number.

Drawing No.

MD101

Sheet of

BUILDING 3 - OVERALL KEY PLAN

Scale: 1/16" = 1'-0"

DEMOLITION PLAN LEGEND	
SYMBOL	DESCRIPTION
	EXISTING TO BE DEMOLISHED (SHOWN IN HEAVY DASHED LINES)
	EXISTING TO REMAIN (SHOWN IN LIGHT LINES)
ETR	EXISTING TO REMAIN AS INSTALLED.

MECHANICAL DEMOLITION KEYED NOTES:

1. REMOVE & DISCARD EXISTING SIDEWALL EXHAUST FAN, DUCTWORK, HANGERS, GRILLES AND ALL ASSOCIATED APPURTENANCES IN ITS ENTIRETY.
2. REMOVE EXISTING SUPPLY DUCTWORK, DIFFUSERS, HANGERS, AND ALL ASSOCIATED APPURTENANCES TO POINT INDICATED ON DRAWING.
3. REMOVE EXISTING RETURN DUCTWORK, GRILLES, HANGERS, AND ALL ASSOCIATED APPURTENANCES TO POINT INDICATED ON DRAWING.
4. CAREFULLY REMOVE & RELOCATE EXISTING THERMOSTAT. REFER TO RENOVATION PLAN ON DRAWING M100 FOR NEW LOCATION.
5. CAREFULLY REMOVE & RELOCATE EXISTING ATC CONTROL PANEL. REFER TO RENOVATION PLAN ON DRAWING M100 FOR NEW LOCATION.

1 / M101 ENLARGED LATRINES DEMOLITION PLAN

Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by LDC

Checked by R

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.8500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 - DUCTWORK DEMOLITION PLAN

Project Number.

Drawing No.

MD200

Sheet of

BUILDING 3 - OVERALL KEY PLAN

Scale: 1/16" = 1'-0"

DEMOLITION PLAN LEGEND	
SYMBOL	DESCRIPTION
	EXISTING TO BE DEMOLISHED (SHOWN IN HEAVY DASHED LINES)
	EXISTING TO REMAIN (SHOWN IN LIGHT LINES)
ETR	EXISTING TO REMAIN AS INSTALLED.

MECHANICAL DEMOLITION KEYED NOTES:

1. REMOVE AND DISPOSE EXISTING 3/4" CONDENSATE DROP TO SERVICE SINK REFER TO DRAWING M201 FOR MORE INFORMATION.

1 ENLARGED LATRINES RENOVATION PLAN

M103 Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by LDC

Checked by R

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 - PIPING DEMOLITION FLOOR PLAN

Project Number.

Drawing No.

MD201

Sheet of

BUILDING 1 - OVERALL KEY PLAN

Scale: 1/16" = 1'-0"

2 M102 ENLARGED LATRINES RENOVATION PLAN

Scale: 1/4" = 1'-0"

1 M102 ENLARGED LATRINES RENOVATION PLAN

Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by LDC

Checked by R□□

Revised on

B|E|R

BUILDING ENGINEERING RESOURCES, INC.

66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com

100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.8500
F 401.228.8205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 - DUCTWORK RENOVATION FLOOR PLAN

Project Number.

Drawing No.

M100

Sheet of

BUILDING 1 - OVERALL KEY PLAN

Scale: 1/16" = 1'-0"

MECHANICAL PIPING NOTES

1. CONTRACTOR SHALL DRAIN ENTIRE SYSTEM AND MAKE SAFE AS REQUIRED TO PERFORM WORK. AT THE COMPLETION OF NEW WORK, CONTRACTOR SHALL FILL THE SYSTEM AND MAINTAIN 40% PROPYLENE GLYCOL THROUGHOUT THE SYSTEM.
2. CONTRACTOR SHALL PROVIDE NEW CONTROL, BALANCING AND ISOLATION VALVES FOR ALL NEW CABINET UNIT HEATERS AND FIN-TUBE RADIATION. REFER TO DETAILS ON DRAWING M300. ALL NEW CONTROL VALVES SHALL BE TIED INTO EXISTING BMS SYSTEM.

2 M100 ENLARGED LATRINES PIPING RENOVATION PART PLAN

Scale: 1/4" = 1'-0"

1 M100 ENLARGED LATRINES PIPING RENOVATION PART PLANS

Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by LDC

Checked by R

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 - PIPING RENOVATION PLANS

Project Number.

Drawing No.

M101

Sheet of

BUILDING 3 - OVERALL KEY PLAN

Scale: 1/16" = 1'-0"

1 ENLARGED LATRINES RENOVATION PLAN

M103 Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by LDC

Checked by R□□

Revised on

B|E|R

BUILDING ENGINEERING RESOURCES, INC.

66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com

100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architecture

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 - DUCTWORK RENOVATION FLOOR PLAN

Project Number.

Drawing No.

M200

Sheet of

BUILDING 3 - OVERALL KEY PLAN

Scale: 1/16" = 1'-0"

1 ENLARGED LATRINES RENOVATION PLAN

M103 Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by LDC

Checked by R□□

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 - PIPING RENOVATION FLOOR PLAN

Project Number.

Drawing No.

M201

Sheet of

GRID CEILING DIFFUSER/REGISTER CONNECTION DETAIL | NTS

TYPICAL FIN-TUBE RADIATION PIPING DETAIL | NTS

ROOF MOUNTED EXHAUST FAN DETAIL | NTS

NOTES:
1. ON DUCTS OVER 48" WIDE, BOTTOM SHALL BE BRACED BY ANGLE. FOR CROSS SECTION AREA MORE THAN 8 SQ. FT., DUCT SHALL BE BRACED BY ANGLES ON ALL FOUR SIDES.
2. CUTTING AND PATCHING SHALL BE LIMITED TO A MINIMUM AS REQUIRED FOR PROPER INSTALLATION.
3. SUPPORTS SHALL BE SPACED AND SIZED PER SMACNA STANDARDS.

DUCT HANGER/SUPPORT DETAIL | NTS

NOTES:
1. VALVES SHALL BE INSTALLED IN A MANNER WERE ALL PORTS, LEVERS, DRAIN CONNECTION, AND ANY COMPONENTS OF VALVES AND FAN COIL UNIT IS EASILY ACCESSIBLE.
2. DO NOT INSULATE HEATING VALVE BODY.

TYPICAL CUH COIL PIPING DETAIL | NTS

WALL MOUNTED EXHAUST FAN DETAIL | NTS

REFRIGERANT PIPE SUPPORT DETAIL | NTS

GENERAL NOTE:
PITCH POCKET SHALL COMPLY WITH EXISTING ROOF MANUFACTURES INSTALLATION AND WARRANTY.

PITCH POCKET DETAIL FOR REFRIGERANT LINES | NTS

NOTES:
1. REFRIGERANT LINE SETS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE SYSTEM MANUFACTURER'S INSTALLATION INSTRUCTIONS (INCLUDING SIZING, ROUTING METHODS AND USE OF REFRIGERANT ACCESSORIES).
2. INSULATE BOTH SUCTION AND LIQUID LINES FOR ANY UNITS WITH HEAT PUMP OPERATION. REFER TO SPECIFICATIONS FOR INSULATION INFORMATION.
3. REFRIGERANT PIPING, CONDENSATE PIPING, CONDENSATE PIPING, CONTROL WIRING AND CONDUITS FROM INDOOR UNIT SHALL BE CONCEALED. THE ONLY VISIBLE COMPONENT SHALL BE THE AIR HANDLER. LOCATE ANY DEVICES NEEDING ACCESS IN AN ACCESSIBLE LOCATION AND PROVIDE ACCESS PANELS WHERE REQUIRED.

SPLIT SYSTEM REFRIGERANT PIPING DETAIL | NTS

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by LDC

Checked by R

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.5800
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

MECHANICAL DETAILS

Project Number.

Drawing No.

M300

Sheet of

LEGEND

- MOUNTING HEIGHTS SHALL BE AS INDICATED UNLESS SHOWN OTHERWISE ON ELECTRICAL DRAWINGS OR ARCHITECTURAL ELEVATIONS
- ALL SYMBOLS MAY NOT BE SHOWN ON PLANS

RACEWAYS AND WIRING

P4–1,3,5 — SINGLE PHASE HOMERUNS TO PANELBOARD. "P4" DENOTES PANEL, "1,3,5" DENOTES CIRCUIT NUMBERS, [(3) 20A, 1P CIRCUITS] NUMBER OF SLASH MARKS DENOTES NUMBER OF #12AWG CONDUCTORS IN MINIMUM 3/4"C. NO SLASH MARKS INDICATE 2#12 & 1#12G–3/4"C UNLESS INDICATED OTHERWISE.

P4–2 20/3 — MULTI–POLE HOMERUN TO PANELBOARD. "P4" DENOTES PANEL, "2" DENOTES CIRCUIT NUMBER, 20 AMP 3 POLE C/B. NUMBER OF SLASH MARKS DENOTES NUMBER OF #12AWG CONDUCTORS IN MINIMUM 3/4"C.

NOTES:
1. GREEN GROUND CONDUCTOR NOT INDICATED BUT SHALL BE INCLUDED IN EACH RACEWAY. SIZE SHALL BE #12AWG UNLESS INDICATED OTHERWISE.

LIGHTING FIXTURES (REFER TO LIGHTING FIXTURE SCHEDULE FOR EXACT FIXTURE TYPE)

A 2a — LIGHTING FIXTURE CEILING OR RECESSED MOUNTED. "A" DENOTES FIXTURE TYPE, "2" DENOTES CIRCUIT NUMBER, "a" DENOTES SWITCH CONTROL,

ROUND RECESSED LIGHTING FIXTURE

EB — SELF–CONTAINED EMERGENCY LIGHTING UNIT

LIGHTING CONTROL DEVICES

Soc ab Svs ab — SINGLE POLE TOGGLE SWITCH. "a" DENOTES FIXTURE CONTROL. "oc" DENOTES INTEGRAL OCCUPANCY SENSOR, "vs" DENOTES INTEGRAL VACANCY SENSOR

S3 — THREE WAY TOGGLE SWITCH

SD — DIMMER SWITCH

OC DT — CEILING MOUNTED OCCUPANCY SENSOR FOR LIGHTING CONTROL. REFER TO LIGHTING PLANS FOR EXACT CATALOG NUMBER "DT" DENOTES DUAL TECHNOLOGY

RECEPTACLES (MOUNTED 18" AFF OR AS INDICATED ON ARCHITECTURAL PLANS)

IG 2 GFI WP — DUPLEX RECEPTACLE, "2" DENOTES CIRCUIT NUMBER, "GFI" DENOTES GROUND FAULT CIRCUIT INTERRUPTER TYPE DEVICE, "IG" DENOTES ISOLATED GROUND TYPE DEVICE, "WP" DENOTES WEATHER PROOF COVER

DUPLEX RECEPTACLE MOUNTED 6" ABOVE COUNTER TOP OR AS INDICATED ON ARCHITECTURAL PLANS

DOUBLE DUPLEX RECEPTACLE

TELECOMMUNICATIONS (MOUNTED 18" AFF)

COMBINATION TELEPHONE/DATA OUTLET

FIRE ALARM SYSTEM

F — MANUAL PULL STATION MOUNTED 48" AFF

V — VISUAL ONLY UNIT MOUNTED 80" AFF.

F — CEILING MOUNTED AUDIO/VISUAL STROBE

I SD — PHOTOELECTRIC SMOKE DETECTOR: "I" DENOTES IONIZATION SMOKE DETECTOR

HD 190° — 135° FIXED TEMPERATURE HEAT DETECTOR. "190°" INDICATES 190°F FIXED TEMPERATURE

POWER DISTRIBUTION EQUIPMENT

DISTRIBUTION PANEL

PANELBOARD, SURFACE MOUNTED

PANELBOARD, FLUSH MOUNTED

J — JUNCTION BOX, SIZED PER NEC

MECHANICAL EQUIPMENT TAG ABBREVIATIONS

AH 1 — DENOTES EQUIPMENT TYPE; DENOTES UNIT NUMBER

ACC	AIR–COOLED CONDENSER
AHU	AIR HANDLING UNIT
B	BOILER
CH	CHILLER
CUH	CABINET UNIT HEATER
EBB	ELECTRIC BASEBOARD
EF	EXHAUST FAN
EH	EXHAUST HOOD
EWH	ELECTRIC WALL HEATER
FC	FAN COIL
HP	HEAT PUMP
MAU	MAKE–UP AIR UNIT
P	PUMP
RTU	ROOF TOP UNIT
UH	UNIT HEATER
VAV	VARIABLE AIR VOLUME BOX
WH	ELECTRIC WATER HEATER

ABBREVIATIONS

3R	NEMA 3R RATING
4X	NEMA 4X RATING
A	AMPERES
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AIC	AMPERE INTERRUPTING CAPACITY
ARCH	ARCHITECT
ATS	AUTOMATIC TRANSFER SWITCH
AWG	AMERICAN WIRE GAUGE
C	CONDUIT
C/B	CIRCUIT BREAKER
C.T.	CURRENT TRANSFORMER
CAT	CATALOG
CKT	CIRCUIT
CU	COPPER
DWG	DRAWING
E	WIRED ON EMERGENCY CIRCUIT
EC	ELECTRICAL CONTRACTOR
EM	EMERGENCY
ETD	EXISTING TO BE DEMOLISHED
ETR	EXISTING TO REMAIN
ETRL	EXISTING TO BE RELOCATED
ETRP	EXISTING TO BE REPLACED
G	GROUND
GC	GENERAL CONTRACTOR
GFI	GROUND FAULT INTERRUPTER
HVAC	HEATING, VENTILATION, AIR CONDITIONING CONTRACTOR
IG	ISOLATED GROUND
KCMIL	ONE THOUSAND CIRCULAR MILS
KVA	KILOVOLT–AMPERES
KVAR	KILOVOLT–AMPERES REACTIVE
KW	KILOWATTS
MCB	MAIN CIRCUIT BREAKER
MCC	MOTOR CONTROL CENTER
MD	MOTORIZED DAMPER
MLO	MAIN LUGS ONLY
NC	NORMALLY CLOSED
NEC	NATIONAL ELECTRICAL CODE
NL	NIGHT LIGHT
NO	NORMALLY OPEN
NTS	NOT TO SCALE
ø	PHASE
P	POLE
PC	PLUMBING CONTRACTOR
P.T.	POTENTIAL TRANSFORMER
PVC	POLYVINYL CHLORIDE
RL	NEW LOCATION OF RELOCATED DEVICE
SM	SURFACE MOUNT
ST	SHUNT TRIP
T/D	TEL/DATA
TEL	TELEPHONE
UG	UNDERGROUND
UNO	UNLESS NOTED OTHERWISE
V	VOLT
VIF	VERIFY IN FIELD
W	WATT
WP	WEATHERPROOF
XFMR	TRANSFORMER

LIGHTING FIXTURE SCHEDULE

TYPE	DESCRIPTION	MANUFACTURER & CATALOG NUMBER	LAMPS NUMBER	LAMPS TYPE	LAMPS VOLTS	LAMPS WATTS	REMARKS
A	1' X 4' LED TROFFER	LG# LGE–2X4SC–40–35–4000–TB	1	LED	120	40	– –
B	2' X 2' LED TROFFER	LG# LGE–2X2SC–32–35–3200–TB	1	LED	120	32	– –
C	6" DOWNLIGHT	PEACHTREE LIGHTING# 6BLRD–20–35K–90–SH–RCA–TRW–120	1	LED	120	25	
EB	EMERGENCY BATTERY UNIT	EMERGI–LITE BECM36–2	2	HALOGEN	12	(2) 9	

LIGHTING FIXTURE NOTES:

1. PROVIDE ACCESSORIES AND MOUNTING HARDWARE FOR ALL FIXTURES.
2. COLORS SHALL BE AS SELECTED BY ARCHITECT.
3. COORDINATE EXACT LOCATION WITH ARCHITECT PRIOR TO ROUGH–IN.
4. ALL COMPACT FLUORESCENT BALLASTS SHALL BE ELECTRONIC TYPE.
5. ALL LAMPS SHALL BE 3500°K.
6. E.C. SHALL ENSURE THAT ALL PROPOSED SWITCHES AND DIMMER SWITCHES ARE COMPATIBLE WITH THE LIGHT FIXTURE(S) INDICATED TO BE CONTROLLED. INSTALL ALL SWITCHES AND DIMMER SWITCHES PER MANUFACTURER'S RECOMMENDATIONS AND REQUIREMENTS.

DEMOLITION AND REMOVAL WORK

A. REMOVE ALL ELECTRICAL EQUIPMENT, WIRING, AND OTHER ELECTRICAL WORK AS REQUIRED. DISCONNECT LOAD AND LINE END OF CONDUCTORS FEEDING DEVICES WHICH ARE TO BE REMOVED OR ABANDONED, REMOVE CONDUCTORS NO LONGER IN USE. CUT BACK TO FLOOR, WALL, OR CEILING AND PLUG BOTH ENDS OF CONCEALED CONDUITS MADE OBSOLETE BY THIS ALTERATION. REMOVE EXPOSED OR ABANDONED CIRCUITS AND OUTLETS. REMOVE MATERIAL AND EQUIPMENT AND DISPOSE OF AS DIRECTED.

B. WHEREVER IT IS REQUIRED TO DISCONNECT OR REMOVE ANY PART OF AN EXISTING CIRCUIT, IMMEDIATELY RECONNECT THAT CIRCUIT OR REESTABLISH SERVICE IN THE REMAINING PORTION OF THE CIRCUIT.

C. THE WORK SHALL ALSO INCLUDE THE REMOVAL OF MATERIALS AS DIRECTED. PRIOR TO REMOVING EQUIPMENT AND MATERIAL FROM PROJECT SITE, THE BUILDING MANAGER OR OWNER WILL INSPECT AND ADVISE WHICH ITEMS WILL BE STORED.

D. WHERE EXISTING RECEPTACLES AND/OR SWITCHES ARE LOCATED IN COLUMNS AND/OR EXTERIOR WALLS, AND ARE NOT TO BE REUSED, REMOVE RECEPTACLE AND CAP OUTLET BOX. RECEPTACLES SHOWN ON PARTITIONS TO BE REMOVED SHALL HAVE ALL WIRING AND CONDUIT REMOVED AS WELL.

E. WHERE PRESENT WORK IS DAMAGED IN THE EXECUTION OF THIS CONTRACT, OR WHERE OPENINGS ARE LEFT DUE TO THE REMOVAL OF CONDUITS, EQUIPMENT, OR APPARATUS, THE SAME SHALL BE REPAIRED OR CLOSED UP TO CORRESPOND IN MATERIAL, QUALITY, SHAPE, AND FINISH WITH THAT OR SIMILAR AND ADJOINING WORK, UNLESS OTHERWISE CALLED FOR.

F. SHOULD ANY DAMAGE DUE TO THE EXECUTION OF THIS CONTRACT OCCUR TO THE FURNITURE, FIXTURES, OR ANY OTHER EQUIPMENT OR APPARATUS, SUCH DAMAGES SHALL BE PROPERLY REPAIRED WITH THE SUPPLY OF NEW ARTICLES AND MADE GOOD WITHOUT EXTRA CHARGE.

G. WHERE REMOVAL OF EXISTING ELECTRICAL EQUIPMENT WILL RESULT IN OUTAGES IN AREA NOT TO BE DEMOLISHED, THIS CONTRACTOR SHALL COORDINATE IN ADVANCE AND OBTAIN THE APPROVAL OF THE BUILDING MANAGER OR OWNER.

NOTES:
1. INSTALL DEVICES ON ONE COMMON VERTICAL CENTERLINE.
2. INSTALL DEVICES AT THIS HEIGHT WHEREVER APPLICABLE.

DETAIL OF TYPICAL DEVICE MOUNTING HEIGHTS | NTS

BRANCH CIRCUIT WIRING NOTES:

1. WIRING IS SHOWN ON DRAWINGS ONLY FOR SPECIFIC ROUTES OR SPECIAL CONDITIONS.
2. WIRING AND CONDUIT SHALL BE REQUIRED BETWEEN ALL OUTLETS INDICATED WITH CIRCUIT NUMBERS AND PANEL DESIGNATIONS.
3. ALL SWITCH CONTROLS SHALL BE PROVIDED WITH WIRING AND CONDUIT AS REQUIRED.
4. ALTHOUGH ALL BRANCH CIRCUIT WIRING AND CONDUIT IS NOT SHOWN, IT IS THE INTENT OF THESE DOCUMENTS THAT A COMPLETE BRANCH CIRCUIT WIRING SYSTEM BE INSTALLED.
5. A GREEN GROUNDING CONDUCTOR SHALL BE RUN WITH ALL CIRCUITS. VERIFY CONDUIT SIZE TO ENSURE IT CAN ACCOMMODATE ALL PHASE, NEUTRAL AND GROUND CONDUCTORS.
6. PROVIDE A NEUTRAL CONDUCTOR TO ALL NEW LIGHTING SWITCH BOXES PER NEC ARTICLE 404.2.
7. WHERE EXISTING SWITCHES AND RECEPTACLES ARE INDICATED TO REMAIN, THIS CONTRACTOR SHALL REPLACE SAID DEVICE(S) AND DEVICE PLATE(S) WITH NEW TO MATCH THE NEW CONSTRUCTION. WHERE THEY ARE INDICATED AS RELOCATED, EXTEND BRANCH CIRCUIT WIRING TO NEW LOCATION AND PROVIDE NEW DEVICE AND DEVICE PLATE TO MATCH NEW CONDITIONS.
8. ALL SELF CONTAINED EMERGENCY LIGHTING UNITS AND EXIT LIGHTING IN THE BUILDING SHALL BE CONNECTED TO THE NEAREST UNSWITCHED LIGHTING CIRCUIT IN THE AREA WITH 2 #12, #12G, 3/4" CONDUIT UNLESS OTHERWISE NOTED.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

MARC R. PLANTE
No. 6397
REGISTERED PROFESSIONAL ENGINEER ELECTRICAL

Drawn by NM

Checked by DEC

Revised on

BER
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street, N. Easton, MA 02356, T 508.230.0260, F 508.230.0265
100 Midway Road - Suite 23, Cranston, RI 02920, T 401.942.3500, F 401.228.6205
ber@ber-engineering.com www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

ELECTRICAL - LEGEND, NOTES & SCHEDULES

Project Number.

Drawing No.

E001

Sheet of

1 ENLARGED LATRINES DEMOLITION PLAN
ED101 Scale: 1/4" = 1'-0"

2 ENLARGED LATRINES DEMOLITION PLAN
ED101 Scale: 1/4" = 1'-0"

3 ENLARGED LATRINES DEMOLITION PLAN
ED101 Scale: 1/4" = 1'-0"

BUILDING 1 – EXISTING OVERALL DEMOLITION FLOOR PLAN
Scale: 1/16" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

MARC R. PLANTE
No. 6397
REGISTERED PROFESSIONAL ENGINEER ELECTRICAL

Drawn by NM
Checked by DEC

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB ARCHITECTS
Architecture · Project Management · Interior Design

Project
RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status
ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents
BUILDING 1 ELECTRICAL - DEMOLITION PLAN

Project Number.

Drawing No.
ED101

Sheet of

1 ED102 BUILDING 3 – EXISTING OVERALL DEMOLITION FLOOR PLAN

Scale: 1/16" = 1'-0"

3 ED102 ENLARGED LATRINES DEMOLITION PLAN

Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

MARC R. PLANTE
No. 6397
REGISTERED PROFESSIONAL ENGINEER ELECTRICAL

Drawn by NM

Checked by DEC

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB ARCHITECTS

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 ELECTRICAL - DEMOLITION PLAN

Project Number.

Drawing No.

ED102

Sheet of

BUILDING 1 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'–0"

2 E101 ENLARGED LATRINES PLAN

Scale: 1/4" = 1'–0"

KEYED NOTES:

1. CONNECT TO EXISTING CIRCUIT FORMALLY SERVING THIS AREA.

1 E101 ENLARGED LATRINES PLAN

Scale: 1/4" = 1'–0"

3 E101 ENLARGED LATRINES PLAN

Scale: 1/4" = 1'–0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

MARC R. PLANTE
No. 6397
REGISTERED PROFESSIONAL ENGINEER ELECTRICAL

Drawn by NM

Checked by DEC

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com

100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB ARCHITECTS

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 ELECTRICAL - LIGHTING PLAN

Project Number.

Drawing No.

E101

Sheet of

BUILDING 1 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'–0"

2 ENLARGED LATRINES PLAN

E102 Scale: 1/4" = 1'–0"

1 ENLARGED LATRINES PLAN

E102 Scale: 1/4" = 1'–0"

3 ENLARGED LATRINES PLAN

E102 Scale: 1/4" = 1'–0"

PANELBOARD SCHEDULE

PANEL DESIGNATION	VOLTS	PHASE	WIRES	MAINS MLO: MAIN LUGS ONLY MCB: MAIN CKT. BKR. BUS SIZE	OVERCURRENT DEVICE FRAME AMPS	OVERCURRENT DEVICE TRIP AMPS	BKR. POLES	BRANCH DEVICES BREAKER AMPS 15	20	25	30	40	50	60	70	* TOTAL POLES	MOUNTING S: SURFACE F: FLUSH	GROUND BUS	ADDITIONAL BRANCH C.B.'S	REMARKS
LF	120/208	3	4	100	100	100	1		24							30	F	✓	–	–
							2		–											
							3		–											

* INCLUDES SPACES

BUILDING 1 – RISER DIAGRAM

Scale: NTS

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

MARC R. PLANTE
No. 6397
REGISTERED PROFESSIONAL ENGINEER ELECTRICAL

Drawn by NM

Checked by DEC

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 ELECTRICAL - POWER PLAN

Project Number.

Drawing No.

E102

Sheet of

BUILDING 3 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'-0"

1 E103 ENLARGED LATRINES PLAN

Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

MARC R. PLANTE
No. 6397
REGISTERED PROFESSIONAL ENGINEER ELECTRICAL

Drawn by NM

Checked by DEC

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB ARCHITECTS

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 ELECTRICAL - LIGHTING PLAN

Project Number.

Drawing No.

E103

Sheet of

BUILDING 3 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'-0"

PANELBOARD SCHEDULE																							
PANEL DESIGNATION	VOLTS	PHASE	WIRES	MAINS MLO: MAIN LUGS ONLY MCB: MAIN CKT. BKR.			BRANCH DEVICES											TOTAL POLES	MOUNTING * S: SURFACE F: FLUSH	ADDITIONAL BRANCH C.B.'S	REMARKS
				BUS SIZE	OVERCURRENT DEVICE		BKR. POLES	BREAKER AMPS													
					FRAME AMPS	TRIP AMPS		5	20	25	30	40	50	60	70						
LD-3	120/208	3	4	150	MLO	MLO	1		32									42	S	–	–
							2	3								1					
							3		–												

* INCLUDES SPACES

1 E104 ENLARGED LATRINES PLAN

Scale: 1/4" = 1'-0"

POWER RISER DIAGRAM

Scale: NTS

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

MARC R. PLANTE
No. 6397
REGISTERED PROFESSIONAL ENGINEER ELECTRICAL

Drawn by NM

Checked by DEC

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
Architecture · Project Management · Interior Design
RGB Architects

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 ELECTRICAL - POWER PLAN

Project Number.

Drawing No.

E104

Sheet of

BUILDING 1 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'–0"

2 FA100 ENLARGED LATRINES PLAN

Scale: 1/4" = 1'–0"

1 FA100 ENLARGED LATRINES PLAN

Scale: 1/4" = 1'–0"

KEYED NOTES:

1. CONNECT NEW NOTIFICATION APPLIANCES TO THE EXISTING NOTIFICATION APPLIANCE CIRCUIT. PROVIDE A BATTERY BOOSTER PACK SIZED FOR THE NEW DEVICES.
2. CONNECT NEW INITIATING APPLIANCE TO EXISTING INITIATING DEVICE CIRCUIT.
3. PROVIDE TESTING OF THE ENTIRE FIRE ALARM SYSTEM UPON COMPLETION OF NEW WORK.

3 FA100 ENLARGED LATRINES PLAN

Scale: 1/4" = 1'–0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

MARC R. PLANTE
No. 6397
REGISTERED PROFESSIONAL ENGINEER ELECTRICAL

Drawn by NM

Checked by DEC

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB ARCHITECTS

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1
FIRE ALARM PLAN

Project Number.

Drawing No.

FA100

Sheet of

BUILDING 3 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'–0"

1 / FA101 ENLARGED LATRINES PLAN

Scale: 1/4" = 1'–0"

KEYED NOTES:

1. CONNECT NEW NOTIFICATION APPLIANCES TO THE EXISTING NOTIFICATION APPLIANCE CIRCUIT. PROVIDE A BATTERY BOOSTER PACK SIZED FOR THE NEW DEVICES.
2. CONNECT NEW INITIATING APPLIANCE TO EXISTING INITIATING DEVICE CIRCUIT.
3. PROVIDE TESTING OF THE ENTIRE FIRE ALARM SYSTEM UPON COMPLETION OF NEW WORK.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

MARC R. PLANTE
No. 6397
REGISTERED PROFESSIONAL ENGINEER ELECTRICAL

Drawn by NM

Checked by DEC

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB ARCHITECTS

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 FIRE ALARM PLAN

Project Number.

Drawing No.

FA101

Sheet of

HANGER ROD SCHEDULE	
PIPE SIZE	ROD SIZE
UP TO 2"	3/8" DIA.
2 1/2" THRU 3"	1/2" DIA.
4" AND 5"	5/8"

HANGER ROD SPACING	
PIPE SIZE	MAX. ALLOWABLE SPACING
1"	7'
1 1/4"	8'
1 1/2"	9'
2"	10'
2 1/2"	11'

1 CLEVIS PIPE HANGER/ROD INSTALLATION

NTS

NOTE:
FIRESTOP SEALANTS AND PIPING PENETRATIONS THROUGH FIRE RATED ASSEMBLIES SHALL COMPLY WITH THE UL FIRE RESISTANCE DIRECTORY.

HANGER ROD SCHEDULE	
PIPE SIZE	ROD SIZE
UP TO 2"	3/8" DIA.
2 1/2" & 3"	1/2" DIA.
4" AND 5"	5/8"
6" – 8"	3/4"
10 & 12"	7/8"

HANGER ROD SPACING	
PIPE SIZE	MAX. ALLOWABLE SPACING
1"	7'
1 1/4"	8'
1 1/2"	9'
2"	10'
2 1/2"	11'
3" – 12"	12'

2 CLEVIS–BAND HANGER/ROD INSTALLATION

NTS

NOTE:
FIRESTOP SEALANTS AND PIPING PENETRATIONS THROUGH FIRE RATED ASSEMBLIES SHALL COMPLY WITH THE UL FIRE RESISTANCE DIRECTORY.

3 MASONRY WALL FIRE RATED SLEEVE

NTS

4 STUD WALL FIRE RATED SLEEVE

NTS

GENERAL NOTES

1. GENERAL NOTES, SYMBOLS LIST AND DETAILS ARE APPLICABLE TO ALL PLUMBING DRAWINGS.
2. DRAWINGS ARE DIAGRAMMATIC: DETERMINE LOCATIONS OF SYSTEMS AND COMPONENTS IN FIELD. DO NOT SCALE DRAWINGS.
3. NEITHER ACCURACY NOR COMPLETION OF UTILITY LOCATIONS SHOWN ON DRAWINGS IS GUARANTEED. DETERMINE EXACT LOCATIONS OF EXISTING UTILITIES IN FIELD, WHETHER OR NOT SHOWN ON DRAWINGS. EXERCISE CAUTION AND IDENTIFY LOCATIONS OF UNMARKED UTILITY LINES AS NECESSARY TO PERFORM WORK OF THIS SECTION.
4. ALL PLUMBING WORK SHALL BE IN ACCORDANCE WITH THE PRESIDING PLUMBING CODE AND ALL APPLICABLE LOCAL CODES.
5. IT SHALL BE THE RESPONSIBILITY OF THIS CONTRACTOR TO COORDINATE WORK WITH THAT OF ALL OTHER TRADES, INCLUDING (BUT NOT LIMITED TO), ELECTRICAL, HVAC, FIRE PROTECTION, STRUCTURAL AND GENERAL ARCHITECTURE.
6. ANY INTERFERENCE SHALL BE BROUGHT TO THE ATTENTION OF THE CONSTRUCTION MANAGER, GENERAL CONTRACTOR, AND/OR THE OWNER'S REPRESENTATIVE, AND RESOLVED PRIOR TO THE INSTALLATION OF THE WORK INVOLVED.
7. ALL PIPING PENETRATING CEILINGS AND WALLS SHALL BE INSTALLED WITH CHROME (STAINLESS WHERE NOTED) PLATED ESCUTCHEONS AT THE PENETRATION. ALL PIPING PENETRATING EXTERIOR WALLS AND ROOFS SHALL BE FLASHED AS REQUIRED AND SHALL BE SEALED WEATHERTIGHT. PIPING PENETRATING FIRE RATED PARTITIONS SHALL BE PROTECTED WITH UL LISTED SEALS OF EQUAL RATING.
8. MANUFACTURERS' MODEL NUMBERS ARE SPECIFIED SOLELY TO ESTABLISH STANDARDS OF QUALITY FOR PERFORMANCE AND MATERIALS.
9. ALL PRODUCT INSTALLATION SHALL ADHERE TO THE MANUFACTURERS' RECOMMENDATIONS.
10. PROVIDE ACCESS PANELS FOR ALL EQUIPMENT THAT REQUIRES PERIODIC SERVICE AND FOR ALL VALVES.
11. TOPS OF ALL FLOOR DRAINS AND CLEANOUTS SHALL BE SET FLUSH WITH FINISHED FLOOR. ALL PIPING ABOVE GRADE SHALL BE PROPERLY SUPPORTED BY THE BUILDING STRUCTURE AND SHALL NOT REST ON CEILING TILES OR CEILING STRUCTURE.
12. CONTRACTOR SHALL COORDINATE ELECTRICAL CHARACTERISTICS AND REQUIREMENTS OF ALL PLUMBING EQUIPMENT WITH THE ELECTRICAL DRAWINGS, AND SHALL FURNISH EQUIPMENT WIRED FOR THE VOLTAGES SHOWN HEREIN.
13. PROVIDE SHUTOFF VALVES ON ALL BRANCH PIPING AND SUPPLIES TO INDIVIDUAL FIXTURES AND EQUIPMENT. PROVIDE BALL VALVES ON ALL WATER MAIN BRANCHES IN CORRIDORS AND WHERE INDICATED ON DRAWINGS. ALL VALVES SHALL BE ACCESSIBLE.
14. ALL SLEEVES THROUGH CONCRETE FLOORS AND ALL CORE DRILLING OF CONCRETE FLOORS AND WALLS SHALL BE BY THIS CONTRACTOR. CONCRETE PADS AND PLATFORMS FOR WORK OF THIS SECTION WILL BE PROVIDED BY GENERAL CONTRACTOR. PROVIDE INFORMATION AS NECESSARY TO COORDINATE WORK.
15. RUN PIPING CONCEALED WHERE POSSIBLE, UNLESS SPECIFIED OTHERWISE.
16. STRUCTURAL WELDING SHALL BE 1/4–INCH FILLET UNLESS REQUIRED OTHERWISE.
17. PROVIDE CLAMPS, OFFSETS, EXPANSION JOINTS, ANCHORS AND GUIDES AS NECESSARY TO PREVENT STRESS ON PIPING.
18. PROVIDE BALANCING VALVES AT SYSTEM LOOP RETURNS AND AT RETURN RISERS, PROVIDE SHUTOFF VALVES AT SYSTEM LOOP SUPPLIES AND SUPPLY RISERS.
19. PROVIDE VENTS AT HIGH POINTS IN PIPING SYSTEMS AND DRAIN VALVES AT LOW POINTS.
20. PROVIDE GAUGE FITTINGS AND THERMOMETER WELLS AT HOT WATER SUPPLY AND RETURN BRANCHES AND AT PUMP INLETS AND OUTLETS.
21. VERIFY EXACT SIZES, LOCATIONS, INVERTS AND ELEVATIONS PRIOR TO RUNNING ANY PIPING. REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATIONS OF ALL FIXTURES AND EQUIPMENT.
22. PIPE SUPPORTS FOR PLUMBING IN BUILDING SHAFTS ARE BY THIS CONTRACTOR. CAREFULLY COORDINATE WITH PLACEMENT OF STEEL GRATE SUPPORT BEAMS. SHAFT PIPE SUPPORT SHALL BEAR FROM WALL AND FROM FLOOR SUPPORT BEAMS.
23. GENERAL FLOOR CONTROL VALVES OF PIPED SERVICES SHALL BE IN THE PIPE SHAFTS UNLESS OTHERWISE INDICATED.
24. OBTAIN GAS PERMITS AND DEFRAY ALL COSTS INCIDENTAL TO THE GAS PIPING SYSTEM. CONTRACTORS WORK SHALL COMMENCE ON THE HOUSE SIDE OF THE UTILITY COMPANY METER.
25. A SUITABLE DRIP OF CONDENSATE POCKET SHALL BE INSTALLED AT THE BOTTOM OF ALL GAS RISERS.
26. ALL GAS PIPING TO COMPLY WITH LOCAL AND STATE CODES.
27. GAS PIPING AND SAFETY DEVICES SHALL CONFORM TO REQUIREMENTS OF NFPA 54 AND SHALL BE SUBJECT TO THE INSPECTION AND APPROVAL OF THE AUTHORITY HAVING JURISDICTION.
28. PROVIDE A SUITABLE GAS COCK VALVE AT HOUSE SIDE OF METER AND EACH BRANCH RUNOUT FROM THE MAIN SERVING GAS OUTLETS AND INDIVIDUAL GAS FIXTURES.
29. GAS PIPING SHALL BE TESTED ACCORDING TO THE STATE FUEL GAS CODE AND NATIONAL CODE PROVISIONS OF THE LOCAL PLUMBING INSPECTOR. IF INSPECTION OF THE TEST SHOWS DEFECTS, SUCH DEFECTIVE WORK AND MATERIAL SHALL BE REPLACED AND INSPECTION AND TEST SHALL BE REDONE.
30. PLUMBING CONTRACTOR IS RESPONSIBLE FOR EXTENDING ALL REGULATOR VENTS TO ATMOSPHERE. REGULATORS ARE PART OF EQUIPMENT GAS TRAIN. PIPE ALL GAS TRAN VENTS FROM HVAC BOILERS TO ATMOSPHERE.
31. NO PIPING SHALL RUN OVER ELECTRICAL PANELS.
32. ALL EXTERIOR GAS PIPING SHALL BE PAINTED WITH TWO (2) COATS OF EPOXY BASED PAINT. COLOR TO MATCH EXISTING. REFER TO SPECIFICATION SECTION 099100 "PAINTING".
33. ALL PIPING THAT PENETRATES FLOORS OR FIRE RATED WALLS SHALL BE FIRE STOPPED W/ FIRE RATED CAULKING PER MANUFACTURERS RECOMMENDATIONS. REFER TO SPECIFICATION SECTION 078413 "PENETRATION FIRESTOPPING".
34. ELECTRICAL SUB CONTRACTOR IS RESPONSIBLE FOR PROVIDING POWER TO ALL EQUIPMENT AND CONTROLS WITHIN THE PLUMBING SYSTEMS FOR THIS PROJECT.

PLUMBING LEGEND

	RE	REMOVE EXISTING PIPING & EQUIPMENT
	ETR	LIGHT LINE INDICATES EXISTING PIPING TO REMAIN
	CTE	CONNECT TO EXISTING
	CC	CUT & CAP
	V&C	VALVE & CAP
	CW	COLD WATER
CW	CW	COLD WATER BELOW FLOOR BURIED
	HW	HOT WATER
	HWR	HOT WATER RECIRCULATION
	S or W	SOIL OR WASTE
S/W	S or W	SOIL OR WASTE BELOW FLOOR OR BURIED
GW	GW OR (GW)	GARAGE WASTE
	V	VENT
V	V	VENT BELOW FLOOR OR BURIED
	CONT	CONTINUATION
	UP	PIPE RISE OR UP
	DN	PIPE DROP OR DOWN
	TEE	PIPE TEE
	SOV	SHUT–OFF VALVE
	CV	CHECK VALVE
	BVA	BALANCING VALVE ASSEMBLY
	W & T	WASTE & TRAP
	CO	CLEANOUT PLUG
	FCO	FLUSH FLOOR CLEANOUT
	WCO	WALL CLEANOUT
		CAPPED PIPE
		ARROW INDICATES DIRECTION OF FLOW
.01		ARROW INDICATES DIRECTION OF SLOPE
		UNION
	HB	HOSE BIBB
	WH	WALL HYDRANT
	FD	FLOOR DRAIN
	FS	FLOOR SINK
	DN	DOWN
	DR	DROP/RISE
	EX	EXISTING
	IW	INDIRECT WASTE
	VTR	VENT THRU ROOF
	INV	INVERT
	TYP	TYPICAL
	VIF	VERIFY EXACT LOCATION, SIZE & INVERT IN FIELD
	NTS	NOT TO SCALE
	VIF	VERIFY EXACT LOCATION, ROUTE & INVERT IN FIELD
	W & V	WASTE AND VENT
	S & V	SOIL AND VENT
	AFF	ABOVE FINISHED FLOOR
	LPC	LIMIT OF PLUMBING CONTRACT
	NIPC	NOT IN PLUMBING CONTRACT
	GC	GENERAL CONTRACTOR
	FPC	FIRE PROTECTION CONTRACTOR
	PC	PLUMBING CONTRACTOR
	EC	ELECTRICAL CONTRACTOR
	HVAC	HVAC CONTRACTOR
	F & I	FURNISH & INSTALL
	S=.01	SLOPE = 1/8" PER FOOT
	S=.02	SLOPE = 1/4" PER FOOT
	F.F.E.	FINSHED FLOOR ELEVATION

DRAIN SCHEDULE

SYMBOL	TYPE	MANUFACTURER	MODEL	OUTLET	STRAINER	REMARKS
FD–1	FLOOR DRAIN	J.R. SMITH	2005Y–A–NB–P050	2"	6"ø NICKEL BRONZE	CAST IRON BODY, NO–HUB, ADJUSTABLE STRAINER, TRAP PRIMER CONNECTION.

NOTES:
1. ALL FLOOR DRAINS SHALL HAVE TRAP SEAL GASKETS EQUAL TO "SURE SEAL".
2. INSTALL PER RI CODE AND MANUFACTURER'S INSTALLATION REQUIREMENTS.

PLUMBING FIXTURE SCHEDULE

SYMBOL	DESCRIPTION	FIXTURE				FIXTURE			SERVICES					REMARKS
		MANUFACTURER	MODEL	TYPE	SIZE	MANUFACTURER	MODEL	TYPE	S/W	V	CW	HW	TW	
P–1	WATER CLOSET	AMERICAN STANDARD	2859.111	WALL HUNG	1.28 GPF	SLOAN	111–1.28–DFB–ESS	SENSOR FLUSH VALVE	4"	2"	1"	–	–	VITREOUS CHINA, ELONGATED, LOW CONSUMPTION, TOP SPUD, SENSOR FLUSH VALVE, HARD WIRED AC POWERED W/ TRANSFORMER, SLOAN #EL–154 120V, 50/60 Hz. BEMIS #3155SSCT OPEN FRONT SEAT. PROVIDE WALL CARRIER.
P–1A	WATER CLOSET – ADA	AMERICAN STANDARD	2859.111	WALL HUNG	1.6 GPF	SLOAN	111–1.6–ES–S–TMO	SENSOR FLUSH VALVE	4"	2"	1"	–	–	VITREOUS CHINA, ELONGATED, LOW CONSUMPTION, TOP SPUD, SENSOR FLUSH VALVE, HARD WIRED AC POWERED W/ TRANSFORMER, SLOAN #EL–154 120V, 50/60 Hz. BEMIS #3155SSCT OPEN FRONT SEAT. PROVIDE WALL CARRIER. BARRIER FREE, ADA COMPLIANT.
P–2	LAVATORY – ADA	INTERSAN	SLV03–L00R00–B–L07–TMV–HW	WALL HUNG	90"x21½"	INTERSAN	L07	SENSOR	1–1/2"	1–1/2"	1/2"	1/2"	–	ANTI–MICROBIAL SOLIDGUARD, LAVATORY SPACING ON 30" CENTERS. PROVIDE GRID DRAIN W/ OVERFLOW. PROVIDE WALL CARRIER. 0.35 GPM SENSOR FAUCET. PROVIDE THERMOSTATIC MIXING VALVE. LOW VOLTAGE CLASS II TRANSFORMER W/ PLUG (1 PER FAUCET). PROVIDE CHROME PLAYED HEAVY DUTY OFF–SET P–TRAP, SUPPLIES & STOPS. COORDINATE FIXTURE COLOR W/ ARCHITECT. BARRIER FREE, ADA COMPLIANT.
P–2A	LAVATORY – ADA	INTERSAN	SLV04–B–L07–TMV–HW	WALL HUNG	120"x21½"	INTERSAN	L07	SENSOR	1–1/2"	1–1/2"	1/2"	1/2"	–	ANTI–MICROBIAL SOLIDGUARD, LAVATORY SPACING ON 30" CENTERS. PROVIDE GRID DRAIN W/ OVERFLOW. PROVIDE WALL CARRIER. 0.35 GPM SENSOR FAUCET. PROVIDE THERMOSTATIC MIXING VALVE. LOW VOLTAGE CLASS II TRANSFORMER W/ PLUG (1 PER FAUCET). PROVIDE CHROME PLAYED HEAVY DUTY OFF–SET P–TRAP, SUPPLIES & STOPS. COORDINATE FIXTURE COLOR W/ ARCHITECT. BARRIER FREE, ADA COMPLIANT.
P–2B	LAVATORY – ADA	AMERICAN STANDARD	0355.012	WALL HUNG	20½"x18¾"	SYMMONS	S–20–2–G–0.5	MANUAL	1–1/2"	1–1/2"	1/2"	1/2"	–	VITREOUS CHINA, 3–HOLE, 4" CENTERS, 0.5 GPM MANUAL FAUCET. PROVIDE GRID DRAIN ASSEMBLY. PROVIDE CHROME PLATED HEAVY DUTY OFFSET P–TRAP, SUPPLIES & STOPS. PROVIDE WALL CARRIER. BARRIER FREE, ADA COMPLIANT.
P–3	URINAL	AMERICAN STANDARD	6590.001	WALL HUNG	–	SLOAN	186–0.5–DFB–ESS	SENSOR FLUSH VALVE	2"	2"	3/4"	–	–	VITREOUS CHINA, LOW CONSUMPTION, TOP–SPUD, SENSOR FLUSH VALVE, HARD WIRED AS POWERED W/ TRANSFORMER, SLOAN #EL–154 120V, 50/60 Hz & SOLENOID VALVE. PROVIDE WALL CARRIER. PROVIDE HEAVY DUTY CHROME PLATED SUPPLY & STOP.
P–3A	URINAL – ADA	AMERICAN STANDARD	6590.001	WALL HUNG	–	SLOAN	186–0.5–DFB–ESS	SENSOR FLUSH VALVE	2"	2"	3/4"	–	–	VITREOUS CHINA, LOW CONSUMPTION, TOP–SPUD, SENSOR FLUSH VALVE, HARD WIRED AS POWERED W/ TRANSFORMER, SLOAN #EL–154 120V, 50/60 Hz & SOLENOID VALVE. PROVIDE WALL CARRIER. PROVIDE HEAVY DUTY CHROME PLATED SUPPLY & STOP. BARRIER FREE, ADA COMPLIANT.
P–4	SHOWER	(BY OTHERS)	–	–	–	SYMMONS	1–901S–1.5	MANUAL	3"	2"	1/2"	1/2"	–	SYMMONS "HYDAPIPE", SURFACE MOUNTED, STAINLESS STEEL SHOWER SYSTEM. PRESSURE BALANCING MIXING VALVE W/ SCREW DRIVER SERVICE STOPS & ADJUSTABLE STOP SCREW. FREE–FLO, ALL BRASS, 1.5 GPM.
P–4A	SHOWER – ADA	(BY OTHERS)	–	–	–	SYMMONS	1–912RS–FSB–1.5	MANUAL	3"	2"	1/2"	1/2"	–	SYMMONS "HYDAPIPE", SURFACE MOUNTED, STAINLESS STEEL SHOWER SYSTEM. PRESSURE BALANCING MIXING VALVE W/ SCREW DRIVER SERVICE STOPS & ADJUSTABLE STOP SCREW. FREE–FLO, ALL BRASS, 1.5 GPM. BARRIER FREE, ADA COMPLIANT.
P–5	SERVICE SINK	STERN WILLIAMS	SB–500	FLOOR MOUNTED	36"x36"x12"	CHICAGO	897–CP	MANUAL	3"	2"	1/2"	–	–	FLOOR MOUNTED, MARBLE CHIPS & CEMENT, WALL MOUNTED CHROME PLATED LEVER FAUCET, VACUUM BREAKER. PROVIDE SPLASH GUARD, MOP & HOSE BRACKETS.
P–6	DRINKING FOUNTAIN	HALSEY TAYLOR	HTHB–HACC8SS–WF	WALL HUNG	SINGLE LEVEL	–	–	–	1–1/2"	1–1/2"	1/2"	–	–	WALL HUNG STAINLESS STEEL, ELECTRIC REFRIGERATED WATER COOLER W/ BOTTLE FILLING STATION – 120V, 60Hz, 1ϕ GFCI OUTLET. BARRIER FREE, ADA COMPLIANT.

NOTES:
1. ALL ADA FIXTURES SHALL BE INSTALLED PER ADA REQUIREMENTS.
2. ALL PLUMBING FIXTURES, EQUIPMENT & ACCESSORIES SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by AG
Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

LEGEND, NOTES, DETAILS & SCHEDULES - PLUMBING

Project Number.

Drawing No.

P001

Sheet of

BUILDING 1 – EXISTING OVERALL DEMOLITION FLOOR PLAN

Scale: 1/16" = 1'-0"

2 / P100 ENLARGED LATRINES DEMOLITION PLAN

Scale: 1/4" = 1'-0"

PLUMBING DEMO KEYED NOTES

1. REMOVE AND DISCARD EXISTING FLOOR MOUNTED FLUSH VALVE WATERCLOSET. CUT AND CAP BACK EXISTING 1" COLD WATER SUPPLY AND 4" SANITARY WASTE AND 2" VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
2. REMOVE AND DISCARD EXISTING FLOOR MOUNTED TANK TYPE WATERCLOSET. CUT AND CAP BACK EXISTING ½" COLD WATER SUPPLY AND 4" SANITARY WASTE AND 2" VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
3. REMOVE AND DISCARD EXISTING WALL HUNG LAVATORY & FAUCET. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
4. REMOVE AND DISCARD EXISTING COUNTER MOUNTED LAVATORY & FAUCET. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
5. REMOVE AND DISCARD EXISTING WALL MOUNTED FLUSH VALVE URINAL AND CARRIER. CUT AND CAP BACK EXISTING 3/4" COLD WATER SUPPLY AND 2" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
6. REMOVE AND DISCARD EXISTING SHOWER ENCLOSURE AND VALVE SYSTEM. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
7. REMOVE AND DISCARD EXISTING WATER COOLER. CUT AND CAP BACK EXISTING ½" CW, 2" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
8. REMOVE AND DISCARD EXISTING SERVICE SINK. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
9. REMOVE AND DISCARD EXISTING FLOOR DRAIN. CUT AND CAP BACK EXISTING TP SUPPLY AND SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
10. REMOVE AND DISCARD EXISTING WALL MOUNTED HOSE BIBB. CUT AND CAP BACK EXISTING ½" COLD WATER SUPPLY LINE BACK TO EXISTING RESPECTIVE MAIN LINE.

NOTES:
VERIFY EXACT LOCATIONS OF ALL ABOVE AND BELOW GROUND DOMESTIC WATER, SANITARY WASTE & VENT, STORM DRAINAGE AND NATURAL GAS SUPPLY & MAIN PIPING IN FIELD.

PLUMBING DEMOLITION NOTES

1. PRIOR TO SUBMITTING BID, THE CONTRACTOR SHALL VISIT THE PROJECT SITE TO BECOME FAMILIAR WITH ALL EXISTING CONDITIONS AND TO DETERMINE THE EXTENT OF WORK TO REMOVE THE EXISTING PLUMBING SYSTEM COMPLETELY. IF DISCREPANCIES EXIST BETWEEN DRAWINGS AND/OR SITE CONDITIONS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE OWNER PRIOR TO SIGNING OF CONTRACT. REQUESTS FOR COMPENSATION FOR EXTRA WORK, WHICH WOULD HAVE BEEN EVIDENT BY COMPLIANCE WITH THE PREVIOUS STATEMENT, WILL NOT BE CONSIDERED.
2. DISCONNECT, DISMANTLE AND DEMOLISH ALL EXISTING PLUMBING SYSTEMS AND EQUIPMENT AS INDICATED IN THE CONTRACT DRAWINGS. REMOVE ALL DEBRIS AND DISCONNECTED EQUIPMENT AND CLEAN OUT EXISTING SPACES. REFER TO ARCHITECTURAL DEMOLITION PLANS FOR DEMOLITION WORK.
3. REMOVE ALL EXISTING DOMESTIC, SANITARY AND GAS PLUMBING SERVICES INDICATED TO BE DEMOLISHED AND CAP BACK TO RESPECTIVE EXISTING MAIN LINES TO REMAIN. REMOVE AND DISCARD EXISTING PLUMBING STACKS, MAINS, BRANCHES AND VENTS SERVING FIXTURES TO BE DEMOLISHED. OBTAIN EXISTING RECORD DRAWINGS FROM OWNER.
4. VERIFY PIPING SERVES ONLY PLUMBING FIXTURES INDICATED FOR DEMOLITION BEFORE SHUT-DOWN FOR DISCONNECTION. IDENTIFY EXISTING PIPING WHICH SERVES FIXTURES TO REMAIN. PROMPTLY NOTIFY ARCHITECT OF ACTIVE PIPING TO BE MAINTAINED WHEN LOCATED IN PARTITIONS TO BE DEMOLISHED.
5. COORDINATE ALL SHUT-DOWNS, TIE-INS, ETC., WITH THE G.C. ELECTRICAL MAKE-SAFE OF PLUMBING EQUIPMENT REQUIRING DEMOLITION SHALL BE COMPLETED BY THE ELECTRICAL SUBCONTRACTOR.
6. DEMOLITION SUBCONTRACTOR MUST PROTECT EXISTING SLAB, WALL, FENCING AND BUILDING STRUCTURE DURING DEMOLITION PHASE. DAMAGE TO EXISTING STRUCTURE SHALL BE REPAIRED AT DEMOLITION SUBCONTRACTORS EXPENSE.
7. ALL DEMOLITION WORK PERFORMED SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE NATIONAL, STATE AND LOCAL CODES, LAWS AND ORDINANCES.

1 / P100 ENLARGED LATRINES DEMOLITION PLAN

Scale: 1/4" = 1'-0"

3 / P100 ENLARGED CLOSET DEMOLITION PLAN

Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by AG

Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 DEMOLITION PLAN SANITARY, WASTE & VENT - PLUMBING

Project Number.

Drawing No.

P100

Sheet of

BUILDING 1 – EXISTING OVERALL DEMOLITION FLOOR PLAN

Scale: 1/16" = 1'–0"

2 P101 ENLARGED LATRINES DEMOLITION PLAN

Scale: 1/4" = 1'–0"

PLUMBING DEMO KEYED NOTES

1. REMOVE AND DISCARD EXISTING FLOOR MOUNTED FLUSH VALVE WATERCLOSET. CUT AND CAP BACK EXISTING 1" COLD WATER SUPPLY AND 4" SANITARY WASTE AND 2" VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
2. REMOVE AND DISCARD EXISTING FLOOR MOUNTED TANK TYPE WATERCLOSET. CUT AND CAP BACK EXISTING ½" COLD WATER SUPPLY AND 4" SANITARY WASTE AND 2" VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
3. REMOVE AND DISCARD EXISTING WALL HUNG LAVATORY & FAUCET. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
4. REMOVE AND DISCARD EXISTING COUNTER MOUNTED LAVATORY & FAUCET. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
5. REMOVE AND DISCARD EXISTING WALL MOUNTED FLUSH VALVE URINAL AND CARRIER. CUT AND CAP BACK EXISTING 3/4" COLD WATER SUPPLY AND 2" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
6. REMOVE AND DISCARD EXISTING SHOWER ENCLOSURE AND VALVE SYSTEM. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
7. REMOVE AND DISCARD EXISTING WATER COOLER. CUT AND CAP BACK EXISTING ½" CW, 2" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
8. REMOVE AND DISCARD EXISTING SERVICE SINK. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
9. REMOVE AND DISCARD EXISTING FLOOR DRAIN. CUT AND CAP BACK EXISTING TP SUPPLY AND SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
10. REMOVE AND DISCARD EXISTING WALL MOUNTED HOSE BIBB. CUT AND CAP BACK EXISTING ½" COLD WATER SUPPLY LINE BACK TO EXISTING RESPECTIVE MAIN LINE.

NOTES:
VERIFY EXACT LOCATIONS OF ALL ABOVE AND BELOW GROUND DOMESTIC WATER, SANITARY WASTE & VENT, STORM DRAINAGE AND NATURAL GAS SUPPLY & MAIN PIPING IN FIELD.

PLUMBING DEMOLITION NOTES

1. PRIOR TO SUBMITTING BID, THE CONTRACTOR SHALL VISIT THE PROJECT SITE TO BECOME FAMILIAR WITH ALL EXISTING CONDITIONS AND TO DETERMINE THE EXTENT OF WORK TO REMOVE THE EXISTING PLUMBING SYSTEM COMPLETELY. IF DISCREPANCIES EXIST BETWEEN DRAWINGS AND/OR SITE CONDITIONS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE OWNER PRIOR TO SIGNING OF CONTRACT. REQUESTS FOR COMPENSATION FOR EXTRA WORK, WHICH WOULD HAVE BEEN EVIDENT BY COMPLIANCE WITH THE PREVIOUS STATEMENT, WILL NOT BE CONSIDERED.
2. DISCONNECT, DISMANTLE AND DEMOLISH ALL EXISTING PLUMBING SYSTEMS AND EQUIPMENT AS INDICATED IN THE CONTRACT DRAWINGS. REMOVE ALL DEBRIS AND DISCONNECTED EQUIPMENT AND CLEAN OUT EXISTING SPACES. REFER TO ARCHITECTURAL DEMOLITION PLANS FOR DEMOLITION WORK.
3. REMOVE ALL EXISTING DOMESTIC, SANITARY AND GAS PLUMBING SERVICES INDICATED TO BE DEMOLISHED AND CAP BACK TO RESPECTIVE EXISTING MAIN LINES TO REMAIN. REMOVE AND DISCARD EXISTING PLUMBING STACKS, MAINS, BRANCHES AND VENTS SERVING FIXTURES TO BE DEMOLISHED. OBTAIN EXISTING RECORD DRAWINGS FROM OWNER.
4. VERIFY PIPING SERVES ONLY PLUMBING FIXTURES INDICATED FOR DEMOLITION BEFORE SHUT–DOWN FOR DISCONNECTION. IDENTIFY EXISTING PIPING WHICH SERVES FIXTURES TO REMAIN. PROMPTLY NOTIFY ARCHITECT OF ACTIVE PIPING TO BE MAINTAINED WHEN LOCATED IN PARTITIONS TO BE DEMOLISHED.
5. COORDINATE ALL SHUT–DOWNS, TIE–INS, ETC., WITH THE G.C. ELECTRICAL MAKE–SAFE OF PLUMBING EQUIPMENT REQUIRING DEMOLITION SHALL BE COMPLETED BY THE ELECTRICAL SUBCONTRACTOR.
6. DEMOLITION SUBCONTRACTOR MUST PROTECT EXISTING SLAB, WALL, FENCING AND BUILDING STRUCTURE DURING DEMOLITION PHASE. DAMAGE TO EXISTING STRUCTURE SHALL BE REPAIRED AT DEMOLITION SUBCONTRACTORS EXPENSE.
7. ALL DEMOLITION WORK PERFORMED SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE NATIONAL, STATE AND LOCAL CODES, LAWS AND ORDINANCES.

1 P101 ENLARGED LATRINES DEMOLITION PLAN

Scale: 1/4" = 1'–0"

3 P101 ENLARGED CLOSET DEMOLITION PLAN

Scale: 1/4" = 1'–0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by AG

Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 DEMOLITION PLAN DOMESTIC WATER - PLUMBING

Project Number.

Drawing No.

P101

Sheet of

BUILDING 3 – EXISTING OVERALL DEMOLITION FLOOR PLAN

Scale: 1/16" = 1'-0"

1 ENLARGED LATRINES DEMOLITION PLAN

P102 Scale: 1/4" = 1'-0"

PLUMBING DEMO KEYED NOTES

1. REMOVE AND DISCARD EXISTING FLOOR MOUNTED FLUSH VALVE WATERCLOSET. CUT AND CAP BACK EXISTING 1" COLD WATER SUPPLY AND 4" SANITARY WASTE AND 2" VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
2. REMOVE AND DISCARD EXISTING FLOOR MOUNTED TANK TYPE WATERCLOSET. CUT AND CAP BACK EXISTING ½" COLD WATER SUPPLY AND 4" SANITARY WASTE AND 2" VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
3. REMOVE AND DISCARD EXISTING WALL HUNG LAVATORY & FAUCET. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
4. REMOVE AND DISCARD EXISTING COUNTER MOUNTED LAVATORY & FAUCET. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
5. REMOVE AND DISCARD EXISTING WALL MOUNTED FLUSH VALVE URINAL AND CARRIER. CUT AND CAP BACK EXISTING 3/4" COLD WATER SUPPLY AND 2" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
6. REMOVE AND DISCARD EXISTING SHOWER ENCLOSURE AND VALVE SYSTEM. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
7. REMOVE AND DISCARD EXISTING WATER COOLER. CUT AND CAP BACK EXISTING ½" CW, 2" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
8. REMOVE AND DISCARD EXISTING SERVICE SINK. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
9. REMOVE AND DISCARD EXISTING FLOOR DRAIN. CUT AND CAP BACK EXISTING TP SUPPLY AND SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
10. REMOVE AND DISCARD EXISTING WALL MOUNTED HOSE BIBB. CUT AND CAP BACK EXISTING ½" COLD WATER SUPPLY LINE BACK TO EXISTING RESPECTIVE MAIN LINE.

NOTES:
VERIFY EXACT LOCATIONS OF ALL ABOVE AND BELOW GROUND DOMESTIC WATER, SANITARY WASTE & VENT, STORM DRAINAGE AND NATURAL GAS SUPPLY & MAIN PIPING IN FIELD.

PLUMBING DEMOLITION NOTES

1. PRIOR TO SUBMITTING BID, THE CONTRACTOR SHALL VISIT THE PROJECT SITE TO BECOME FAMILIAR WITH ALL EXISTING CONDITIONS AND TO DETERMINE THE EXTENT OF WORK TO REMOVE THE EXISTING PLUMBING SYSTEM COMPLETELY. IF DISCREPANCIES EXIST BETWEEN DRAWINGS AND/OR SITE CONDITIONS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE OWNER PRIOR TO SIGNING OF CONTRACT. REQUESTS FOR COMPENSATION FOR EXTRA WORK, WHICH WOULD HAVE BEEN EVIDENT BY COMPLIANCE WITH THE PREVIOUS STATEMENT, WILL NOT BE CONSIDERED.
2. DISCONNECT, DISMANTLE AND DEMOLISH ALL EXISTING PLUMBING SYSTEMS AND EQUIPMENT AS INDICATED IN THE CONTRACT DRAWINGS. REMOVE ALL DEBRIS AND DISCONNECTED EQUIPMENT AND CLEAN OUT EXISTING SPACES. REFER TO ARCHITECTURAL DEMOLITION PLANS FOR DEMOLITION WORK.
3. REMOVE ALL EXISTING DOMESTIC, SANITARY AND GAS PLUMBING SERVICES INDICATED TO BE DEMOLISHED AND CAP BACK TO RESPECTIVE EXISTING MAIN LINES TO REMAIN. REMOVE AND DISCARD EXISTING PLUMBING STACKS, MAINS, BRANCHES AND VENTS SERVING FIXTURES TO BE DEMOLISHED. OBTAIN EXISTING RECORD DRAWINGS FROM OWNER.
4. VERIFY PIPING SERVES ONLY PLUMBING FIXTURES INDICATED FOR DEMOLITION BEFORE SHUT-DOWN FOR DISCONNECTION. IDENTIFY EXISTING PIPING WHICH SERVES FIXTURES TO REMAIN. PROMPTLY NOTIFY ARCHITECT OF ACTIVE PIPING TO BE MAINTAINED WHEN LOCATED IN PARTITIONS TO BE DEMOLISHED.
5. COORDINATE ALL SHUT-DOWNS, TIE-INS, ETC., WITH THE G.C. ELECTRICAL MAKE-SAFE OF PLUMBING EQUIPMENT REQUIRING DEMOLITION SHALL BE COMPLETED BY THE ELECTRICAL SUBCONTRACTOR.
6. DEMOLITION SUBCONTRACTOR MUST PROTECT EXISTING SLAB, WALL, FENCING AND BUILDING STRUCTURE DURING DEMOLITION PHASE. DAMAGE TO EXISTING STRUCTURE SHALL BE REPAIRED AT DEMOLITION SUBCONTRACTORS EXPENSE.
7. ALL DEMOLITION WORK PERFORMED SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE NATIONAL, STATE AND LOCAL CODES, LAWS AND ORDINANCES.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by AG

Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB ARCHITECTS
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 DEMOLITION PLAN SANITARY, WASTE & VENT - PLUMBING

Project Number.

Drawing No.

P102

Sheet of

BUILDING 3 – EXISTING OVERALL DEMOLITION FLOOR PLAN

Scale: 1/16" = 1'–0"

1 ENLARGED LATRINES DEMOLITION PLAN

P103 Scale: 1/4" = 1'–0"

PLUMBING DEMO KEYED NOTES

1. REMOVE AND DISCARD EXISTING FLOOR MOUNTED FLUSH VALVE WATERCLOSET. CUT AND CAP BACK EXISTING 1" COLD WATER SUPPLY AND 4" SANITARY WASTE AND 2" VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
2. REMOVE AND DISCARD EXISTING FLOOR MOUNTED TANK TYPE WATERCLOSET. CUT AND CAP BACK EXISTING ½" COLD WATER SUPPLY AND 4" SANITARY WASTE AND 2" VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
3. REMOVE AND DISCARD EXISTING WALL HUNG LAVATORY & FAUCET. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
4. REMOVE AND DISCARD EXISTING COUNTER MOUNTED LAVATORY & FAUCET. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
5. REMOVE AND DISCARD EXISTING WALL MOUNTED FLUSH VALVE URINAL AND CARRIER. CUT AND CAP BACK EXISTING 3/4" COLD WATER SUPPLY AND 2" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
6. REMOVE AND DISCARD EXISTING SHOWER ENCLOSURE AND VALVE SYSTEM. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND 1½" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
7. REMOVE AND DISCARD EXISTING WATER COOLER. CUT AND CAP BACK EXISTING ½" CW, 2" SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
8. REMOVE AND DISCARD EXISTING SERVICE SINK. CUT AND CAP BACK EXISTING ½" HOT & COLD WATER SUPPLY AND SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
9. REMOVE AND DISCARD EXISTING FLOOR DRAIN. CUT AND CAP BACK EXISTING TP SUPPLY AND SANITARY WASTE & VENT LINES BACK TO EXISTING RESPECTIVE MAIN LINES.
10. REMOVE AND DISCARD EXISTING WALL MOUNTED HOSE BIBB. CUT AND CAP BACK EXISTING ½" COLD WATER SUPPLY LINE BACK TO EXISTING RESPECTIVE MAIN LINE.

NOTES:
VERIFY EXACT LOCATIONS OF ALL ABOVE AND BELOW GROUND DOMESTIC WATER, SANITARY WASTE & VENT, STORM DRAINAGE AND NATURAL GAS SUPPLY & MAIN PIPING IN FIELD.

PLUMBING DEMOLITION NOTES

1. PRIOR TO SUBMITTING BID, THE CONTRACTOR SHALL VISIT THE PROJECT SITE TO BECOME FAMILIAR WITH ALL EXISTING CONDITIONS AND TO DETERMINE THE EXTENT OF WORK TO REMOVE THE EXISTING PLUMBING SYSTEM COMPLETELY. IF DISCREPANCIES EXIST BETWEEN DRAWINGS AND/OR SITE CONDITIONS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE OWNER PRIOR TO SIGNING OF CONTRACT. REQUESTS FOR COMPENSATION FOR EXTRA WORK, WHICH WOULD HAVE BEEN EVIDENT BY COMPLIANCE WITH THE PREVIOUS STATEMENT, WILL NOT BE CONSIDERED.
2. DISCONNECT, DISMANTLE AND DEMOLISH ALL EXISTING PLUMBING SYSTEMS AND EQUIPMENT AS INDICATED IN THE CONTRACT DRAWINGS. REMOVE ALL DEBRIS AND DISCONNECTED EQUIPMENT AND CLEAN OUT EXISTING SPACES. REFER TO ARCHITECTURAL DEMOLITION PLANS FOR DEMOLITION WORK.
3. REMOVE ALL EXISTING DOMESTIC, SANITARY AND GAS PLUMBING SERVICES INDICATED TO BE DEMOLISHED AND CAP BACK TO RESPECTIVE EXISTING MAIN LINES TO REMAIN. REMOVE AND DISCARD EXISTING PLUMBING STACKS, MAINS, BRANCHES AND VENTS SERVING FIXTURES TO BE DEMOLISHED. OBTAIN EXISTING RECORD DRAWINGS FROM OWNER.
4. VERIFY PIPING SERVES ONLY PLUMBING FIXTURES INDICATED FOR DEMOLITION BEFORE SHUT–DOWN FOR DISCONNECTION. IDENTIFY EXISTING PIPING WHICH SERVES FIXTURES TO REMAIN. PROMPTLY NOTIFY ARCHITECT OF ACTIVE PIPING TO BE MAINTAINED WHEN LOCATED IN PARTITIONS TO BE DEMOLISHED.
5. COORDINATE ALL SHUT–DOWNS, TIE–INS, ETC., WITH THE G.C. ELECTRICAL MAKE–SAFE OF PLUMBING EQUIPMENT REQUIRING DEMOLITION SHALL BE COMPLETED BY THE ELECTRICAL SUBCONTRACTOR.
6. DEMOLITION SUBCONTRACTOR MUST PROTECT EXISTING SLAB, WALL, FENCING AND BUILDING STRUCTURE DURING DEMOLITION PHASE. DAMAGE TO EXISTING STRUCTURE SHALL BE REPAIRED AT DEMOLITION SUBCONTRACTORS EXPENSE.
7. ALL DEMOLITION WORK PERFORMED SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE NATIONAL, STATE AND LOCAL CODES, LAWS AND ORDINANCES.

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by AG
Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB ARCHITECTS
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3 DEMOLITION PLAN DOMESTIC WATER - PLUMBING

Project Number.

Drawing No.

P103

Sheet of

BUILDING 1 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'-0"

2 ENLARGED LATRINES PLAN

P104 Scale: 1/4" = 1'-0"

PLUMBING KEYED NOTES

1. NEW WALL MOUNTED FLUSH VALVE WATERCLOSET & CARRIER: 1"CW DR, 4"S DN & 2"V DR
2. NEW COUNTER MOUNTED LAVATORY & FAUCET: 1/2"CW DR, 1/2"HW DR, 1½"W DN, 2"V DR
3. NEW WALL MOUNTED LAVATORY & FAUCET: 1/2"CW DR, 1/2"HW DR, 1½"W DN, 2"V DR
4. NEW WALL MOUNTED FLUSH VALVE URINAL & CARRIER: 3/4"CW DR, 2"S DN, 2"V DR
5. NEW SHOWER ENCLOSURE & VALVE SYSTEM: 1/2"CW DR, 1/2"HW DR, 2"W DN, 2"V DR
6. NEW FLOOR MOUNTED SERVICE SINK & FAUCET: ½"CW DR, ½"HW DR, 3"W DN, 2"V DR
7. NEW WALL MOUNTED DRINKING FOUNTAIN: 1/2"CW DR, 1½"W DN, 1½"V DR
8. NEW 2" FLOOR DRAIN: 2"W DN, 2"V DR
9. NEW WALL MOUNTED HOSE BIBB: 1/2"CW DR

NOTE:
CONNECT ALL NEW DOMESTIC WATER, SANITARY WASTE & VENT AND NATURAL GAS SUPPLY PIPING FROM NEW FIXTURES & EQUIPMENT TO EXISTING RESPECTIVE MAIN LINES. VERIFY EXACT LOCATIONS IN FIELD. TRENCH PIPING AS REQUIRED.

1 ENLARGED LATRINES PLAN

P104 Scale: 1/4" = 1'-0"

3 ENLARGED CLOSET PLAN

P104 Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by AG

Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
ber@ber-engineering.com
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1
NEW FLOOR PLAN
SANITARY, WASTE & VENT - PLUMBING

Project Number.

Drawing No.

P104

Sheet of

BUILDING 1 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'–0"

2 ENLARGED LATRINES PLAN

P105 Scale: 1/4" = 1'–0"

PLUMBING KEYED NOTES

1. NEW WALL MOUNTED FLUSH VALVE WATERCLOSET & CARRIER: 1"CW DR, 4"S DN & 2"V DR
2. NEW COUNTER MOUNTED LAVATORY & FAUCET: 1/2"CW DR, 1/2"HW DR, 1½"W DN, 2"V DR
3. NEW WALL MOUNTED LAVATORY & FAUCET: 1/2"CW DR, 1/2"HW DR, 1½"W DN, 2"V DR
4. NEW WALL MOUNTED FLUSH VALVE URINAL & CARRIER: 3/4"CW DR, 2"S DN, 2"V DR
5. NEW SHOWER ENCLOSURE & VALVE SYSTEM: 1/2"CW DR, 1/2"HW DR, 2"W DN, 2"V DR
6. NEW FLOOR MOUNTED SERVICE SINK & FAUCET: ½"CW DR, ½"HW DR, 3"W DN, 2"V DR
7. NEW WALL MOUNTED DRINKING FOUNTAIN: 1/2"CW DR, 1½"W DN, 1½"V DR
8. NEW 2" FLOOR DRAIN: 2"W DN, 2"V DR
9. NEW WALL MOUNTED HOSE BIBB: 1/2"CW DR

NOTE:
CONNECT ALL NEW DOMESTIC WATER, SANITARY WASTE & VENT AND NATURAL GAS SUPPLY PIPING FROM NEW FIXTURES & EQUIPMENT TO EXISTING RESPECTIVE MAIN LINES. VERIFY EXACT LOCATIONS IN FIELD. TRENCH PIPING AS REQUIRED.

1 ENLARGED LATRINES PLAN

P105 Scale: 1/4" = 1'–0"

3 ENLARGED CLOSET PLAN

P105 Scale: 1/4" = 1'–0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by AG

Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB Architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1
NEW FLOOR PLAN
DOMESTIC WATER
- PLUMBING

Project Number.

Drawing No.

P105

Sheet of

BUILDING 3 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'-0"

1 ENLARGED LATRINES PLAN

P106 Scale: 1/4" = 1'-0"

PLUMBING KEYED NOTES

1. NEW WALL MOUNTED FLUSH VALVE WATERCLOSET & CARRIER: 1"CW DR, 4"S DN & 2"V DR
2. NEW COUNTER MOUNTED LAVATORY & FAUCET: 1/2"CW DR, 1/2"HW DR, 1½"W DN, 2"V DR
3. NEW WALL MOUNTED LAVATORY & FAUCET: 1/2"CW DR, 1/2"HW DR, 1½"W DN, 2"V DR
4. NEW WALL MOUNTED FLUSH VALVE URINAL & CARRIER: 3/4"CW DR, 2"S DN, 2"V DR
5. NEW SHOWER ENCLOSURE & VALVE SYSTEM: 1/2"CW DR, 1/2"HW DR, 2"W DN, 2"V DR
6. NEW FLOOR MOUNTED SERVICE SINK & FAUCET: ½"CW DR, ½"HW DR, 3"W DN, 2"V DR
7. NEW WALL MOUNTED DRINKING FOUNTAIN: 1/2"CW DR, 1½"W DN, 1½"V DR
8. NEW 2" FLOOR DRAIN: 2"W DN, 2"V DR
9. NEW WALL MOUNTED HOSE BIBB: 1/2"CW DR

NOTE:
CONNECT ALL NEW DOMESTIC WATER, SANITARY WASTE & VENT AND NATURAL GAS SUPPLY PIPING FROM NEW FIXTURES & EQUIPMENT TO EXISTING RESPECTIVE MAIN LINES. VERIFY EXACT LOCATIONS IN FIELD. TRENCH PIPING AS REQUIRED.

1 END OF RUN FCO INSTALLATION

NTS

2 FLOOR DRAIN INSTALLATION (EX. SLAB)

NTS

NOTE:
TRAP TO BE INSTALLED ABOVE CEILING. PROVIDE ACCESS PANEL AS REQUIRED.

3 HUB DRAIN DIAGRAM

NTS

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by AG

Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908

Phone: (401) 272-1730
Fax: (401) 273-7156

E-mail: rgbinfo@rgb.net
www.rgb.net

RGB Architects

Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3
NEW FLOOR PLAN
SANITARY, WASTE & VENT - PLUMBING

Project Number.

Drawing No.

P106

Sheet of

BUILDING 3 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'-0"

1 ENLARGED LATRINES PLAN

P107 Scale: 1/4" = 1'-0"

PLUMBING KEYED NOTES

1. NEW WALL MOUNTED FLUSH VALVE WATERCLOSET & CARRIER: 1"CW DR, 4"S DN & 2"V DR
2. NEW COUNTER MOUNTED LAVATORY & FAUCET: 1/2"CW DR, 1/2"HW DR, 1½"W DN, 2"V DR
3. NEW WALL MOUNTED LAVATORY & FAUCET: 1/2"CW DR, 1/2"HW DR, 1½"W DN, 2"V DR
4. NEW WALL MOUNTED FLUSH VALVE URINAL & CARRIER: 3/4"CW DR, 2"S DN, 2"V DR
5. NEW SHOWER ENCLOSURE & VALVE SYSTEM: 1/2"CW DR, 1/2"HW DR, 2"W DN, 2"V DR
6. NEW FLOOR MOUNTED SERVICE SINK & FAUCET: ½"CW DR, ½"HW DR, 3"W DN, 2"V DR
7. NEW WALL MOUNTED DRINKING FOUNTAIN: 1/2"CW DR, 1½"W DN, 1½"V DR
8. NEW 2" FLOOR DRAIN: 2"W DN, 2"V DR
9. NEW WALL MOUNTED HOSE BIBB: 1/2"CW DR

NOTE:
CONNECT ALL NEW DOMESTIC WATER, SANITARY WASTE & VENT AND NATURAL GAS SUPPLY PIPING FROM NEW FIXTURES & EQUIPMENT TO EXISTING RESPECTIVE MAIN LINES. VERIFY EXACT LOCATIONS IN FIELD. TRENCH PIPING AS REQUIRED.

NOTE:
PROVIDE AND INSTALL A BALANCING VALVE ASSEMBLY (BVA) AT EACH DOMESTIC HOT WATER RETURN BRANCH LINE PRIOR TO THE CONNECTION TO THE DOMESTIC HOT WATER RETURN MAIN.

1 BALANCING VALVE ASSEMBLY DETAIL

NTS

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by AG

Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
ber@ber-engineering.com
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 3
NEW FLOOR PLAN
DOMESTIC WATER
- PLUMBING

Project Number.

Drawing No.

P107

Sheet of

NOTE:
1. FIRESTOP SEALANTS AND PIPING PENETRATIONS THROUGH FIRE RATED ASSEMBLIES SHALL COMPLY WITH THE UL FIRE RESISTANCE DIRECTORY.

1 MASONRY WALL FIRE RATED SLEEVE NTS

HANGER ROD SCHEDULE	
PIPE SIZE	ROD SIZE
UP TO 2"	3/8" DIA.
2 1/2" & 3"	1/2" DIA.
4" AND 5"	5/8"
6" – 8"	3/4"
10 & 12"	7/8"

HANGER ROD SPACING	
PIPE SIZE	MAX. ALLOWABLE SPACING
1"	7'
1 1/4"	8'
1 1/2"	9'
2"	10'
2 1/2"	11'
3" – 12"	12'

FIRE PROTECTION SYSTEMS

2 TYPICAL PIPE HANGER DIAGRAM NTS

NOTE:
REFER TO SPECIFICATION SECTION 210000 FOR SPRINKLER HEAD TYPES AND LOCATION REQUIREMENTS.

3 EXPOSED UPRIGHT SPRINKLER NTS

NOTE:
REFER TO SPECIFICATION SECTION 210000 FOR SPRINKLER HEAD TYPES AND LOCATION REQUIREMENTS.

4 PENDENT SPRINKLER RETURN BEND DROP NTS

NOTE:
REFER TO SPECIFICATION SECTION 210000 FOR SPRINKLER HEAD TYPES AND LOCATION REQUIREMENTS.

5 SPRINKLER LOCATION IN CEILING TILES NTS

FIRE PROTECTION GENERAL NOTES:

1. THE WORK COVERED CONSISTS OF FURNISHING ALL LABOR AND MATERIALS NECESSARY TO INSTALL, COMPLETE AND READY FOR CONTINUOUS OPERATION, THE FIRE PROTECTION SYSTEMS, APPARATUS AND EQUIPMENT FOR THIS PROJECT. AS SHOWN ON DRAWING, PLUS AS REQUIRED BY NFPA-13, AS REFERENCED IN THE RHODE ISLAND BUILDING & FIRE CODES AND THE AUTHORITY HAVING JURISDICTION.
2. ALL EQUIPMENT AND MATERIALS FURNISHED UNDER THE FIRE PROTECTION SUBCONTRACT, LABOR AND TESTING PERFORMED HEREIN SHALL BE IN COMPLETE ACCORDANCE WITH THE RHODE ISLAND BUILDING CODE.
3. ANY AND ALL PERMITS REQUIRED FOR INSTALLATION OF ANY MATERIAL SHALL BE OBTAINED AS PART OF THE WORK INCLUDING ALL FEES OR EXPENSES INCURRED.
4. UNLESS OTHERWISE NOTED, IT IS THE INTENT OF THESE DOCUMENTS THAT THIS AREA SHALL BE 100% SPRINKLERED.
5. ALL SPRINKLER HEADS PROTECTING LIGHT HAZARD AREAS SHALL BE QUICK RESPONSE.
6. THE SPRINKLER CONTRACTOR SHALL PERFORM A HYDRANT FLOW TEST AND SHALL BASE HIS/HER HYDRAULIC CALCULATIONS ON HIS/HER TEST RESULTS.
7. THE SPRINKLER CONTRACTOR SHALL PREPARE HIS/HERS OWN FABRICATION/WORKING DRAWINGS OF THE SPRINKLER WORK AND OBTAIN APPROVALS FROM AUTHORITIES HAVING JURISDICTION PRIOR TO INSTALLATION, AND SUBMIT TO THE ARCHITECT FOR APPROVAL.
8. ROUTING OF SPRINKLER MAINS, BRANCHES AND HEADS SHALL BE THOROUGHLY COORDINATED WITH OTHER TRADES AND BUILDING STRUCTURE PRIOR TO SUBMISSION OF COORDINATED SHOP DRAWINGS. FIRE PROTECTION CONTRACTOR IS RESPONSIBLE FOR COORDINATING, PREPARING, AND SUBMITTING COORDINATION DRAWINGS FOR APPROVAL.
9. THE FIRE PROTECTION CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL, STORAGE AND CUTTING OF ANY CEILING TILES TO ACCOMMODATE SPRINKLER HEADS. HE/SHE SHALL ALSO REINSTALL THE CEILING TILES AND REPLACE ANY DAMAGED TILES.
10. SPRINKLER HEADS IN AREAS WITH NO FINISHED CEILING SHALL BE LOCATED AS HIGH AS POSSIBLE. HEADS SUBJECT TO PHYSICAL DAMAGE SHALL BE INSTALLED WITH PROTECTIVE CAGES.
11. PATCH PIPE CORES WHERE FIRE PROTECTION PIPING HAS BEEN INSTALLED. PAINT PATCH WORK TO MATCH SURFACES.
12. THESE DRAWINGS ARE DIAGRAMMATIC AND ARE NOT INTENDED TO SHOW EACH AND EVERY OFFSET WITH REGARD TO THE PIPING THAT IS TO BE INSTALLED. THE CONTRACTOR SHALL VISIT THE SITE, READ ALL DRAWINGS, AND MAKE DETAILED NOTES OF ALL NECESSARY OFFSETS REQUIRED WITH THE INSTALLATION OF HIS/HER WORK. NO EXTRA PAYMENT WILL BE ALLOWED FOR ADDITIONAL WORK CAUSED BY UNFAMILIARITY WITH SITE AND PROJECT CONDITIONS.
13. THE FIRE PROTECTION CONTRACTOR IS RESPONSIBLE TO PROVIDE A COMPLETE SET OF SHOP DRAWINGS AND HYDRAULIC CALCULATIONS WHICH SHALL BEAR THE SEAL OF A FIRE PROTECTION ENGINEER DULY LICENSED IN THE STATE OF RHODE ISLAND.
14. CONTRACTOR IS TO CLEAN/FLUSH ENTIRE SYSTEM BACK TO THE STREET WATER MAIN.
15. AT THE COMPLETION, TEST ENTIRE SYSTEM PER NFPA-13, AND NFPA-25. FILE ALL REPORTS AND CERTIFICATIONS. SUBMIT TO OWNER COPIES OF ALL REPORTS AND CERTIFICATIONS, TOGETHER WITH A COPY OF NFPA-25.
16. INSTRUCT THE OWNER ON MAINTENANCE PROCEDURES AND SYSTEM OPERATION.
17. SUBMIT ACCURATE AS-BUILT DRAWINGS.
18. PROVIDE PROPER SEISMIC RESTRAINTS FOR ALL REQUIRED FIRE PROTECTION PIPING PER NFPA AND LOCAL BUILDING CODES.
19. PRESSURE TEST ALL PIPING AND ALARMS PER NFPA.
20. WHERE ALL SPRINKLER PIPING IS EXPOSED, COORDINATE PAINTING PIPING AND SPRINKLER HEADS WITH ARCHITECT. REFER TO SPECIFICATION SECTION 099100 "PAINTING".
21. WHERE EXTERIOR CANOPIES REQUIRE SPRINKLER PROTECTION PER NFPA, PROVIDE DRY TYPE SPRINKLERS OFF OF WET SPRINKLER SYSTEM.
22. INSTALL ALL PENDENT SPRINKLERS LOCATED ON SUSPENDED CEILINGS ON CENTER OF CEILING TILES BOTH WAYS. IF SPRINKLERS ARE LOCATED IN GYPSUM CEILINGS, INSTALL AND ALIGN HORIZONTALLY AND VERTICALLY WITH LIGHT FIXTURES AS MUCH AS POSSIBLE SPACING REQUIREMENTS ALLOW.
23. PROVIDE SPRINKLER PROTECTION UNDER EXPOSED DUCTWORK 4'-0" WIDE OR GREATER.

FIRE PROTECTION LEGEND

	NEW WORK PIPING (INDICATED AS HEAVY LINE)
ETR	EXISTING TO REMAIN (INDICATED AS LIGHT LINE)
RE	EXISTING PIPING & EQUIPMENT TO BE REMOVED
CTE	CONNECT TO EXISTING
F	FIRE SERVICE BELOW GRADE OR BURIED
WS	WET SPRINKLER PIPE
D	SPRINKLER DRAIN
FDC	FIRE DEPARTMENT CONNECTION PIPE
	PIPE TEE LOOKING UP
	PIPE TEE LOOKING UP
UP	PIPE ELBOW UP
DN/DR	PIPE ELBOW DOWN OR DROP
CONT	CONTINUATION
	FLOW IN DIRECTION OF ARROW
UN	UNION
PG	PRESSURE GAUGE WITH PETCOCK
FS	FLOW SWITCH
CV	CHECK VALVE
GV	GATE VALVE
TS	GATE VALVE WITH TAMPER SWITCH
PRV	PRESSURE REDUCING/REGULATING VALVE
OS&Y W/TS	OS & Y GATE VALVE WITH TAMPER SWITCH
BV W/TS	BALL VALVE WITH TAMPER SWITCH
VIV	VALVE IN VERTICAL
VIV W/TS	VALVE IN VERTICAL WITH TAMPER SWITCH
WACV	ALARM CHECK VALVE (WET SYSTEM)
PIV W/TS	POST INDICATOR VALVE W/TAMPER SWITCH
DCVA	HORIZONTAL DOUBLE CHECK VALVE ASSEMBLY
WTS	WATER TIGHT SLEEVE
DV	DRAIN VALVE WITH HOSE END
SC	SIAMESE FIRE DEPT. CONNECTION
U	UPRIGHT WET SPRINKLER
P	RECESSED PENDENT WET SPRINKLER
IP	INSTITUTIONAL PENDENT WET SPRINKLER
S	SIDEWALL WET SPRINKLER
SG	SIDEWALL WET SPRINKLER W/ GUARD
IS	INTUITIONAL SIDEWALL WET SPRINKLER
UG	UPRIGHT W/ GUARD
PG	PENDENT WET SPRINKLER W/ GUARD
TYP	TYPICAL
EX	EXISTING
AFF	ABOVE FINISHED FLOOR
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
LFPC	LIMIT OF FIRE PROTECTION CONTRACT
NFPC	NOT IN FIRE PROTECTION CONTRACT
GC	GENERAL CONTRACTOR
FPC	FIRE PROTECTION CONTRACTOR
PC	PLUMBING CONTRACTOR
EC	ELECTRICAL CONTRACTOR
HVAC	HVAC CONTRACTOR
FI	FURNISH & INSTALL
FFE	FINISHED FLOOR ELEVATION
VIF	VERIFY IN FIELD

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

Drawn by AG
Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project
RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status
ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents
LEGEND, NOTES & DETAILS
-FIRE PROTECTION

Project Number.

Drawing No.
FP001

Sheet of

BUILDING 1 – EXISTING OVERALL DEMOLITION FLOOR PLAN

Scale: 1/16" = 1'–0"

2 ENLARGED LATRINES DEMOLITION PLAN

FP100 Scale: 1/4" = 1'–0"

1 ENLARGED LATRINES DEMOLITION PLAN

FP100 Scale: 1/4" = 1'–0"

3 ENLARGED CLOSET DEMOLITION PLAN

FP100 Scale: 1/4" = 1'–0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by AG

Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1 DEMOLITION PLAN - FIRE PROTECTION

Project Number.

Drawing No.

FP100

Sheet of

BUILDING 1 – OVERALL FLOOR PLAN

Scale: 1/16" = 1'-0"

2 ENLARGED LATRINES PLAN

FP101 Scale: 1/4" = 1'-0"

1 ENLARGED LATRINES PLAN

FP101 Scale: 1/4" = 1'-0"

3 ENLARGED CLOSET PLAN

FP101 Scale: 1/4" = 1'-0"

This drawing is copyrighted and is subject to copyright protection as an "architectural work" under 17 U. S. C. Sec. 101 et seq. The protection includes but is not limited to the overall form as well as the arrangement and composition of spaces, materials, color and elements in the design. Under such protection, unauthorized use of this drawing may result in the cessation of construction or buildings being seized and/or monetary compensation being awarded to The Robinson Green Beretta Corporation (RGB).

Any reproduction, possession, or use of this drawing or any part thereof without the express written permission of RGB, is prohibited. Violators will be prosecuted to the full extent of the law.

© RGB 2017

Certification

STEVEN A. KARAN
No. 6537
REGISTERED PROFESSIONAL ENGINEER (MECHANICAL)

Drawn by AG

Checked by ARV

Revised on

B|E|R
BUILDING ENGINEERING RESOURCES, INC.
66 Main Street
N. Easton, MA 02356
T 508.230.0260
F 508.230.0265
ber@ber-engineering.com
100 Midway Road - Suite 23
Cranston, RI 02920
T 401.942.3500
F 401.228.6205
www.ber-engineering.com

50 Holden Street
Providence, Rhode Island 02908
Phone: (401) 272-1730
Fax: (401) 273-7156
E-mail: rgbinfo@rgb.net
www.rgb.net
RGB architects
Architecture · Project Management · Interior Design

Project

RHODE ISLAND ARMY NATIONAL GUARD

WARWICK LATRINES MODERNIZATION

541 AIRPORT ROAD, WARWICK, RI 02886

Drawing Status

ISSUED FOR CONSTRUCTION

Issued On 20 MARCH 2018

Sheet Contents

BUILDING 1
NEW FLOOR PLAN
- FIRE PROTECTION

Project Number.

Drawing No.

FP102

Sheet of