

March 20, 2020

STATE OF RHODE ISLAND AND PROVIDENCE PLANTATION
DEPARTMENT OF ADMINISTRATION

DIVISION OF PURCHASES BID NO. 7602817

RHODE ISLAND DEPARTMENT OF TRANSPORTATION

RHODE ISLAND CONTRACT NO.2020-CB-023

FEDERAL-AID PROJECT NO. FAP Nos: BRO-0673(002)

Bridge Group 43A - Mohegan

Broncos Highway Sta. 262+50 to Sta. 271+00

CITY/TOWN OF Burrillville

COUNTY OF PROVIDENCE

NOTICE TO PROSPECTIVE BIDDERS

ADDENDUM NO. 2 Prospective bidders and all concerned are hereby notified of the following changes in the Plans, Specifications, Proposal and Distribution of Quantities for this contract. These changes shall be incorporated in the Plans, Specifications, Proposal and Distribution of Quantities, and shall become an integral part of the Contract Documents.

A. Distribution of Quantities

1. Addendum No. 1 Distribution of Quantities Changes

Quantities were revised in the Addendum No. 1 Quest Lite Bid file whose descriptions were not included in the addendum cover letter. Below are the Addendum No. 1 Distribution of Quantities changes.

2. Table of Contents

Remove Index pages 1 through 3 in their entirety and replace them with revised pages 1 (R-1) through 3 (R-1) attached to this Addendum No. 2. The Index has been revised.

3. Pages 4 and 5

Remove pages 4 and 5 in their entirety and replace them with revised pages 4 (R-1) and 5 (R-1) attached to this Addendum No. 2. Item Code 204.0100 "Trimming and Fine Grading" has been revised.

4. Pages 6 through 8


Remove pages 6 through 8 in their entirety and replace them with revised pages 6 (R-1) through 8 (R-1) and insert new page 7a attached to this Addendum No. 2. Item Codes 302.0100 "Gravel Borrow Subbase Course", 401.1000 "Class 19.0 HMA", and 401.2100 "Modified Class 12.5 HMA" have been revised.

5. Page 17

Remove page 17 in its entirety and replace them with revised page 17 (R-1) attached to this Addendum No. 2. Item Code 906.0602 "Bituminous Berm Standard 7.5.1" has been revised.

6. Pages 23 and 24

Remove pages 23 and 24 in their entirety and replace them with revised pages 23 (R-1) and 24 (R-1) attached to this Addendum No. 2. Item Code 932.0200 "Full-Depth Sawcut of Bituminous Pavement" has been revised.



RI Department of Transportation

Administrator, Division of Project Management

Table of Contents - Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
R.I. Contract No. - 2020-CB-023
FAP Nos: BRO-0673(002)

ItemCode	Description	Page
201.0402	REMOVE AND DISPOSE CONCRETE CURB	1
201.0409	REMOVE AND DISPOSE FLEXIBLE PAVEMENT	1
201.0415	REMOVE AND DISPOSE GUARDRAIL AND POST ALL TYPES	1
201.0419	REMOVE AND DISPOSE FENCE	1
201.0428	REMOVE AND DISPOSE FRAME AND GRATE OR FRAME AND COVER	2
201.0610	REMOVE AND DISPOSE DIRECTIONAL, WARNING, REGULATORY, SERVICE, AND STREET SIGNS	2
201.9905	REMOVE AND SALVAGE TRAFFIC SIGNAL EQUIPMENT	3
202.0100	EARTH EXCAVATION	3
202.0700	COMMON BORROW	3
203.0100	STRUCTURAL EXCAVATION EARTH	3
203.0650	CRUSHED STONE FILL UNDER STRUCTURES	3
203.0700	PERVIOUS FILL	4
204.0100	TRIMMING AND FINE GRADING	4
206.0312	COMPOST FILTER SOCK 12 INCH DIAMETER	5
209.0200	SACK INSERT CATCH BASIN INLET PROTECTION	5
211.9901	CONSTRUCTION ACCESS - PIER RECONSTRUCTION	6
212.2100	MAINTENANCE AND CLEANING OF EROSION AND POLLUTION CONTROLS	6
213.0100	PLACEMENT OF MILLINGS BENEATH GUARDRAIL	6
302.0100	GRAVEL BORROW SUBBASE COURSE	6
401.1000	CLASS 19.0 HMA	7
401.2100	MODIFIED CLASS 12.5 HMA	7
401.3000	CLASS 9.5 HMA	8
403.0300	ASPHALT EMULSION TACK COAT	8
410.1000	TEMPORARY PATCHING MATERIAL/TRENCHES	8
701.9901	6-INCH PVC PRESSURE PIPE AND FITTINGS	9
701.9902	8-INC PVC PIPE AND FITTINGS	9
701.9903	8-INCH STEEL GRAVITY SEWER AND 6-INCH STEEL FORCE MAIN ACROSS THE MOHEGAN BRIDGE NO. 673	9
701.9904	6-INCH FLEXIBLE COUPLING	9
701.9905	8-INCH FLEXIBLE COUPLING	9
701.9906	TEMPORARY SEWER BYPASS PUMPING AND PIPING SYSTEMS	10
702.0515	FRAME AND GRATE HIGH CAPACITY STANDARD 6.3.3	10
702.0533	PRECAST CONCRETE APRON STONE 38'' STANDARD 7.1.8	10
702.9901	SAND FILTER AND SEDIMENT FOREBAY NORTH	10
702.9902	SAND FILTER AND SEDIMENT FOREBAY SOUTH	11
702.9903	PRECAST 4'-0" ROUND SEWER MANHOLE (BURRILLVILLE)	11
702.9904	SEWER MANHOLE FRAME AND COVER (BURRILLVILLE)	11
702.9907	FORCE MAIN LEAKAGE TEST	11
702.9910	SEWER MANHOLE FRAME AND COVER BURRILLVILLE STANDARD	11
702.9911	PRECAST SEWER MANHOLE 4' DIAMETER BURRILLVILLE STANDARD	12
707.1000	ADJUST SANITARY MANHOLE	12
707.1100	ADJUST CATCH BASINS	12
708.9040	CLEANING AND FLUSHING PIPE ALL SIZES	12
708.9041	CLEANING CATCH BASINS ALL TYPES AND SIZES	13
708.9042	CLEANING MANHOLES ALL TYPES AND SIZES	13
711.0110	3'' PAVED WATERWAY CLASS I-1 STANDARD 8.4.0	13
800.9901	MOHEGAN BRIDGE NO. 673	14
803.9901	REMOVE AND DISPOSE EXISTING MOHEGAN BRIDGE NO. 673	14
804.9901	PILOT BORING PROGRAM	14
817.2112	REPAIRS TO STRUCTURE CONCRETE MASONRY - PATCHING MORTAR	14
817.2142	REPAIRS TO STRUCTURE CONCRETE MASONRY - FORM AND CAST IN PLACE CONCRETE	14

Table of Contents - Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
R.I. Contract No. - 2020-CB-023
FAP Nos: BRO-0673(002)

ItemCode	Description	Page
824.9901	TEMPORARY JACKING AND SHORING OF PIER CAP	15
841.9901	DRILLED SHAFT - FURNISH AND INSTALL	15
841.9902	DRILLED SHAFT - OBSTRUCTION REMOVAL	15
901.0101	GUARDRAIL STEEL BEAM SINGLE FACE EARTH AND ASPHALT	15
901.0185	STEEL THRIE BEAM BRIDGE CONNECTION	15
901.9901	RADIUS GUARDRAIL STEEL BEAM SINGLE FACE EARTH AND ASPHALT	16
901.9903	GUARDRAIL END TREATMENT MASH COMPLIANT TL-2	16
903.0206	CHAIN LINK FENCE 6' STD 31.2.0	16
903.0410	TEMPORARY CHAIN LINK FENCE	16
906.0210	CEMENT CONCRETE CURB PRECAST STRAIGHT STANDARD 7.1.0	16
906.0221	6' PRECAST CONCRETE TRANSITION CURB STANDARD 7.1.2	17
906.0602	BITUMINOUS BERM STANDARD 7.5.1	17
907.0100	WATER FOR DUST CONTROL	17
914.5010	FLAGPERSONS	17
914.5020	FLAGPERSONS - OVERTIME	18
916.0600	SHOCK ABSORBING BARRIER MODULES	18
919.0101	TEST PITS	18
920.0040	DUMPED STONE RIPRAP R-3, R-4, R-5 STANDARD 8.3.0	18
920.0130	BEDDING FOR RIPRAP FS-1 STANDARD 8.3.0	18
920.0200	FILTER FABRIC FOR RIP-RAP	19
922.0100	TEMPORARY CONSTRUCTION SIGNS STANDARD 29.1.0 AND 27.1.1	19
923.0105	DRUM BARRICADE STANDARD 26.2.0	21
923.0120	PLASTIC PIPE BARRICADE STANDARD 26.3.0	22
923.0200	FLUORESCENT TRAFFIC CONES STANDARD 26.1.0	22
925.0112	PORTABLE CHANGEABLE MESSAGE SIGN	22
926.0140	REFLECTIVE DELINEATORS FOR TEMPORARY CONCRETE BARRIERS	22
926.0200	ANCHORED BARRIER FOR TEMPORARY TRAFFIC CONTROL	22
926.9901	TEMPORARY BARRIER (TL-3)	23
929.0110	FIELD OFFICE	23
931.0110	CLEANING AND SWEEPING PAVEMENT	23
932.0100	CUTTING AND MATCHING ASPHALT	23
932.0200	FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT	23
935.0400	REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING	24
936.0100	MOBILIZATION AND DEMOBILIZATION	24
937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	24
943.0200	TRAINEE MAN-HOURS	24
L01.0104	PLANTABLE SOIL 4 INCHES DEEP	24
L02.0101	GENERAL HIGHWAY SEEDING (TYPE 1)	25
L08.0109	TREE TRIMMING	25
L09.9901	SELECTIVE CLEARING FOR CONSTRUCTION ACCESS AT BRIDGE NO. 673	25
T04.5001	6 AWG SINGLE CONDUCTOR CABLE 600V INSULATION	26
T04.5305	14 AWG 5 CONDUCTOR CABLE	26
T04.5309	14 AWG 9 CONDUCTOR CABLE	26
T04.9902	VIDEO DETECTION SYSTEM CABLE	26
T06.2020	2 IN. RIGID STEEL CONDUIT-OVERHEAD	27
T06.2030	3 IN. RIGID STEEL CONDUIT-OVERHEAD	27
T11.6006	SPAN AND MESSENGER WIRES 6/16	27
T11.9901	TRAFFIC SIGNAL STANDARD WOOD 40 FEET	27
T12.0004	ACTUATED CONTROLLER TS-2, TYPE 1 W/4 PHASE ASSEMBLY POLE MOUNTED INCLUDING CABINET STD. 19.1.1	27
T12.9150	METER SOCKET W/MANUAL BY-PASS	28
T12.9903	MAINTENANCE OF TEMPORARY SIGNAL SYSTEM	28
T13.9901	VIDEO DETECTION SYSTEM CAMERA	28

Table of Contents - Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

ItemCode	Description	Page
T13.9902	VIDEO DETECTION SYSTEM HARDWARE	28
T14.3413	1 WAY 3 SECTION SPAN MOUNTED SIGNAL HEAD 12 INCH	28
T14.3423	2 WAY 3 SECTION SPAN MOUNTED SIGNAL HEAD 12 INCH	29
T14.3613	1 WAY 3 SECTION BRACKET MOUNTED SIGNAL HEAD 12 INCH	29
T15.0100	DIRECTIONAL REGULATORY AND WARNING SIGNS	29
T15.1000	STREET SIGN ASSEMBLY STD. 24.6.1	30
T20.0706	6 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS	31
T20.0712	12 INCH WHITE WATERBORNE PAINT PAVEMENT MARKINGS	31
T20.0904	4 INCH YELLOW WATERBORNE PAINT PAVEMENT MARKINGS	32
T20.2406	6 INCH WHITE FINAL EPOXY RESIN PAVEMENT MARKINGS	32
T20.2412	12 INCH WHITE FINAL EPOXY RESIN PAVEMENT MARKINGS	33
T20.2506	6 INCH WHITE INTERIM EPOXY RESIN PAVEMENT MARKINGS	33
T20.2512	12 INCH WHITE INTERIM EPOXY RESIN PAVEMENT MARKINGS	33
T20.2804	4 INCH YELLOW FINAL EPOXY RESIN PAVEMENT MARKINGS	34
T20.2904	4 INCH YELLOW INTERIM EPOXY RESIN PAVEMENT MARKINGS	34
T20.2906	6 INCH YELLOW INTERIM EPOXY RESIN PAVEMENT MARKINGS	34
T20.3401	FINAL EPOXY RESIN PAVEMENT MARKING SYMBOL - ARROW (STRAIGHT, LEFT, RIGHT OR COMBINED) STANDARD 20.1.0	35
T20.3501	INTERIM EPOXY RESIN PAVEMENT MARKING SYMBOL - ARROW (STRAIGHT, LEFT, RIGHT OR COMBINED) STANDARD 20.1.0	35
T20.4506	REMOVE PAVEMENT MARKING LINE - LESS THAN OR EQUAL TO 6 INCHES WIDE	35
T20.4508	REMOVE PAVEMENT MARKING LINE - GREATER THAN 6 INCHES WIDE	36
T20.4511	REMOVE PAVEMENT MARKING SYMBOL - ARROW (STRAIGHT, LEFT, RIGHT OR COMBINED)	36

Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
011	203.0650	Cont.				
				Item 203.0650 Total:		
				10.00		
012	203.0700	PERVIOUS FILL	CY			
		MOHEGAN BRIDGE NO. 673				
		MOHEGAN BRIDGE NO. 673		60.00	0014	01
				Item 203.0700 Total:		
				60.00		
013	204.0100	TRIMMING AND FINE GRADING	SY			
		BRONCOS HIGHWAY (BERMB)				
		268+01, 29' LT TO 271+00,		78.88	0014	01
		22' LT (BERMB)				
		268+02, 36' RT TO 271+00,		78.61	0014	01
		24' RT (BERMB)				
		BRONCOS HIGHWAY (PAVE1)				
		263+40 TO 264+20 (PAVE1)		398.00	0014	01
		266+46 TO 267+00 (PAVE1)		269.00	0014	01
		BRONCOS HIGHWAY (PSOIL)				
		262+12 LT TO BRIDGE (PSOIL)		383.00	0014	01
		262+30 RT TO BRIDGE (PSOIL)		296.00	0014	01
		BRIDGE NE TO DOUGLAS		284.00	0014	01
		TURNPIKE (PSOIL)				
		BRIDGE SE TO DOUGLAS		515.00	0014	01
		TURNPIKE (PSOIL)				
		DOUGLAS TURNPIKE TO 271+00		416.00	0014	01
		LT (PSOIL)				
		DOUGLAS TURNPIKE TO 271+00		651.00	0014	01
		RT (PSOIL)				
		MOHEGAN BRIDGE (8.3.0)				
		STA 265+60, 42' RT (8.3.0)		9.00	0014	01
		STA 269+05 LT (8.3.0)		10.00	0014	01
		STA 269+05 RT (8.3.0)		45.00	0014	01
		MOHEGAN BRIDGE (8.4.0)				
		STA 265+60 TO 266+00, 42' RT		27.00	0014	01

Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
013	204.0100	Cont.	(8.4.0)			
		STA 269.05 RT (8.4.0)		4.50	0014	01
		STA 269+05 LT (8.4.0)		4.50	0014	01
		QUANTITY				
		ROUNDING		0.85	0014	01
Item 204.0100 Total:				3,470.34		
014	206.0312	COMPOST FILTER SOCK 12 INCH DIAMETER	LF			
		MOHEGAN BRIDGE NO. 673				
		STA 262+12, 37' LT - 262+30, 31 RT		560.00	0014	01
		STA 265+49, 45' RT - 267+80, 218 RT		360.00	0014	01
		STA 265+60, 25' RT TO 267+80, 218' RT TO 267+50, 80' RT TO 266+23, 25' RT		680.00	0014	01
		STA 266+10, 28' LT - 267+14, 108 LT		180.00	0014	01
		STA 266+30, 40' RT - 267+62, 78 Rt		300.00	0014	01
		STA 271+00 LT TO DOUGLAS TURNPIKE		430.00	0014	01
		STA 271+00 RT TO DOUGLAS TURNPIKE		425.00	0014	01
Item 206.0312 Total:				2,935.00		
015	209.0200	SACK INSERT CATCH BASIN INLET PROTECTION	EACH			
		MOHEGAN BRIDGE NO. 673				
		STA 263+50 LT		1.00	0014	01
		STA 263+50 RT		1.00	0014	01
		STA 266+75 LT		1.00	0014	01

Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
015	209.0200	Cont.				
		STA 266+85 RT		1.00	0014	01
		STA 267+20 LT		1.00	0014	01
		STA 267+57 LT		1.00	0014	01
Item 209.0200 Total:				6.00		
016	211.9901	CONSTRUCTION ACCESS - PIER	LS			
		RECONSTRUCTION				
		MOHEGAN BRIDGE NO. 673				
		MOHEGAN BRIDGE NO. 673		1.00	0014	01
Item 211.9901 Total:				1.00		
017	212.2100	MAINTENANCE AND CLEANING OF	LS			
		EROSION AND POLLUTION CONTROLS				
		MOHEGAN BRIDGE NO. 673				
		PER SPECIFICATIONS		1.00	0014	01
Item 212.2100 Total:				1.00		
018	213.0100	PLACEMENT OF MILLINGS BENEATH	LF			
		GUARDRAIL				
		MOHEGAN BRIDGE NO. 673				
		STA 262+50, 24' RT - 264+20,		170.00	0014	01
		24 RT				
		STA 262+50, 30' LT - 264+20,		170.00	0014	01
		23 LT				
		STA 266+55, 24' LT - 267+16,		132.00	0014	01
		108 LT				
		STA 266+55, 24' RT - 267+55,		140.00	0014	01
		83' RT				
Item 213.0100 Total:				612.00		
019	302.0100	GRAVEL BORROW SUBBASE COURSE	CY			
		BRONCOS HIGHWAY (BERMB)				
		268+01, 29' LT TO 271+00,		26.29	0014	01

Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
019	302.0100	Cont.				
		22' LT (BERMB)				
		268+02, 36' RT TO 271+00,		26.20	0014	01
		24' RT (BERMB)				
		BRNCOS HIGHWAY (PAVE1)				
		263+40 TO 264+20 (PAVE1)		132.67	0014	01
		266+46 TO 267+00 (PAVE1)		89.67	0014	01
		MOHEGAN BRIDGE (8.4.0)				
		STA 265+60 TO 266+00, 42' RT		4.50	0014	01
		(8.4.0)				
		STA 269.05 RT (8.4.0)		0.75	0014	01
		STA 269+05 LT (8.4.0)		0.75	0014	01
		QUANTITY				
		ROUNDING		0.97	0014	01
Item 302.0100 Total:				281.80		
020	401.1000	CLASS 19.0 HMA	TON			
		BRNCOS HIGHWAY (BERMB)				
		268+01, 29' LT TO 271+00,		26.30	0014	01
		22' LT (BERMB)				
		268+02, 36' RT TO 271+00,		26.21	0014	01
		24' RT (BERMB)				
		BRNCOS HIGHWAY (PAVE1)				
		263+40 TO 264+20 (PAVE1)		194.42	0014	01
		266+46 TO 267+00 (PAVE1)		131.41	0014	01
		QUANTITY				
		ROUNDING		0.17	0014	01
Item 401.1000 Total:				378.51		
021	401.2100	MODIFIED CLASS 12.5 HMA	TON			
		BRNCOS HIGHWAY (BERMA)				
		262+50 TO 263+40 LT (BERMA)			0014	01
		262+50 TO 263+40 RT (BERMA)			0014	01
		BRNCOS HIGHWAY (BERMB)				

Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
021	401.2100	Cont.				
		268+01, 29' LT TO 271+00,		13.60	0014	01
		22' LT (BERMB)				
		268+02, 36' RT TO 271+00,		13.56	0014	01
		24' RT (BERMB)				
		BRONCOS HIGHWAY (MICRO)				

Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
021	401.2100	Cont.				
		262+50 TO 263+40 (MICRO)		62.84	0014	01
		267+00 TO 268+25 (MICRO)		179.09	0014	01
		BRONCOS HIGHWAY (PAVE1)				
		263+40 TO 264+20 (PAVE1)		51.47	0014	01
		266+46 TO 267+00 (PAVE1)		34.78	0014	01
		QUANTITY				
		ROUNDING		0.06	0014	01
Item 401.2100 Total:				355.40		
022	401.3000	CLASS 9.5 HMA	TON			
		MOHEGAN BRIDGE (8.4.0)				
		STA 265+60 TO 266+00, 42' RT		5.04	0014	01
		(8.4.0)				
		STA 269.05 RT (8.4.0)		0.84	0014	01
		STA 269+05 LT (8.4.0)		0.84	0014	01
		QUANTITY				
		ROUNDING		0.28	0014	01
Item 401.3000 Total:				7.00		
023	403.0300	ASPHALT EMULSION TACK COAT	SY			
		BRONCOS HIGHWAY (MICRO)				
		262+50 TO 263+40 (MICRO)		486.00	0014	01
		267+00 TO 268+25 (MICRO)		1,385.00	0014	01
		BRONCOS HIGHWAY (PAVE1)				
		263+40 TO 264+20 (PAVE1)		796.00	0014	01
		266+46 TO 267+00 (PAVE1)		538.00	0014	01
Item 403.0300 Total:				3,205.00		
024	410.1000	TEMPORARY PATCHING	TON			
		MATERIAL/TRENCHES				
		MOHEGAN BRIDGE				
		CONSTRUCTION		6.00	0014	01
Item 410.1000 Total:				6.00		

Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
060	906.0210	Cont.				
		22' LT				
		STA 266+55, 23' RT - 266+82,		30.00	0014	01
		23' RT				
Item 906.0210 Total:				170.00		
061	906.0221	6' PRECAST CONCRETE TRANSITION	EACH			
		CURB STANDARD 7.1.2				
		BRONCOS HIGHWAY				
		263+40 TO 263+46 LT		1.00	0014	01
		263+40 TO 263+46 RT		1.00	0014	01
		266+75 TO 266+81 LT		1.00	0014	01
		266+86 TO 266+92 RT		1.00	0014	01
		267+20, 45' LT		2.00	0014	01
Item 906.0221 Total:				6.00		
062	906.0602	BITUMINOUS BERM STANDARD 7.5.1	LF			
		BRONCOS HIGHWAY (BERMA)				
		262+50 TO 263+40 LT (BERMA)			0014	01
		262+50 TO 263+40 RT (BERMA)			0014	01
		BRONCOS HIGHWAY (BERMB)				
		268+01, 29' LT TO 271+00,		284.00	0014	01
		22' LT (BERMB)				
		268+02, 36' RT TO 271+00,		283.00	0014	01
		24' RT (BERMB)				
Item 906.0602 Total:				567.00		
063	907.0100	WATER FOR DUST CONTROL	MGAL			
		MOHEGAN BRIDGE NO. 673				
		PER SPECIFICATIONS		14.00	0014	01
Item 907.0100 Total:				14.00		
064	914.5010	FLAGPERSONS	MHRS			
		MOHEGAN BRIDGE NO. 673				

Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
078	926.9901	TEMPORARY BARRIER (TL-3)	LF			
		MOHEGAN BRIDGE				
		MPT STAGE 1		180.00	0014	01
		MPT STAGE 2		130.00	0014	01
Item 926.9901 Total:				310.00		
079	929.0110	FIELD OFFICE	PMO			
		MOHEGAN BRIDGE NO. 673				
		PER SPECIFICATIONS		34.00	0014	01
Item 929.0110 Total:				34.00		
080	931.0110	CLEANING AND SWEEPING PAVEMENT	HSY			
		MOHEGAN BRIDGE				
		CONSTRUCTION		300.00	0014	01
Item 931.0110 Total:				300.00		
081	932.0100	CUTTING AND MATCHING ASPHALT	LF			
		MOHEGAN BRIDGE NO. 673				
		STA 262+50, 30' LT - 24 RT		54.00	0014	01
		STA 267+25, 80' LT - 267+53, 83' LT		28.00	0014	01
		STA 267+61, 77' RT - 267+89, 71' RT		28.00	0014	01
		STA 268+25 - 271+00 LT		275.00	0014	01
		STA 268+25 - 271+00 RT		275.00	0014	01
		STA 268+25 LT-RT		50.00	0014	01
Item 932.0100 Total:				710.00		
082	932.0200	FULL-DEPTH SAWCUT OF BITUMINOUS PAVEMENT	LF			
		BRONCOS HIGHWAY (BERMB)				
		268+01, 29' LT TO 271+00, 22' LT (BERMB)		284.00	0014	01

Distribution of Quantities

Project Name - Bridge Group 43A - Mohegan
 Estimate Name - Bridge Group 43A - Mohegan (Addendum 1)
 R.I. Contract No. - 2020-CB-023
 FAP Nos: BRO-0673(002)

Item No.	Item Code	Description	UM	Qty.	Pay Code	Seq. No.
082	932.0200	Cont.		283.00	0014	01
		268+02, 36' RT TO 271+00, 24' RT (BERMB)				
		MOHEGAN BRIDGE NO. 673				
		STA 263+41, 25' LT - 23' RT		48.00	0014	01
		STA 267+00, 28' LT - 23' RT		51.00	0014	01
Item 932.0200 Total:				666.00		
083	935.0400	REMOVING BITUMINOUS PAVEMENT BY MICRO MILLING	SY			
		BRONCOS HIGHWAY (MICRO)				
		262+50 TO 263+40 (MICRO)		486.00	0014	01
		267+00 TO 268+25 (MICRO)		1,385.00	0014	01
Item 935.0400 Total:				1,871.00		
084	936.0100	MOBILIZATION AND DEMOBILIZATION	LS			
		MOHEGAN BRIDGE NO. 673				
		PER SPECIFICATIONS		1.00	0014	01
Item 936.0100 Total:				1.00		
085	937.0200	MAINTENANCE AND MOVEMENT TRAFFIC PROTECTION	LS			
		MOHEGAN BRIDGE NO. 673				
		MPT		1.00	0014	01
Item 937.0200 Total:				1.00		
086	943.0200	TRAINEE MAN-HOURS	MHRS			
		MOHEGAN BRIDGE NO. 673				
		PER SPECIFICATIONS		1,300.00	0014	01
Item 943.0200 Total:				1,300.00		
087	L01.0104	PLANTABLE SOIL 4 INCHES DEEP	SY			
		BRONCOS HIGHWAY (PSOIL)				
		262+12 LT TO BRIDGE (PSOIL)		383.00	0014	01