3.11.2.6. **Temporary Barrier**

The DB Entity shall provide all Temporary Barrier required for the Project. All barrier shall be placed such that no blunt ends are exposed to traffic. If blunt ends are required, approved impact attenuation devices must be installed and maintained at all times. Barrier installed on bridges with a drop off must be anchored as approved by the Engineer. Temporary Barrier shall meet the requirements of RIDOT's Standard Specifications for Road and Bridge Construction, RIDOT Standard Details and AASHTO's Roadside Design Guide and shall be MASH compliant. Additionally, any temporary barrier anchored into to new structures should be placed with cast in place inserts. No drilling into new decks will be allowed to anchor temporary barrier. Temporary barrier for traffic control shall conform to the requirements of RIDOT TAC – 0349.